

DALTON ROAD

CONST. CONC. STREET HEADER
AND CONN. TO EXIST. ASPH. PVMT.

2
43,560 S.F.
1.00 ACRES
FUTURE PARSONAGE

BLOCK A
1
153,266 S.F.
3.52 ACRES

PAD 544.50
PROPOSED
FAMILY LIFE CENTER

FUTURE SANCTUARY

2" HACKBERRY
TO BE REMOVED

TEMPORARY ROCK
TURNAROUND

END CONC. PVMT.

FIRE LANE PAVING TO BE
6" - 3500psi CONCRETE WITH
MINIMUM 6% LIME STABILIZED
6" SUB-GRADE.

STATE HWY. 205

INSTALL:
66 L.F. 18" CMP
W/TXDOT HDWLS.
NOTE:
CONTRACTOR TO OBTAIN A
TXDOT PERMIT BEFORE
INSTALLING 18" CMP &
HDWLS.

AS BUILT



8/00

TREE LIST

1-16" CEDAR
1-24" HACKBERRY
40' TOTAL

REPLACEMENT TREES

14-3" RED OAKS

B.M.
CITY OF ROCKWALL MONUMENT
LOCATED N 71° 57' 13" W 15.3'
FROM THE MOST NORTHERLY
NORTHEAST CORNER OF LOT 1
ELEV.: 542.98

REVISION DESCRIPTION		DATE	SCALE	DESIGN	DRAWN
REV. JMA		8/8/00	1" = 30'	H.L.E.	
REV.		3/3/99			
REV.		12/29/98			
HAROLD L. EVANS CONSULTING ENGINEER P.O. BOX 28355 2331 GUS THOMASSON ROAD, SUITE 102 DALLAS, TEXAS 75228, (214) 328-8133					
GRADING AND PAVING PLAN THE FREE METHODIST CHURCH OF NORTH AMERICA ADDITION CITY OF ROCKWALL					
SHEET NO. 4					
JOB NO. 9878					