



CASE COVER SHEET

City of Rockwall
Planning and Zoning Department
385 S. Goliad Street
Rockwall, Texas 75087

PLANNING & ZONING CASE NO.

PLANNING & ZONING FEE

PLATTING APPLICATION

- MASTER PLAT
- PRELIMINARY PLAT
- FINAL PLAT
- REPLAT
- AMENDING OR MINOR PLAT
- PLAT REINSTATEMENT REQUEST

SITE PLAN APPLICATION

- SITE PLAN
- AMENDED SITE PLAN/ELEVATIONS/LANDSCAPING

ZONING APPLICATION

- ZONING CHANGE
- SPECIFIC USE PERMIT
- PD DEVELOPMENT PLAN

OTHER APPLICATION

- TREE REMOVAL
- VARIANCE REQUEST/SPECIAL EXCEPTIONS

RECORD OF RECOMMENDATIONS, VOTING RECORDS, AND CONDITIONS OF APPROVAL

ARCHITECTURE REVIEW BOARD

PLANNING AND ZONING COMMISSION

CITY COUNCIL READING #1

CITY COUNCIL READING #2

CONDITIONS OF APPROVAL

NOTES



DEVELOPMENT APPLICATION

City of Rockwall
Planning and Zoning Department
385 S. Goliad Street
Rockwall, Texas 75087

STAFF USE ONLY
PLANNING & ZONING CASE NO.

NOTE: THE APPLICATION IS NOT CONSIDERED ACCEPTED BY THE CITY UNTIL THE PLANNING DIRECTOR AND CITY ENGINEER HAVE SIGNED BELOW.

DIRECTOR OF PLANNING:

CITY ENGINEER:

PLEASE CHECK THE APPROPRIATE BOX BELOW TO INDICATE THE TYPE OF DEVELOPMENT REQUEST (SELECT ONLY ONE BOX):

PLATTING APPLICATION FEES:

- MASTER PLAT (\$100.00 + \$15.00 ACRE) ¹
- PRELIMINARY PLAT (\$200.00 + \$15.00 ACRE) ¹
- FINAL PLAT (\$300.00 + \$20.00 ACRE) ¹
- REPLAT (\$300.00 + \$20.00 ACRE) ¹ (\$565.72)
- AMENDING OR MINOR PLAT (\$150.00)
- PLAT REINSTATEMENT REQUEST (\$100.00)

SITE PLAN APPLICATION FEES:

- SITE PLAN (\$250.00 + \$20.00 ACRE) ¹
- AMENDED SITE PLAN/ELEVATIONS/LANDSCAPING PLAN (\$100.00)

ZONING APPLICATION FEES:

- ZONING CHANGE (\$200.00 + \$15.00 ACRE) ¹
- SPECIFIC USE PERMIT (\$200.00 + \$15.00 ACRE) ^{1&2}
- PD DEVELOPMENT PLANS (\$200.00 + \$15.00 ACRE) ¹

OTHER APPLICATION FEES:

- TREE REMOVAL (\$75.00)
- VARIANCE REQUEST/SPECIAL EXCEPTIONS (\$100.00) ²

NOTES:

¹: IN DETERMINING THE FEE, PLEASE USE THE EXACT ACREAGE WHEN MULTIPLYING BY THE PER ACRE AMOUNT. FOR REQUESTS ON LESS THAN ONE ACRE, ROUND UP TO ONE (1) ACRE.

²: A \$1,000.00 FEE WILL BE ADDED TO THE APPLICATION FEE FOR ANY REQUEST THAT INVOLVES CONSTRUCTION WITHOUT OR NOT IN COMPLIANCE TO AN APPROVED BUILDING PERMIT.

PROPERTY INFORMATION [PLEASE PRINT]

ADDRESS NWC of Hwy 205 and Future FM 549

SUBDIVISION Creekside Commons LOT 15,16 & 18 BLOCK A

GENERAL LOCATION NWC of Hwy 205 and Future FM 549

ZONING, SITE PLAN AND PLATTING INFORMATION [PLEASE PRINT]

CURRENT ZONING Commercial (C) CURRENT USE Undeveloped

PROPOSED ZONING Commercial (C) PROPOSED USE Restaurant w/ drive-through

ACREAGE 13.286 LOTS [CURRENT] 15,16 & 18 LOTS [PROPOSED] 19,20 & 21

SITE PLANS AND PLATS: BY CHECKING THIS BOX YOU ACKNOWLEDGE THAT DUE TO THE PASSAGE OF HB3167 THE CITY NO LONGER HAS FLEXIBILITY WITH REGARD TO ITS APPROVAL PROCESS, AND FAILURE TO ADDRESS ANY OF STAFF'S COMMENTS BY THE DATE PROVIDED ON THE DEVELOPMENT CALENDAR WILL RESULT IN THE DENIAL OF YOUR CASE.

OWNER/APPLICANT/AGENT INFORMATION [PLEASE PRINT/CHECK THE PRIMARY CONTACT/ORIGINAL SIGNATURES ARE REQUIRED]

<input type="checkbox"/> OWNER	Creekside Commons Crossing LP	<input checked="" type="checkbox"/> APPLICANT	The Dimension Group
CONTACT PERSON	Michael Hampton	CONTACT PERSON	Keaton Mai
ADDRESS	[REDACTED]	ADDRESS	[REDACTED]
CITY, STATE & ZIP	[REDACTED]	CITY, STATE & ZIP	[REDACTED]
PHONE	[REDACTED]	PHONE	[REDACTED]
E-MAIL	[REDACTED]	E-MAIL	[REDACTED]

NOTARY VERIFICATION [REQUIRED]

BEFORE ME, THE UNDERSIGNED AUTHORITY, ON THIS DAY PERSONALLY APPEARED Michael Hampton [OWNER] THE UNDERSIGNED, WHO STATED THE INFORMATION ON THIS APPLICATION TO BE TRUE AND CERTIFIED THE FOLLOWING:


I HEREBY CERTIFY THAT I AM THE OWNER FOR THE PURPOSE OF THIS APPLICATION; ALL INFORMATION SUBMITTED HEREIN IS TRUE AND CORRECT; AND THE APPLICATION FEE OF \$ 565.72 TO COVER THE COST OF THIS APPLICATION, HAS BEEN PAID TO THE CITY OF ROCKWALL ON THIS THE 16th DAY OF JANUARY, 2026 BY SIGNING THIS APPLICATION, I AGREE THAT THE CITY OF ROCKWALL (I.E. "CITY") IS AUTHORIZED AND PERMITTED TO PROVIDE INFORMATION CONTAINED WITHIN THIS APPLICATION TO THE PUBLIC. THE CITY IS ALSO AUTHORIZED AND PERMITTED TO REPRODUCE ANY COPYRIGHTED INFORMATION SUBMITTED IN CONJUNCTION WITH THIS APPLICATION, IF SUCH REPRODUCTION IS ASSOCIATED OR IN RESPONSE TO A REQUEST FOR PUBLIC INFORMATION."

GIVEN UNDER MY HAND AND SEAL OF OFFICE ON THIS THE 16th DAY OF January, 2026

OWNER'S SIGNATURE

[Signature of Michael Hampton]
[Signature of Kathy Granberg]

NOTARY PUBLIC IN AND FOR THE STATE OF TEXAS





CHECKLIST FOR PLAT SUBMITTALS

City of Rockwall
 Planning and Zoning Department
 385 S. Goliad Street
 Rockwall, Texas 75087

Case Type:

- Minor/Amending Plat
- Final Plat
- Master Plat
- Replat
- Preliminary Plat
- Vacation Plat

Case Number

Reviewed By:

Review Date:




GENERAL REFERENCE: Chapter 38.7, *Subdivision and Platting Procedures*, of the Municipal Code of Ordinances

NOTES: The requirements listed below are applicable to all platting case types, unless otherwise indicated in the '[]' below the requirement description. On the checklist below a Replat, Minor Subdivision Plat, and Vacation Plat would be required to meet all the same requirements as a Final Plat.

Requirements	✓= OK	N/A	Comments
Case Number	<input type="checkbox"/>	<input type="checkbox"/>	The case number will be provided by staff and placed in the lower right-hand corner of all new submittals.
Items Necessary for Plat Review:			
✓ Plat	<input checked="" type="checkbox"/>	<input type="checkbox"/>	[Final Plat, Preliminary Plat & Master Plat]
✓ Treescape Plan	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	If Applicable [Final Plat & Preliminary Plat]
✓ Landscape Plan	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	If Applicable [Final Plat & Preliminary Plat]
✓ Parks and Open Space Plan	<input type="checkbox"/>	<input checked="" type="checkbox"/>	If Applicable [Preliminary Plat & Master Plat]
✓ Preliminary Drainage Plan	<input type="checkbox"/>	<input checked="" type="checkbox"/>	If Applicable [Preliminary Plat]
✓ Preliminary Utility Plan	<input type="checkbox"/>	<input checked="" type="checkbox"/>	If Applicable [Preliminary Plat]
✓ Plat Reinstatement Request	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Check w/ Planning Staff
Submittal Requirements	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Two (2) large (18" x 24") folded copies and one (1) PDF digital copy of each plat is required at the time of submittal.
Engineering Information [Final Plat]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Provide accurate plat dimensions with all engineering information necessary to reproduce the plat on the ground. ENGINEERING SUBMITTAL AND APPROVAL REQUIRED PRIOR TO SUBMITTING AN APPLICATION FOR FINAL PLAT.
Title Block	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Provide the appropriate title block information in the lower right-hand corner as referenced in Chapter 38.7, <i>Subdivision and Platting Procedures</i> , of the Municipal Code of Ordinances.
Owner, Developer, and/or Surveyor/Engineer (Name/Address/Phone Number/Date of Preparation)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	This includes the names and addresses of the subdividers, record owner, land planner, engineer and/or surveyor. The date of plat preparation should also be put in the lower right-hand corner.
Survey Monuments/State Plane Coordinates	<input checked="" type="checkbox"/>	<input type="checkbox"/>	The location of the development is required to be tied to a Rockwall monument, or tie two (2) corners to state plan coordinates (NAD 83 State Plane Texas, North Central [7202], US Survey Feet).
Vicinity Map	<input checked="" type="checkbox"/>	<input type="checkbox"/>	A Vicinity Map should show the boundaries of the proposed subdivision relative to the rest of the city at an appropriate scale to determine the general location of the area being platted.
North Point or North Arrow	<input checked="" type="checkbox"/>	<input type="checkbox"/>	The north point or north arrow must be facing true north on all plans, unless the scale of the drawings or scope of the project requires a different position.
Numeric and Graphic Scale	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Subdivision plats should be drawn to an Engineering Scale of 1"=50', 1"=100', etc...
Subdivision (Boundary, Acreage, and Square Footage)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Indicate the subdivision boundary lines, and acreage and square footage. For Master Plats provide a schematic layout of the entire tract to be subdivided, any remainder tracts and its relationship to adjacent property and existing adjoining developments.
Lot and Block (Designation, Width, Depth and Area)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Identification of each lot and block by number or letter. For each lot indicate the square footage and acreage or provide a calculation sheet. Also provide a total lot count.
Dwelling Units/Population Density [Preliminary & Master Plat]	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate the proposed number of <i>Dwelling Units</i> and the proposed <i>Population Density</i> (i.e. the total number of <i>Dwelling Units/Total Acreage = Population Density</i>).
Building Setbacks (Residential Plats <u>ONLY</u>)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Label the building lines where adjacent to a street.
Easements	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Label all existing and proposed easements relative to the site and include the type, purpose and width.


City Limits/Limits of the Extraterritorial Jurisdiction (ETJ)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	If contiguous with the area being platted or if visible on the vicinity map, the corporate limits of the City of Rockwall and its Extraterritorial Jurisdiction (ETJ) should be clearly labeled.
Utilities (P) [Preliminary Plat]	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate the locations of all existing and proposed utilities. Include the size and type of each.
Property Lines	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Provide all the proposed and platted property lines.
Streets	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Label all proposed and existing streets with the proposed or approved names. For Master Plats indicate the existing arterials and collector streets to serve the land to be platted consistent with the Thoroughfare Plan or proposed amendments.
Right-Of-Way and Centerline	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Label the right-of-way width and street centerline for each street both within and adjacent to the development.
Additional Right-Of-Way	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate the location and dimensions of any proposed right-of-way dedication.
Corner Clips	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate all existing and proposed corner clips and any subsequent dedication.
Median Openings [Preliminary Plat]	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Locate and identify existing and/or proposed median openings and left turn channelization.
Topographical Contours [Preliminary Plat & Master Plat]	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Topographical information and physical features to include contours at 2-foot intervals.
Drainage Areas [Preliminary Plat & Master Plat]	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Show all drainage areas and all proposed storm drainages areas with sizes if applicable.
Wooded Areas [Preliminary Plat & Master Plat]	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate the boundaries of all Wooded Areas or dense tree clusters.
Zoning and Land Use Information [Preliminary Plat & Master Plat]	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate the Zoning classifications, and the existing and proposed Land Uses.
Existing Man-Made Features [Master Plat]	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate all significant man-made features such as railroad, roads, buildings, utilities or other physical structures as shown on USGS topographic maps, utility company records and city records when such features affect the plans.
Parks and Open Space [Preliminary Plat & Master Plat]	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Identify the dimensions, names, and description of all existing and proposed public and private Parks and Open Spaces. Also, indicate the dimensions, names, and descriptions of all schools and other public uses. A Master Plat shall be accompanied by a Parks and Open Space Plan that shows all proposed trails, parks and open space and any proposed amenities for these private and public uses of land and indicate the phase of completion.
Proposed Improvements [Preliminary Plat]	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate how the proposed improvements would relate to those in the surrounding area.
Water Sources [Preliminary Plat]	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate water sources inside the city limits or in the extraterritorial jurisdiction (ETJ).
Sewage Disposal [Preliminary Plat]	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate sewage disposal method inside the city limits or in the extraterritorial jurisdiction (ETJ).
Adjacent Properties	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Record owners of contiguous parcels of subdivided land, names and lot patterns of contiguous subdivisions, approved Concept Plans, reference recorded subdivision plats adjoining platted land by record name and by deed record volume and page.
Phasing Plan [Master Plat]	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Delineation of the boundary of each phase for a proposed subdivision, the order of the development of each phase, and a schedule for the development of each phase.
Dedication	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate the boundary lines, dimensions and descriptions, of spaces to be dedicated for public use of the inhabitants of the development.
Flood Elevations	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Show 100-Year & 50-Year floodplain and floodway boundaries (if applicable).
Wetlands and Waters of the U.S	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Indicate the boundary lines of delineated Wetlands and Water of the United States (WOTUS) (if applicable).
Statement of Service [Master Plat]	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Provide a detailed statement of how the proposed subdivision will be served by water, wastewater, roadway and drainage facilities that have adequate capacity to serve the development.
Legal Description	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Place the Legal Description (Metes and Bounds Description/Field Notes) where indicated in the Owner's Certificate per the application packet.
General Notes	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Provide the following General Notes provided in the Standard Plat Wording section of the application packet: (1) Subdivider's Statement (2) Public Improvement Statement (3) Drainage and Detention Easements (4) Fire Lanes (5) Street Appurtenances

Purpose [Conveyance Plat]	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Provide the purpose of the conveyance plat under the General Notes section of the plat.
Owner's Certificate of Dedication	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Provide the Owner's Certificate of Dedication for all public right-of-way, easements, parks and open space, and other public uses provided in the <i>Standard Plat Wording</i> section of the application packet.
Notary Public Signature Block	<input checked="" type="checkbox"/>	<input type="checkbox"/>	All signatures on the Owner's Certificate of Dedication shall be required to be acknowledged by a notary public. The Notary Public Signature Block is provided in the <i>Standard Plat Wording</i> section of the application packet.
Surveyor's/Registered Engineer Certificate	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Required to have the seal and signature of surveyor or registered engineer responsible for the surveying the development and/or the preparation of the plat. The Surveyor's/Registered Engineer Certificate is provided in the <i>Standard Plat Wording</i> section of the application packet.
Profiles and Cross Sections for Floodplains	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Profiles and cross sections of all floodplains shall be shown on the subdivision plat at a minimum distance of 300-feet in order to determine that the subdivision plat will function in accordance with the City's <i>Standards of Design and Construction</i> . These profiles and cross sections shall contain the elevations and source of data for the information provided (if applicable).
Signature Block	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Provide the appropriate standard signature block(s) for approval of the plat provided in the <i>Standard Plat Wording</i> section of the application packet.
Compliance with Preliminary Plat	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Does the plat comply with all the special requirements developed in the preliminary plat review?
Review Plans with Franchise Utility Companies	<input checked="" type="checkbox"/>	<input type="checkbox"/>	It is the applicant's responsibility to review the proposed plans and plat with any private utility companies such as electric, gas, cable, trash and telecommunications companies.



CURVE #	LENGTH	RADIUS	DELTA	CHORD
C1	81.75'	1155.00'	4°03'19"	S58° 43' 21"W 81.73'
C2	160.34'	1110.00'	8°16'36"	S56° 38' 44"W 160.20'
C3	28.00'	36.00'	44°33'46"	S66° 35' 16"W 27.30'

LINE #	LENGTH	DIRECTION
L1	114.68'	S33°19'17"E
L2	25.09'	S29°29'58"E
L3	269.61'	S44°06'48"W
L4	228.23'	N45°52'18"W
L5	269.64'	N44°08'20"E
L6	22.85'	N45°51'55"W
L7	121.80'	N1°07'51"W
L8	217.17'	S1°14'47"E
L9	45.15'	S88°52'09"W
L10	21.83'	S44°43'37"W
L11	169.64'	N45°51'55"W
L12	81.31'	S45°51'55"E



LEGEND:

IRF IRON ROD FOUND
PC "TXDOT" IRON ROD FOUND WITH PINK CAP STAMPED "TXDOT"
YC "TXHS" IRON ROD FOUND WITH YELLOW CAP STAMPED "TXHS"
IRS IRON ROD SET WITH YELLOW CAP STAMPED "TXHS"
-CM- CONTROLLING MONUMENT
D.R.R.C.T. DEED RECORDS, ROCKWALL COUNTY, TEXAS
M.R.R.C.T. MAP RECORDS, ROCKWALL COUNTY, TEXAS
O.P.R.R.C.T. OFFICIAL PUBLIC RECORDS, ROCKWALL COUNTY, TEXAS
INST. NO. INSTRUMENT NUMBER
VOL., PG. VOLUME, PAGE

ENGINEER
THE DIMENSION GROUP
10755 SANDHILL ROAD
DALLAS, TEXAS 75238
attn: KEATON MAI

OWNER
CREEKSIDE COMMONS CROSSING, LP
10755 SANDHILL ROAD
DALLAS, TEXAS 75238



SURVEYOR
TEXAS HERITAGE
SURVEYING, LLC

10610 Metric Drive, Suite 124, Dallas, TX 75243
Office 214-340-9700 Fax 214-340-9710
txheritage.com
Firm No. 10169300

FINAL PLAT
LOTS 19-21, BLOCK A
CREEKSIDE COMMONS ADDITION
BEING A REPLAT OF
LOTS 15, 16, & 18, BLOCK A,
CREEKSIDE COMMONS ADDITION
BEING 3 LOTS
13.286 ACRES / 578,731 SF
SITUATED IN THE
W. W. FORD SURVEY, ABSTRACT NO. 80
CITY OF ROCKWALL, ROCKWALL COUNTY, TEXAS

PARCEL CURVE TABLE				
CURVE #	LENGTH	RADIUS	DELTA	CHORD
C4	28.00'	36.00'	44°33'46"	S66° 35' 16"W 27.30'
C5	5.02'	25.00'	11°30'57"	N5° 51' 30"W 5.02'
C6	39.77'	25.00'	91°09'19"	S45° 40' 41"E 35.71'
C7	39.22'	25.00'	89°53'04"	S43° 48' 41"W 35.32'
C8	47.03'	20.00'	134°44'04"	S21° 30' 07"W 36.92'
C9	28.32'	20.00'	81°08'24"	S86° 26' 06"E 26.02'
C10	21.46'	49.00'	25°05'14"	N65° 32' 19"E 21.28'
C11	9.22'	49.00'	10°47'12"	N83° 28' 33"E 9.21'

PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L16	15.00'	N44°07'42"E
L17	52.07'	N45°52'18"W
L18	20.00'	N45°54'27"W
L19	51.04'	N43°59'07"E
L20	22.38'	N1°00'53"W
L21	153.66'	N43°59'07"E
L22	11.87'	N45°30'22"W
L23	19.90'	N44°29'38"E
L24	11.70'	S46°00'53"E
L25	31.45'	N43°59'07"E

PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L26	35.20'	N46°00'53"W
L27	20.00'	N44°08'05"E
L28	35.15'	S45°51'55"E
L29	12.34'	N43°59'07"E
L30	35.29'	N88°52'09"E
L31	5.01'	N1°06'12"W
L32	20.00'	N88°52'09"E
L33	5.00'	S1°06'12"E
L34	453.33'	N88°52'09"E
L35	301.80'	S54°13'54"E



PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L36	18.16'	S29°14'52"E
L37	20.00'	S60°45'12"W
L38	13.73'	S29°14'52"E
L39	290.70'	N54°13'54"W
L40	493.69'	S88°52'09"W
L41	220.81'	S43°59'07"W
L42	22.38'	S1°00'53"E
L43	59.36'	S43°59'07"W
L44	134.56'	N88°52'09"E
L45	20.01'	N2°38'25"W

PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L46	586.72'	S88°52'09"W
L47	20.00'	S1°13'55"E
L48	25.89'	S44°06'48"W
L49	10.00'	S44°06'48"W
L50	16.89'	N45°53'12"W
L51	15.09'	S89°06'48"W
L52	200.57'	N45°53'12"W
L53	10.32'	N44°08'20"E
L54	196.43'	S45°47'38"E
L55	15.09'	N89°06'48"E


PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L56	21.03'	S45°53'12"E
L57	12.00'	N88°45'13"E
L58	193.03'	N88°45'13"E
L59	5.00'	S1°14'47"E
L60	192.63'	S88°45'13"W
L61	168.03'	N88°45'13"E
L62	24.00'	S1°14'47"E
L63	168.18'	S88°45'13"W
L64	74.45'	N1°07'51"W
L65	10.00'	N88°45'13"E

PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L66	182.71'	S1°14'47"E
L67	9.99'	S88°52'09"W
L68	12.02'	S1°14'47"E
L69	34.64'	S88°52'09"W
L70	71.67'	N45°51'55"W
L71	44.60'	N88°52'09"E
L72	11.98'	S1°14'47"E

PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L13	22.85'	N45°51'55"W
L14	45.15'	S88°52'09"W
L15	21.83'	S44°43'37"W




- LEGEND:
- IRF IRON ROD FOUND
 - PC "TXDOT" IRON ROD FOUND WITH PINK CAP STAMPED "TXDOT"
 - IRS IRON ROD SET WITH YELLOW CAP STAMPED "TXHS"
 - <CM> CONTROLLING MONUMENT
 - D.R.R.C.T. DEED RECORDS, ROCKWALL COUNTY, TEXAS
 - M.R.R.C.T. MAP RECORDS, ROCKWALL COUNTY, TEXAS
 - O.P.R.R.C.T. OFFICIAL PUBLIC RECORDS, ROCKWALL COUNTY, TEXAS
 - INST. NO. INSTRUMENT NUMBER
 - VOL., PG. VOLUME, PAGE
 - ESMT. EASEMENT
 - WSEL WATER SURFACE ELEVATION
 - MIN. F.F.E. MINIMUM FINISHED FLOOR ELEVATION



BLOCK 1
SOMERSET PARK
INST. NO. 2018000001707
O.P.R.R.C.T.

BLOCK A
EDWARDS ACRES SUBDIVISION
INST. NO. 2014000006510
O.P.R.R.C.T.



SYLVANPARK DRIVE
(83' RIGHT-OF-WAY)

SANITARY SEWER ESMT.
INST. NO. 2017000002409
O.P.R.R.C.T.


10' ELECTRIC &
TELEPHONE ESMT.
INST. NO. 2014000006510
O.P.R.R.C.T.

15' WATER LINE ESMT.
INST. NO. 2014000006510
O.P.R.R.C.T.

BLOCK A
EDWARDS ACRES SUBDIVISION
INST. NO. 2014000006510
O.P.R.R.C.T.

10' ELECTRIC &
TELEPHONE ESMT.
INST. NO. 2014000006510
O.P.R.R.C.T.

15' WATER LINE ESMT.
INST. NO. 2014000006510
O.P.R.R.C.T.



STATE HIGHWAY 549
(VARIABLE WIDTH RIGHT-OF-WAY)

N 88°45'13" E 1358.95'

100-YR WSEL = 519.58

15' BUILDING LINE
INST. NO. 20230000008813
O.P.R.R.C.T.

LOT 21
476,460 SQ. FT.
10.938 ACRES
MIN. F.F.E. = 528.93

DETENTION ESMT.
INST. NO. 2024000004925
O.P.R.R.C.T.

SANITARY SEWER ESMT.
INST. NO. 2015000003475
D.R.R.C.T.


15' WATER PIPELINE ESMT.
R.C.H. WATER SUPPLY CORP.
VOL. 64, PG. 319
D.R.R.C.T.

MIN. F.F.E. = 521.54

20' LANDSCAPE BUFFER
INST. NO. 20230000008813
O.P.R.R.C.T.

MATCH LINE PG 2

WILLIAM W. FORD SURVEY,
ABSTRACT NO. 80



100-YR WSEL = 526.93

SANITARY SEWER ESMT.
INST. NO. 2015000003475
D.R.R.C.T.

20' WATER ESMT.
INST. NO. 20230000008813
O.P.R.R.C.T.

30' WASTEWATER ESMT.
INST. NO. 20230000008813
O.P.R.R.C.T.

100-YR WSEL = 518.87

10' UTILITY ESMT.
INST. NO. 20230000008813
O.P.R.R.C.T.

25' BUILDING LINE
INST. NO. 20230000008813
O.P.R.R.C.T.

CH=S58°43'21"W 81.73'
L=81.75', R=1155.00'
A=4°03'19"

CREEKSIDE COMMONS ADDITION
BLOCK A

578,731 SQ. FT.
13.286 ACRES

CREEKSIDE COMMONS CROSSING, LP
INST. NO. 20220000021201
O.P.R.R.C.T.


20' DRAINAGE ESMT.
INST. NO. 2024000004925
O.P.R.R.C.T.

1/2" IRF
YC *TXHS*
S 29°29'58" E
25.09'

STATE HIGHWAY 549
(VARIABLE WIDTH RIGHT-OF-WAY)

MATCH LINE PG 5

MATCH LINE PG 2



VISIBILITY ESMT.
INST. NO. 2024000004925
O.P.R.R.C.T.

VISIBILITY ESMT.
INST. NO. 2024000004925
O.P.R.R.C.T.

1/2" IRF
YC 'SUMMIT'

STATE OF TEXAS
INST. NO. 20180000021509
O.P.R.R.C.T.

STATE HIGHWAY 205
(VARIABLE WIDTH RIGHT-OF-WAY)

STATE OF TEXAS
INST. NO. 20210000017067
O.P.R.R.C.T.

VISIBILITY ESMT.
INST. NO. 2024000004925
O.P.R.R.C.T.

VISIBILITY ESMT.
INST. NO. 2024000004925
O.P.R.R.C.T.

1/2" IRF
YC 'SUMMIT'

STATE OF TEXAS
INST. NO. 20180000021509
O.P.R.R.C.T.

STATE HIGHWAY 205
(VARIABLE WIDTH RIGHT-OF-WAY)

STATE OF TEXAS
INST. NO. 20210000017067
O.P.R.R.C.T.

20' DRAINAGE ESMT.
INST. NO. 2024000004925
O.P.R.R.C.T.

LOT 14
BLOCK A
CREEKSIDE COMMONS
INST. NO. 2024000004925
O.P.R.R.C.T.

24' FIRELANE, ACCESS,
& UTILITY ESMT.
INST. NO. 20230000008813
O.P.R.R.C.T.

549 CROSSING, LP
INST. NO. 20210000028395
O.P.R.R.C.T.

LOT 1
BLOCK A
CREEKSIDE COMMONS
INST. NO. 20230000008813
O.P.R.R.C.T.

15' UTILITY ESMT.
INST. NO. 20230000008813
O.P.R.R.C.T.

25' BUILDING LINE
INST. NO. 20230000008813
O.P.R.R.C.T.

20' LANDSCAPE BUFFER
INST. NO. 20230000008813
O.P.R.R.C.T.

DETENTION ESMT.
INST. NO. 20230000008813
O.P.R.R.C.T.

GENERAL NOTES:

1) Subdivider's Statement: Selling a portion of this addition by metes and bounds is unlawful and a violation of the Subdivision Ordinance of the City of Rockwall and Chapter 212, Municipal Regulation of Subdivisions and Property Development, of the Texas Local Government Code, and shall be subject to the City of Rockwall withholding utilities and building permits.

2) Public Improvement Statement: It shall be the policy of the City of Rockwall to withhold issuing building permits until all streets, water, sewer and storm drainage systems have been accepted by the City. The approval of a subdivision plat by the City does not constitute any representation, assurance or guarantee that any building within such plat shall be approved, authorized or permit issued, nor shall such approval constitute any representation, assurance or guarantee by the City of Rockwall of the adequacy and availability for water and sanitary sewer for personal use and fire protection within such subdivision plat, as required under the Subdivision Ordinance of the City of Rockwall.

3) Drainage and Detention Easements: Property owner shall be responsible for maintaining, repairing, and replacing and shall bear sole liability of all systems within the drainage and detention easements.

4) Fire Lanes: All Fire Lanes will be constructed, maintained, repaired and replaced by the property owner. Fire Lanes shall be constructed in accordance with the approved Civil Engineering Plans for both on-site and off-site Fire Lane improvements.

5) Street Appurtenances: All decorative signage, posts, or lights installed in public right-of-way shall be installed, maintained, repaired, and replaced by the homeowner's association (HOA).

6) Bearings are based upon the Texas State Plane Coordinate System, Texas North Central Zone (4202), North American Datum of 1983 (2011).

7) The purpose of this replat is to create easements and change lot boundary lines.

8) Benchmarks:

COR-8: Aluminum disk stamped "City of Rockwall Survey Monument" at the northerly intersection of Silver View Lane and Diamond Way Drive ± 1 foot north of curb line in center of curve.
N= 7,018,063.113; E= 2,609,533.682; Elevation= 600.48'

COR-9: Brass disk stamped "City of Rockwall Survey Monument" on the south side of Discovery Boulevard at the southeaster corner of curb inlet ± 180 feet east intersection of Discovery/Corporate.
N= 7,020,550.132; E= 2,607,463.893; Elevation= 595.63'


9) Zoning: Commercial (C) District

10) Base Flood Elevation information per FEMA GIS, FIRM Panel #48397C0045L.

11) All Visibility Easements are 30'x30' unless otherwise noted.

12) WSEL information based upon Floodplain / Detention Study NDMCE No. 23-014 by Nathan D. Maier Consulting Engineers, Inc. completed December of 2023.

MATCH LINE PG 5



MATCH LINE PG 3

OWNER'S CERTIFICATE:

STATE OF TEXAS
COUNTY OF ROCKWALL

WHEREAS, Creekside Commons Crossing, LP is the owner of that tract of land situated in the William W. Ford Survey, Abstract No. 80, City of Rockwall, Rockwall County, Texas, being Lots 15, 16, & 18, Block A of Creekside Commons, an addition to the City of Rockwall, Rockwall County, Texas according to the plat thereof recorded in Instrument Number 2024000004925 of the Official Public Records of Rockwall County, Texas, and being a part of that tract of land described in Special Warranty Deed to Creekside Commons Crossing, LP recorded in Instrument Number 2022000021201 of the Official Public Records of Rockwall County, Texas, and being more particularly described by metes and bounds as follows:

Commencing at a 1/2 inch iron rod with yellow plastic cap stamped "TXHS" found for corner, said corner being in the northeast corner of that tract of land described as Parcel 1 Part 1 in deed to the State of Texas recorded in Instrument Number 2018000021509 of the Official Public Records of Rockwall County, Texas, said corner also being the northwest corner of Lot 17, Block A of said Creekside Commons Addition, said corner also being in the south right-of-way line of existing State Highway 549 (variable width right-of-way);

Thence North 88 degrees 45 minutes 13 seconds East, along the south right-of-way line of said existing State Highway 549, a distance of 491.43 feet to an "X" found for corner, said corner being the northeast corner of said Lot 17, Block A, said corner being the POINT OF BEGINNING;

Thence North 88 degrees 45 minutes 13 seconds East, along the south right-of-way line of said existing State Highway 549, a distance of 1,358.95 feet to a 5/8 inch iron rod with pink plastic cap stamped "TXDOT" found for corner, said corner being the northwest corner of that tract of land described as Parcel 1 Part 2 in deed to the State of Texas recorded in Instrument Number 2018000021509 of the Official Public Records of Rockwall County, Texas, said corner also being the most northerly northeast corner of said Lot 18, Block A, said corner also being in a northwest right-of-way line of new State Highway 549 (variable width right-of-way);

Thence, along the northwest line of said State of Texas Parcel 1 Part 2 tract and along the northwest line of said new State Highway 549, the following courses and distances:

Thence South 33 degrees 19 minutes 17 seconds East, a distance of 114.68 feet to a 1/2 inch iron rod with yellow plastic cap stamped "TXHS" found for corner, said corner being the beginning of a non-tangent curve to the right, having a delta of 04 degrees 03 minutes 19 seconds, a radius of 1,155.00 feet and a chord bearing and distance of South 58 degrees 43 minutes 21 seconds West, 81.73 feet;

Thence, in a southwesterly direction, along said curve to the right, an arc length of 81.75 feet to a 5/8 inch iron rod with pink plastic cap stamped "TXDOT" found for corner;

Thence South 60 degrees 46 minutes 14 seconds West, a distance of 382.65 feet to a 1/2 inch iron rod with yellow plastic cap stamped "TXHS" found for corner;

Thence South 29 degrees 29 minutes 58 seconds East, a distance of 25.09 feet to a 1/2 inch iron rod with yellow plastic cap stamped "TXHS" found for corner;

Thence South 60 degrees 45 minutes 08 seconds West, a distance of 437.07 feet to a "X" found for corner, said corner being the beginning of a non-tangent curve to the left, having a delta of 08 degrees 16 minutes 36 seconds, a radius of 1,110.00 feet and a chord bearing and distance of South 56 degrees 38 minutes 44 seconds West, 160.20 feet;

Thence, in a southwesterly direction, along said curve to the left, an arc length of 160.34 feet to a 1/2 inch iron rod with yellow plastic cap stamped "TXHS" found for corner, said corner being the east corner of Lot 1, Block A of said Creekside Commons, an addition to the City of Rockwall, Rockwall County, Texas according to the plat thereof recorded in Instrument Number 2023000008813 of the Official Public Records of Rockwall County, Texas;

Thence North 45 degrees 53 minutes 13 seconds West, along the northeast line of said Lot 1, Block A, a distance of 261.06 feet to an "X" found for corner, said corner being the north corner of said Lot 1, Block A, said corner also being the east corner of Lot 14, Block A of said Creekside Commons Addition (Inst. No. 2024000004925);

Thence North 45 degrees 51 minutes 55 seconds West, along the northeast line of said Lot 14, Block A, a distance of 202.16 feet to an "X" found for corner, said corner being the north corner of said Lot 14, Block A;

Thence South 44 degrees 06 minutes 48 seconds West, along the northwest line of said Lot 14, Block A, a distance of 269.61 feet to a 1/2 inch iron rod with cap stamped "SUMMIT" found for corner, said corner being the west corner of said Lot 14, Block A, said corner also being in the northeast line of said State of Texas Parcel 1 Part 1 tract;


Thence North 45 degrees 52 minutes 18 seconds West, along a northeast line of said State of Texas Parcel 1 Part 1 tract, a distance of 228.23 feet to a 1/2 inch iron rod with yellow plastic cap stamped "TXHS" found for corner, said corner being the south corner of said Lot 17, Block A;

Thence North 44 degrees 08 minutes 20 seconds East, along the southeast line of said Lot 17, Block A, a distance of 269.64 feet to an "X" found for corner, said corner being the east corner of said Lot 17, Block A;

Thence North 45 degrees 51 minutes 55 seconds West, along the easterly line of said Lot 17, Block A, a distance of 22.85 feet to an "X" found for corner;

Thence North 01 degrees 07 minutes 51 seconds West, along the easterly line of said Lot 17, Block A, a distance of 121.80 feet to the POINT OF BEGINNING and containing 578,731 square feet or 13.286 acres of land.

MATCH LINE PG 4



OWNER'S DEDICATION:

NOW THEREFORE, KNOW ALL MEN BY THESE PRESENTS:

STATE OF TEXAS
COUNTY OF ROCKWALL

I the undersigned owner of the land shown on this plat, and designated herein as the CREEKSIDE COMMONS ADDITION subdivision to the City of Rockwall, Texas, and whose name is subscribed hereto, hereby dedicate to the use of the public forever all streets, alleys, parks, water courses, drains, easements and public places thereon shown on the purpose and consideration therein expressed. I further certify that all other parties who have a mortgage or lien interest in the CREEKSIDE COMMONS ADDITION subdivision have been notified and signed this plat. I understand and do hereby reserve the easement strips shown on this plat for the purposes stated and for the mutual use and accommodation of all utilities desiring to use or using same. I also understand the following;

1. No buildings shall be constructed or placed upon, over, or across the utility easements as described herein.
2. Any public utility shall have the right to remove and keep removed all or part of any buildings, fences, trees, shrubs, or other growths or improvements which in any way endanger or interfere with construction, maintenance or efficiency of their respective system on any of these easement strips; and any public utility shall at all times have the right of ingress or egress to, from and upon the said easement strips for purposes of construction, reconstruction, inspecting, patrolling, maintaining, and either adding to or removing all or part of their respective system without the necessity of, at any time, procuring the permission of anyone.
3. The City of Rockwall will not be responsible for any claims of any nature resulting from or occasioned by the establishment of grade of streets in the subdivision.
4. The developer/property owner and subdivision engineer shall bear total responsibility for storm drain improvements.
5. The developer/property owner shall be responsible for the necessary facilities to provide drainage patterns and drainage controls such that properties within the drainage area are not adversely affected by storm drainage from the development.
6. No house dwelling unit, or other structure shall be constructed on any lot in this addition by the owner or any other person until the developer and/or owner has complied with all requirements of the Subdivision Regulations of the City of Rockwall regarding improvements with respect to the entire block on the street or streets on which property abuts, including the actual installation of streets with the required base and paving, curb and gutter, water and sewer, drainage structures, storm structures, storm sewers, and alleys, all according to the specifications of the City of Rockwall; or

Until an escrow deposit, sufficient to pay for the cost of such improvements, as determined by the city's engineer and/or city administrator, computed on a private commercial rate basis, has been made with the city secretary, accompanied by an agreement signed by the developer and/or owner, authorizing the city to make such improvements at prevailing private commercial rates, or have the same made by a contractor and pay for the same out of the escrow deposit, should the developer and/or owner fail or refuse to install the required improvements within the time stated in such written agreement, but in no case shall the City be obligated to make such improvements itself. Such deposit may be used by the owner and/or developer as progress payments as the work progresses in making such improvements by making certified requisitions to the city secretary, supported by evidence of work done; or

Until the developer and/or owner files a corporate surety bond with the city secretary in a sum equal to the cost of such improvements for the designated area, guaranteeing the installation thereof within the time stated in the bond, which time shall be fixed by the city council of the City of Rockwall.

I further acknowledge that the dedications and/or exaction's made herein are proportional to the impact of the Subdivision upon the public services required in order that the development will comport with the present and future growth needs of the City; I, my successors and assigns hereby waive any claim, damage or cause of action that I may have as a result of the dedication of exactions made herein.

Creekside Commons Crossing, LP

Jassem Setayesh
President/CEO

STATE OF TEXAS
COUNTY OF DALLAS

BEFORE ME, the undersigned authority, on this day personally appeared Jassem Setayesh, a Texas limited liability company, known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that he executed the same for the purposes and considerations therein stated.

GIVEN UNDER MY HAND AND SEAL OF OFFICE, this _____ day of _____, 2026.

Notary Signature

SURVEYORS CERTIFICATE:

I, J. R. January, do hereby certify that I prepared this plat from an actual and accurate survey of the land, and that the corner monuments shown thereon were properly placed under my personal supervision.

J. R. January, R.P.L.S. No. 5382

APPROVED: I hereby certify that the above and foregoing Subdivision Plat was reviewed by the Planning and Zoning Commission and approved by the City Council of the City of Rockwall, Texas for the preparation of a Final Plat on the _____ day of _____, 2026.

Mayor of the City of Rockwall

Planning and Zoning Chairman

City Secretary

City Engineer

ENGINEER
THE DIMENSION GROUP
10755 SANDHILL ROAD
DALLAS, TEXAS 75238
attn: KEATON MAI


OWNER
CREEKSIDE COMMONS CROSSING, LP
10755 SANDHILL ROAD
DALLAS, TEXAS 75238



SURVEYOR
TEXAS HERITAGE
SURVEYING, LLC
10610 Metric Drive, Suite 124, Dallas, TX 75243
Office 214-340-9700 Fax 214-340-9710
txheritage.com
Firm No. 10169300

FINAL PLAT
LOTS 19-21, BLOCK A
CREEKSIDE COMMONS ADDITION
BEING A REPLAT OF
LOTS 15, 16, & 18, BLOCK A,
CREEKSIDE COMMONS ADDITION
BEING 3 LOTS
13.286 ACRES / 578,731 SF
SITUATED IN THE
W. W. FORD SURVEY, ABSTRACT NO. 80
CITY OF ROCKWALL, ROCKWALL COUNTY, TEXAS

STATE HIGHWAY 549 (VARIABLE WIDTH RIGHT-OF-WAY)



LANDSCAPE CALCULATIONS

PERMITTING AUTHORITY: CITY OF ROCKWALL, TX
 ZONING: C
 ADJACENT ZONING: C

OVERALL
 TOTAL SITE AREA: 40,751 SF
 LANDSCAPE AREA REQUIRED: 8,150 SF (20% OF SITE AREA)
 LANDSCAPE AREA PROVIDED: 8,594 SF
 % OF REQ. AREA IN FRONT AND SIDE YARDS: 91.7% (MIN 50%)
 IMPERVIOUS AREA ON SITE: 32,157 SF

LANDSCAPE BUFFER ALONG S FM 549, MIN. WIDTH 10'
 LENGTH OF FRONTAGE: 192 LF (NOT INCL WIDTH OF DRIVEWAY)
 CANOPY TREES REQUIRED: 4 CANOPY TREES (1 PER 50 LF)
 CANOPY TREES PROVIDED: 4 CANOPY TREES
 ACCENT TREES REQUIRED: 4 ACCENT TREES (1 PER 50 LF)
 ACCENT TREES PROVIDED: 4 ACCENT TREES
 SHRUBS REQUIRED: 48 SHRUBS PROVIDED
 BERM REQUIRED: 30' BERM - SEE CIVIL PLANS FOR FINAL GRADES
 NOTE: ADDITIONAL SHRUBS HAVE BEEN ADDED TO PROVIDE AN ENHANCED SCREEN AT THE DRIVE THROUGH.

PARKING LOT HEAD LIGHT SCREENING
 PROVIDED AS REQUIRED.

PARKING LOT LANDSCAPING
 SIZE OF PARKING AND MANEUVERING AREA: 22,382 SF
 QUANTITY OF PARKING SPACES: 27 PARKING SPACES
 CANOPY TREES REQUIRED: 3 CANOPY TREES (1 PER 10 PARKING SPACES)
 CANOPY TREES PROVIDED: 3 CANOPY TREES
 NOTE: NO PARKING SPACE MAY BE MORE THAN 80 LF FROM THE TRUNK OF A CANOPY TREE.

GENERAL GRADING AND PLANTING NOTES

- BY SUBMITTING A PROPOSAL FOR THE LANDSCAPE PLANTING SCOPE OF WORK, THE CONTRACTOR CONFIRMS THAT HE HAS READ, AND WILL COMPLY WITH, THE ASSOCIATED NOTES, SPECIFICATIONS, AND DETAILS WITH THIS PROJECT.
- THE GENERAL CONTRACTOR IS RESPONSIBLE FOR REMOVING ALL EXISTING VEGETATION (EXCEPT WHERE NOTED TO REMAIN).
- IN THE CONTEXT OF THESE PLANS, NOTES, AND SPECIFICATIONS, "FINISH GRADE" REFERS TO THE FINAL ELEVATION OF THE SOIL SURFACE (NOT TOP OF MULCH) AS INDICATED ON THE GRADING PLANS.
 - BEFORE STARTING WORK, THE LANDSCAPE CONTRACTOR SHALL VERIFY THAT THE ROUGH GRADES OF ALL LANDSCAPE AREAS ARE WITHIN +/-0.1' OF FINISH GRADE. SEE SPECIFICATIONS FOR MORE DETAILED INSTRUCTION ON TURF AREA AND PLANTING BED PREPARATION.
 - CONSTRUCT AND MAINTAIN FINISH GRADES AS SHOWN ON GRADING PLANS, AND CONSTRUCT AND MAINTAIN SLOPES AS RECOMMENDED BY THE GEOTECHNICAL REPORT. ALL LANDSCAPE AREAS SHALL HAVE POSITIVE DRAINAGE AWAY FROM STRUCTURES AT THE MINIMUM SLOPE SPECIFIED IN THE REPORT AND ON THE GRADING PLANS, AND AREAS OF POTENTIAL PONDING SHALL BE REGRADED TO BLEND IN WITH THE SURROUNDING GRADES AND ELIMINATE PONDING POTENTIAL.
 - THE LANDSCAPE CONTRACTOR SHALL DETERMINE WHETHER OR NOT THE EXPORT OF ANY SOIL WILL BE NEEDED, TAKING INTO ACCOUNT THE ROUGH GRADE PROVIDED, THE AMOUNT OF SOIL AMENDMENTS TO BE ADDED (BASED ON A SOIL TEST, PER SPECIFICATIONS), AND THE FINISH GRADES TO BE ESTABLISHED.
 - ENSURE THAT THE FINISH GRADE IN SHRUB AREAS IMMEDIATELY ADJACENT TO WALKS AND OTHER WALKING SURFACES, AFTER INSTALLING SOIL AMENDMENTS, IS 3" BELOW THE ADJACENT FINISH SURFACE, IN ORDER TO ALLOW FOR PROPER MULCH DEPTH. TAPER THE SOIL SURFACE TO MEET FINISH GRADE, AS SPECIFIED ON THE GRADING PLANS, AT APPROXIMATELY 18" AWAY FROM THE WALKS.
 - ENSURE THAT THE FINISH GRADE IN TURF AREAS IMMEDIATELY ADJACENT TO WALKS AND OTHER WALKING SURFACES, AFTER INSTALLING SOIL AMENDMENTS, IS 1" BELOW THE FINISH SURFACE OF THE WALKS. TAPER THE SOIL SURFACE TO MEET FINISH GRADE, AS SPECIFIED ON THE GRADING PLANS, AT APPROXIMATELY 18" AWAY FROM THE WALKS.
 - SHOULD ANY CONFLICTS AND/OR DISCREPANCIES ARISE BETWEEN THE GRADING PLANS, GEOTECHNICAL REPORT, THESE NOTES AND PLANS, AND ACTUAL CONDITIONS, THE CONTRACTOR SHALL IMMEDIATELY BRING SUCH ITEMS TO THE ATTENTION OF THE LANDSCAPE ARCHITECT, GENERAL CONTRACTOR, AND OWNER.
- ALL PLANT LOCATIONS ARE DIAGRAMMATIC. ACTUAL LOCATIONS SHALL BE VERIFIED WITH THE LANDSCAPE ARCHITECT OR DESIGNER PRIOR TO PLANTING. THE LANDSCAPE CONTRACTOR SHALL ENSURE THAT ALL REQUIREMENTS OF THE PERMITTING AUTHORITY ARE MET (I.E., MINIMUM PLANT QUANTITIES, PLANTING METHODS, TREE PROTECTION METHODS, ETC.).
 - THE LANDSCAPE CONTRACTOR IS RESPONSIBLE FOR DETERMINING PLANT QUANTITIES; PLANT QUANTITIES SHOWN ON LEGENDS AND CALLOUTS ARE FOR GENERAL INFORMATION ONLY. IN THE EVENT OF A DISCREPANCY BETWEEN THE PLAN AND THE PLANT LEGEND, THE PLANT QUANTITY AS SHOWN ON THE PLAN (FOR INDIVIDUAL SYMBOLS) OR CALLOUT (FOR GROUNDCOVER PATTERNS) SHALL TAKE PRECEDENCE.
 - NO SUBSTITUTIONS OF PLANT MATERIALS SHALL BE ALLOWED WITHOUT THE WRITTEN PERMISSION OF THE LANDSCAPE ARCHITECT. IF SOME OF THE PLANTS ARE NOT AVAILABLE, THE LANDSCAPE CONTRACTOR SHALL NOTIFY THE LANDSCAPE ARCHITECT IN WRITING (VIA PROPER CHANNELS).
 - THE CONTRACTOR SHALL, AT A MINIMUM, PROVIDE REPRESENTATIVE PHOTOS OF ALL PLANTS PROPOSED FOR THE PROJECT. THE CONTRACTOR SHALL ALLOW THE LANDSCAPE ARCHITECT AND THE OWNER/OWNER'S REPRESENTATIVE TO INSPECT, AND APPROVE OR REJECT, ALL PLANTS DELIVERED TO THE JOBSITE. REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS FOR SUBMITTALS.
- CONTRACTOR SHALL PROVIDE AND INSTALL SOLID SOD IN ALL RIGHT-OF-WAYS AND PARKWAYS (UNLESS NOT ALLOWED BY THE LOCAL JURISDICTION) AND SHALL PROVIDE WATERING AND MAINTENANCE UNTIL THE TURF IS ESTABLISHED AND HAS BEEN ACCEPTED BY OWNER.
- THE CONTRACTOR SHALL MAINTAIN THE LANDSCAPE IN A HEALTHY CONDITION FOR 90 DAYS AFTER ACCEPTANCE BY THE OWNER. REFER TO SPECIFICATIONS FOR CONDITIONS OF ACCEPTANCE FOR THE START OF THE MAINTENANCE PERIOD, AND FOR FINAL ACCEPTANCE AT THE END OF THE MAINTENANCE PERIOD.
- SEE SPECIFICATIONS AND DETAILS FOR FURTHER REQUIREMENTS.

ROOT BARRIERS

THE CONTRACTOR SHALL INSTALL ROOT BARRIERS NEAR ALL NEWLY-PLANTED TREES THAT ARE LOCATED WITHIN FIVE (5) FEET OF PAVING, CURBS, WATER, STORM, OR SANITARY SEWER UTILITIES. ROOT BARRIERS SHALL BE "CENTURY" OR "DEEP-ROOT" 24" DEEP PANELS (OR EQUAL). BARRIERS SHALL BE LOCATED IMMEDIATELY ADJACENT TO HARDSCAPE. INSTALL PANELS PER MANUFACTURER'S RECOMMENDATIONS. UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR USE ROOT BARRIERS OF A TYPE THAT COMPLETELY ENCIRCLE THE ROOTBALL.

MULCHES

AFTER ALL PLANTING IS COMPLETE, CONTRACTOR SHALL INSTALL 2" THICK LAYER OF 1-1/2" SHREDDED WOOD MULCH, NATURAL (UNDYED), OVER LANDSCAPE FABRIC IN ALL PLANTING AREAS (EXCEPT FOR TURF AND SEEDED AREAS). CONTRACTOR SHALL SUBMIT SAMPLES OF ALL MULCHES TO LANDSCAPE ARCHITECT AND OWNER FOR APPROVAL PRIOR TO CONSTRUCTION. ABSOLUTELY NO EXPOSED GROUND SHALL BE LEFT SHOWING ANYWHERE ON THE PROJECT AFTER MULCH HAS BEEN INSTALLED (SUBJECT TO THE CONDITIONS AND REQUIREMENTS OF THE "GENERAL GRADING AND PLANTING NOTES" AND SPECIFICATIONS).

PLANTING & IRRIGATION GUARANTEE

THE LANDSCAPE CONTRACTOR SHALL GUARANTEE THAT ALL NEWLY INSTALLED AND EXISTING PLANTS SHALL SURVIVE FOR ONE YEAR AFTER FINAL OWNER ACCEPTANCE OF THE INSTALLATION WORK. THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR APPROPRIATE WATERING OF THE LANDSCAPE THROUGH INSTALLATION OF A PROPERLY DESIGNED IRRIGATION SYSTEM. THE OWNER SHALL APPROVE THE SYSTEM DESIGN BEFORE INSTALLATION OF PLANTS OR IRRIGATION.

IRRIGATION CONCEPT

- AN AUTOMATIC IRRIGATION SYSTEM SHALL BE INSTALLED AND OPERATIONAL BY THE TIME OF FINAL INSPECTION. THE ENTIRE IRRIGATION SYSTEM SHALL BE INSTALLED BY A LICENSED AND QUALIFIED IRRIGATION CONTRACTOR.
- THE IRRIGATION SYSTEM WILL MEET THE REQUIREMENTS OF THE UDC.
- THE IRRIGATION SYSTEM WILL OPERATE ON POTABLE WATER, AND THE SYSTEM WILL HAVE APPROPRIATE BACKFLOW PREVENTION DEVICES INSTALLED TO PREVENT CONTAMINATION OF THE POTABLE SOURCE.
- ALL NON-TURF PLANTED AREAS SHALL BE DRIP IRRIGATED. SODDED AND SEEDED AREAS SHALL BE IRRIGATED WITH SPRAY OR ROTOR HEADS AT 100% HEAD-TO-HEAD COVERAGE.
- ALL PLANTS SHARING SIMILAR HYDROZONE CHARACTERISTICS SHALL BE PLACED ON A VALVE DEDICATED TO PROVIDE THE NECESSARY WATER REQUIREMENTS SPECIFIC TO THAT HYDROZONE.
- THE IRRIGATION SYSTEM SHALL BE DESIGNED AND INSTALLED, TO THE MAXIMUM EXTENT POSSIBLE, TO CONSERVE WATER BY USING THE FOLLOWING DEVICES AND SYSTEMS: MATCHED PRECIPITATION RATE TECHNOLOGY ON ROTOR AND SPRAY HEADS (WHEREVER POSSIBLE), RAIN SENSORS, AND MULTI-PROGRAM COMPUTERIZED IRRIGATION CONTROLLERS FEATURING SENSORY INPUT CAPABILITIES.

PLANT SCHEDULE						
SYMBOL	KEY	QTY	BOTANICAL NAME	COMMON NAME	SIZE	SPACING
TREES						
⊙	CL	4	CHILOPSIS LINEARIS 'TIMELESS BEAUTY'	TIMELESS BEAUTY DESERT WILLOW	MIN. 4' HT.	PER PLAN
⊙	QB	4	QUERCUS BUCKLEYI	TEXAS RED OAK	MIN. 4" CAL.	PER PLAN
⊙	UC	3	ULMUS CRASSIFOLIA	CEDAR ELM	MIN. 4" CAL.	PER PLAN
SHRUBS						
⊙	AG	64	ABELIA GRANDIFLORA 'ROSE CREEK'	ROSE CREEK ABELIA	5 GAL.	2' O.C.
⊙	IV	53	ILEX VOMITORIA 'NANA'	DWARF YAUPON HOLLY	5 GAL.	3' O.C.
⊙	MC	39	MYRICA CERIFERA 'DON'S DWARF'	DON'S DWARF WAX MYRTLE	5 GAL.	4' O.C.
GROUNDCOVER						
⊙	6733 SF		SOD: CYNODON DACTYLON 'TIF TUF'	TIF TUF BERMUDA GRASS	SOD	

CAUTION NOTICE TO CONTRACTORS
 THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL 811 AT LEAST 72 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATIONS OF THE UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THESE PLANS.



10/06/25

BY	REVISION DESCRIPTION	DATE
SS	approved by	
LC	designed by	
SMS	drawn by	

LANDSCAPE PLAN
 LOT 18, BLOCK A, CREEKSIDE COMMONS ADDITION
 NWC STATE HIGHWAY 205 & F.M. 549
 A 0.936 ACRE TRACT OF LAND IN THE WILLIAM W. FORD SURVEY, ABST. NO 80
 CITY OF ROCKWALL, ROCKWALL COUNTY, TEXAS
 CITY PROJECT #SP2025-039
 October 6, 2025

APPROVED:
 I hereby certify that the above and foregoing site plan for a development in the City of Rockwall, Texas, was approved by the Planning & Zoning Commission of the City of Rockwall on the ____ day of ____, 2025.
 WITNESS OUR HANDS, this ____ day of ____, 2025.
 Planning & Zoning Commission, Chairman Director of Planning and Zoning

ENGINEER/APPLICANT
 THE DIMENSION GROUP
 10755 SANDHILL ROAD
 DALLAS, TX, 75238
 PHONE: (214) 343-9400
 CONTACT: KEATON L. MAI, PE

OWNER
 PRUDENT DEVELOPMENT
 10755 SANDHILL ROAD
 DALLAS, TEXAS 75238
 PHONE: (214) 271-4630
 CONTACT: MICHAEL HAMPTON

DEVELOPER
 VALLEY BELLS ENTERPRISES, LLC
 101 E. CHEROKEE STREET
 JACKSONVILLE, TX 75766
 PHONE: (903) 586-1524
 CONTACT: MIKE STRANSBERRY

LANDSCAPE PLAN
 TACO BELL
 NWC STATE HIGHWAY 205 AND FM 549
 ROCKWALL, TEXAS 75082
 SHEET
LP-1

PLANTING SPECIFICATIONS

GENERAL

A. QUALIFICATIONS OF LANDSCAPE CONTRACTOR

- ALL LANDSCAPE WORK SHOWN ON THESE PLANS SHALL BE PERFORMED BY A SINGLE FIRM SPECIALIZING IN LANDSCAPE PLANTING.
- A LIST OF SUCCESSFULLY COMPLETED PROJECTS OF THIS TYPE, SIZE AND NATURE MAY BE REQUESTED BY THE OWNER FOR FURTHER QUALIFICATION MEASURES.
- THE LANDSCAPE CONTRACTOR SHALL HOLD A VALID NURSERY AND FLORAL CERTIFICATE ISSUED BY THE TEXAS DEPARTMENT OF AGRICULTURE, AS WELL AS OPERATE UNDER A COMMERCIAL PESTICIDE APPLICATOR LICENSE ISSUED BY EITHER THE TEXAS DEPARTMENT OF AGRICULTURE OR THE TEXAS STRUCTURAL PEST CONTROL BOARD.

B. SCOPE OF WORK

- WORK COVERED BY THESE SECTIONS INCLUDES THE FURNISHING AND PAYMENT OF ALL MATERIALS, LABOR, SERVICES, EQUIPMENT, LICENSES, TAXES AND ANY OTHER ITEMS THAT ARE NECESSARY FOR THE EXECUTION, INSTALLATION AND COMPLETION OF ALL WORK SPECIFIED HEREIN AND / OR SHOWN ON THE LANDSCAPE PLANS, NOTES, AND DETAILS.
- ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH ALL APPLICABLE LAWS, CODES AND REGULATIONS REQUIRED BY AUTHORITIES HAVING JURISDICTION OVER SUCH WORK, INCLUDING ALL INSPECTIONS AND PERMITS REQUIRED BY FEDERAL, STATE AND LOCAL AUTHORITIES IN SUPPLY, TRANSPORTATION AND INSTALLATION OF MATERIALS.
- THE LANDSCAPE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL UNDERGROUND UTILITY LINES (WATER, SEWER, ELECTRICAL, TELEPHONE, GAS, CABLE, TELEVISION, ETC.) PRIOR TO THE START OF ANY WORK.

PRODUCTS

- A. ALL MANUFACTURED PRODUCTS SHALL BE NEW.**
- B. CONTAINERS AND BALLED-AND-BURLAPPED PLANTS:**
- FURNISH NURSERY-GROWN PLANTS COMPLYING WITH ANSI Z60.1-2014. PROVIDE WELL-SHAPED, FULLY BRANCHED, HEALTHY, VIGOROUS STOCK FREE OF DISEASE, INSECTS, EGGS, LARVAE, AND DEFECTS SUCH AS KNOTS, SUN SCALD, INJURIES, ABRASIONS, AND DISFIGUREMENT. ALL PLANTS WITH A SPECIES SHALL HAVE SIMILAR SIZE, AND SHALL BE OF A FORM TYPICAL FOR THE SPECIES. ALL TREES SHALL BE OBTAINED FROM SOURCES WITHIN 200 MILES OF THE PROJECT SITE, AND WITH SIMILAR CLIMATIC CONDITIONS.
 - ROOT SYSTEMS SHALL BE HEALTHY, DENSELY BRANCHED ROOT SYSTEMS, NON-POT-BOUND, FREE FROM ENCIRCLING AND/OR GIRDLING ROOTS, AND FREE FROM ANY OTHER ROOT DEFECTS (SUCH AS J-SHAPED ROOTS).
 - TREES MAY BE PLANTED FROM CONTAINERS OR BALLED-AND-BURLAPPED (BBB), UNLESS SPECIFIED ON THE PLANTING LEGEND. BARE-ROOT TREES ARE NOT ACCEPTABLE.
 - ANY PLANT DEEMED UNACCEPTABLE BY THE LANDSCAPE ARCHITECT OR OWNER SHALL BE IMMEDIATELY REMOVED FROM THE SITE AND SHALL BE REPLACED WITH AN ACCEPTABLE PLANT OF LIKE TYPE AND SIZE AT THE CONTRACTOR'S OWN EXPENSE. ANY PLANTS APPEARING TO BE UNHEALTHY, EVEN IF DETERMINED TO STILL BE ALIVE, SHALL NOT BE ACCEPTED. THE LANDSCAPE ARCHITECT AND OWNER SHALL BE THE ACCEPTABILITY OF PLANT MATERIAL.
 - ALL TREES SHALL BE STANDARD IN FORM UNLESS OTHERWISE SPECIFIED. TREES WITH CENTRAL LEADERS WILL NOT BE ACCEPTED IF LEADER IS DAMAGED OR REMOVED. PRUNE ALL DAMAGED TWIGS AFTER PLANTING.
 - CALIPER MEASUREMENTS FOR STANDARD (SINGLE TRUNK) TREES SHALL BE AS FOLLOWS: SIX INCHES ABOVE THE ROOT FLARE FOR TREES UP TO AND INCLUDING FOUR INCHES IN CALIPER, AND TWELVE INCHES ABOVE THE ROOT FLARE FOR TREES EXCEEDING FOUR INCHES IN CALIPER.
 - MULTI-TRUNK TREES SHALL BE MEASURED BY THEIR OVERALL HEIGHT, MEASURED FROM THE TOP OF THE ROOT BALL, WHERE CALIPER MEASUREMENTS ARE USED, THE CALIPER SHALL BE CALCULATED AS ONE-HALF OF THE SUM OF THE CALIPER OF THE THREE LARGEST TRUNKS.
 - ANY TREE OR SHRUB SHOWN TO HAVE EXCESS SOIL PLACED ON TOP OF THE ROOT BALL, SO THAT THE ROOT FLARE HAS BEEN COMPLETELY COVERED, SHALL BE REJECTED.
- C. SEED:** PROVIDE BLEND OF SPECIES AND VARIETIES AS NOTED ON THE PLANS, WITH MAXIMUM PERCENTAGES OF PURITY, GERMINATION, AND MINIMUM PERCENTAGE OF WEED SEED AS INDICATED ON PLANS. EACH BAG OF SEED SHALL BE ACCOMPANIED BY A TAG FROM THE SUPPLIER INDICATING THE COMPOSITION OF THE SEED.
- D. TOPSOIL:** SANDY TO CLAY LOAM TOPSOIL, FREE OF STONES LARGER THAN 1/2 INCH, FOREIGN MATTER, PLANTS, ROOTS, AND SEEDS.
- E. COMPOST:** WELL-COMPOSTED, STABLE, AND WEED-FREE ORGANIC MATTER, pH RANGE OF 5.5 TO 8, MOISTURE CONTENT 35 TO 55 PERCENT BY WEIGHT, 100 PERCENT PASSING THROUGH 3/4-INCH SIEVE; SOLUBLE SALT CONTENT OF 5 TO 10 DECISEMENS/M; NOT EXCEEDING 0.5 PERCENT INERT CONTAMINANTS AND FREE OF SUBSTANCES TOXIC TO PLANTINGS. NO MANURE OR ANIMAL-BASED PRODUCTS SHALL BE USED.
- F. FERTILIZER:** GRANULAR FERTILIZER CONSISTING OF NITROGEN, PHOSPHORUS, POTASSIUM, AND OTHER NUTRIENTS IN PROPORTIONS, AMOUNTS, AND RELEASE RATES RECOMMENDED IN A SOIL REPORT FROM A QUALIFIED SOIL-TESTING AGENCY (SEE BELOW).
- G. MULCH:** SIZE AND TYPE AS INDICATED ON PLANS, FREE FROM DELETERIOUS MATERIALS AND SUITABLE AS TOP DRESSING OF TREES AND SHRUBS.
- H. TREE STAKING AND GUYING**
- STAKES: 1/2" LONG GREEN METAL T-POSTS.
 - GUY AND TIE WIRE: ASTM A 641, CLASS 1, GALVANIZED-STEEL WIRE, 2-STRAND, TWISTED, 0.106 INCH DIAMETER.
 - STRAP CHAIRING GUARD: REINFORCED NYLON OR CANVAS AT LEAST 1-1/2 INCH WIDE, WITH GROMMETS TO PROTECT TREE TRUNKS FROM DAMAGE.
- J. STEEL EDGING:** PROFESSIONAL STEEL EDGING, 14 GAUGE THICK X 4 INCHES WIDE, FACTORY PAINTED DARK GREEN. ACCEPTABLE MANUFACTURERS INCLUDE COL-MET OR APPROVED EQUAL.
- K. PRE-EMERGENT HERBICIDES:** ANY GRANULAR, NON-STAINING PRE-EMERGENT HERBICIDE THAT IS LABELED FOR THE SPECIFIC ORNAMENTALS OR TURF ON WHICH IT WILL BE UTILIZED. PRE-EMERGENT HERBICIDES SHALL BE APPLIED PER THE MANUFACTURER'S LABELED RATES.

METHODS

- A. SOIL PREPARATION**
- BEFORE STARTING WORK, THE LANDSCAPE CONTRACTOR SHALL VERIFY THAT THE GRADE OF ALL LANDSCAPE AREAS ARE WITHIN +0.0' OF FINISH GRADE. THE CONTRACTOR SHALL NOTIFY THE OWNER IMMEDIATELY SHOULD ANY DISCREPANCIES EXIST.
 - SOIL TESTING:
 - AFTER FINISH GRADES HAVE BEEN ESTABLISHED, CONTRACTOR SHALL HAVE SOIL SAMPLES FROM THE PROJECT'S LANDSCAPE AREAS TESTED BY AN ESTABLISHED SOIL TESTING LABORATORY. EACH SAMPLE SUBMITTED TO THE LAB SHALL CONTAIN NO LESS THAN ONE QUART OF SOIL, TAKEN FROM BETWEEN THE SOIL SURFACE AND 6" DEPTH. IF NO SAMPLE LOCATIONS ARE INDICATED ON THE PLANS, THE CONTRACTOR SHALL TAKE A MINIMUM OF THREE SAMPLES FROM VARIOUS REPRESENTATIVE LOCATIONS FOR TESTING.
 - THE CONTRACTOR SHALL HAVE THE SOIL TESTING LABORATORY PROVIDE RESULTS FOR THE FOLLOWING: SOIL TEXTURAL CLASS, GENERAL SOIL FERTILITY, pH, ORGANIC MATTER CONTENT, SALT (CEC), LIME, SODIUM ADSORPTION RATIO (SAR) AND BORON CONTENT.
 - THE CONTRACTOR SHALL ALSO SUBMIT THE PROJECT'S PLANT LIST TO THE LABORATORY ALONG WITH THE SOIL SAMPLES.
 - THE SOIL REPORT PRODUCED BY THE LABORATORY SHALL CONTAIN RECOMMENDATIONS FOR THE FOLLOWING (AS APPROPRIATE): SEPARATE SOIL PREPARATION AND BACKFILL MIX RECOMMENDATIONS FOR ORNAMENTAL PLANTS, SERIC PLANTS, TURF, AND NATIVE SEED, AS WELL AS PRE-PLANT FERTILIZER APPLICATIONS AND RECOMMENDATIONS FOR ANY OTHER SOIL RELATED ISSUES. THE REPORT SHALL ALSO PROVIDE A FERTILIZER PROGRAM FOR THE ESTABLISHMENT PERIOD AND FOR LONG-TERM MAINTENANCE.
 - THE CONTRACTOR SHALL INSTALL SOIL AMENDMENTS AND FERTILIZERS PER THE SOILS REPORT RECOMMENDATIONS. ANY CHANGE IN COST DUE TO THE SOIL REPORT RECOMMENDATIONS, EITHER INCREASE OR DECREASE, SHALL BE SUBMITTED TO THE OWNER WITH THE REPORT.
 - FOR BIDDING PURPOSES ONLY, THE SOIL PREPARATION SHALL CONSIST OF THE FOLLOWING:
 - TURF: INCORPORATE THE FOLLOWING AMENDMENTS INTO THE TOP 8" OF SOIL BY MEANS OF ROTOTILLING AFTER CROSS-RIPPING:
 - NITROGEN STABILIZED ORGANIC AMENDMENT - 4 CU. YDS. PER 1,000 S.F.
 - PREPLANT TURF FERTILIZER (10-20-10 OR SIMILAR, SLOW RELEASE, ORGANIC) - 15 LBS PER 1,000 S.F.
 - "CLAY BUSTER" OR EQUAL - USE MANUFACTURER'S RECOMMENDED RATE
 - TREES, SHRUBS, AND PERENNIALS: INCORPORATE THE FOLLOWING AMENDMENTS INTO THE TOP 8" OF SOIL BY MEANS OF ROTOTILLING AFTER CROSS-RIPPING:
 - NITROGEN STABILIZED ORGANIC AMENDMENT - 4 CU. YDS. PER 1,000 S.F.
 - 12-12-12 FERTILIZER (OR SIMILAR, ORGANIC, SLOW RELEASE) - 10 LBS. PER CU. YD.
 - "CLAY BUSTER" OR EQUAL - USE MANUFACTURER'S RECOMMENDED RATE
 - IRON SULPHATE - 2 LBS. PER CU. YD.
 - IN THE CONTEXT OF THESE PLANS, NOTES, AND SPECIFICATIONS, "FINISH GRADE" REFERS TO THE FINAL ELEVATION OF THE SOIL SURFACE (NOT TOP OF MULCH) AS INDICATED ON THE GRADING PLANS. BEFORE STARTING WORK, THE LANDSCAPE CONTRACTOR SHALL VERIFY THAT THE ROUGH GRADES OF ALL LANDSCAPE AREAS ARE WITHIN +0.0' OF FINISH GRADE. SEE SPECIFICATIONS FOR MORE DETAILED INSTRUCTION ON TURF AREA AND PLANTING BED PREPARATION.
 - CONSTRUCT AND MAINTAIN FINISH GRADES AS SHOWN ON GRADING PLANS, AND CONSTRUCT AND MAINTAIN SLOPES AS RECOMMENDED BY THE GEOTECHNICAL REPORT. ALL LANDSCAPE AREAS SHALL HAVE POSITIVE DRAINAGE AWAY FROM STRUCTURES AT THE MINIMUM SLOPE SPECIFIED IN THE REPORT AND ON THE GRADING PLANS, AND AREAS OF POTENTIAL PONDING SHALL BE REGRADED TO BLEND IN WITH THE SURROUNDING GRADES AND ELIMINATE PONDING POTENTIAL.
 - THE LANDSCAPE CONTRACTOR SHALL DETERMINE WHETHER OR NOT THE EXPORT OF ANY SOIL WILL BE NEEDED, TAKING INTO ACCOUNT THE ROUGH GRADE PROVIDED, AND THE FINISH GRADES TO BE ESTABLISHED.
 - AFTER INSTALLING SOIL AMENDMENTS IN SHRUB AREAS, AND IN ORDER TO ALLOW FOR PROPER MULCH DEPTH, ENSURE THAT THE FINISH GRADE IMMEDIATELY ADJACENT TO WALKS AND OTHER WALKING SURFACES IS 0" BELOW FINISH GRADE, TAPERING TO MEET FINISH GRADE AT APPROXIMATELY 18" AWAY FROM THE SURFACE.
 - AFTER INSTALLING SOIL AMENDMENTS IN TURF AREAS, ENSURE THAT THE FINISH GRADE IN TURF AREAS IMMEDIATELY ADJACENT TO WALKS AND OTHER WALKING SURFACES IS 1" BELOW FINISH GRADE, TAPERING TO MEET FINISH GRADE AT APPROXIMATELY 18" AWAY FROM THE SURFACE.
 - SHOULD ANY CONFLICTS AND/OR DISCREPANCIES ARISE BETWEEN THE GRADING PLANS, GEOTECHNICAL REPORT, THESE NOTES AND PLANS, AND ACTUAL CONDITIONS, THE CONTRACTOR SHALL IMMEDIATELY BRING SUCH ITEMS TO THE ATTENTION OF THE LANDSCAPE ARCHITECT, GENERAL CONTRACTOR, AND OWNER.
 - ONCE SOIL PREPARATION IS COMPLETE, THE LANDSCAPE CONTRACTOR SHALL ENSURE THAT THERE ARE NO DEBRIS, TRASH, OR STONES LARGER THAN 1" REMAINING IN THE TOP 6" OF SOIL.

B. SUBMITTALS

- THE CONTRACTOR SHALL PROVIDE SUBMITTALS AND SAMPLES, IF REQUIRED, TO THE LANDSCAPE ARCHITECT, AND RECEIVE APPROVAL IN WRITING FOR SUCH SUBMITTALS BEFORE WORK COMMENCES.
- SUBMITTALS SHALL INCLUDE PHOTOS OF PLANTS WITH A RULER OR MEASURING STICK FOR SCALE. PHOTOS OR SAMPLES OF ANY REQUIRED MULCHES, AND SOIL TEST RESULTS AND PREPARATION RECOMMENDATIONS FROM THE TESTING LAB (INCLUDING COMPOST AND FERTILIZER RATES AND TYPES, AND OTHER AMENDMENTS FOR TREE/SHRUB, TURF, AND SEED AREAS AS MAY BE APPROPRIATE).
- SUBMITTALS SHALL ALSO INCLUDE MANUFACTURER CUT SHEETS FOR PLANTING ACCESSORIES SUCH AS TREE STAKES AND TIES, EDGING, AND LANDSCAPE FABRICS (IF ANY).
- WHERE MULTIPLE ITEMS ARE SHOWN ON A PAGE, THE CONTRACTOR SHALL CLEARLY INDICATE THE ITEM BEING CONSIDERED.

C. GENERAL PLANTING

- REMOVE ALL NURSERY TAGS AND STAKES FROM PLANTS.
- EXCEPT IN AREAS TO BE PLANTED WITH ORNAMENTAL GRASSES, APPLY PRE-EMERGENT HERBICIDES AT THE MANUFACTURER'S RECOMMENDED RATE.
- TRENCHING NEAR PLANTINGS:
 - CONTRACTOR SHALL NOT DISTURB ROOTS 1-1/2" AND LARGER IN DIAMETER WITHIN THE CRITICAL ROOT ZONE (CRZ) OF EXISTING TREES, AND SHALL EXERCISE ALL POSSIBLE CARE AND PRECAUTIONS TO AVOID INJURY TO TREE ROOTS, TRUNKS, AND BRANCHES. THE CRZ IS DEFINED AS A CIRCULAR AREA EXTENDING OUTWARD FROM THE TREE TRUNK, WITH A RADIUS EQUAL TO 1" FOR EVERY 1" OF TRUNK DIAMETER-AT-BREAST-HEIGHT (4.5' ABOVE THE AVERAGE GRADE AT THE TRUNK).
 - ALL EXCAVATION WITHIN THE CRZ SHALL BE PERFORMED USING HAND TOOLS. NO MACHINE EXCAVATION OR TRENCHING OF ANY KIND SHALL BE ALLOWED WITHIN THE CRZ.
 - ALTER ALIGNMENT OF PIPE TO AVOID TREE ROOTS 1-1/2" AND LARGER IN DIAMETER. WHERE TREE ROOTS 1-1/2" AND LARGER IN DIAMETER ARE ENCOUNTERED IN THE FIELD, TUNNEL UNDER SUCH ROOTS. WRAP EXPOSED ROOTS WITH SEVERAL LAYERS OF BURLAP AND KEEP MOIST. CLOSE ALL TRENCHES WITHIN THE CANOPY DRIP LINES WITHIN 24 HOURS.
 - ALL SEVERED ROOTS SHALL BE HAND PRUNED WITH SHARP TOOLS AND ALLOWED TO AIR-DRY. DO NOT USE ANY SORT OF SEALERS OR WOUND PAINTS.

C. TREE PLANTING

- TREE PLANTING HOLES SHALL BE EXCAVATED TO MINIMUM WIDTH OF TWO TIMES THE WIDTH OF THE ROOTBALL, AND TO A DEPTH EQUAL TO THE DEPTH OF THE ROOTBALL LESS TWO TO FOUR INCHES. SCARIFY THE SIDES AND BOTTOM OF THE PLANTING HOLE PRIOR TO THE PLACEMENT OF THE TREE.
- REMOVE ANY CLUMPING THAT MAY HAVE BEEN CAUSED DURING THE EXCAVATION OF THE HOLE. FOR CONTAINER AND BOX TREES, TO REMOVE ANY POTENTIALLY GIRDLING ROOTS AND OTHER ROOT DEFECTS, THE CONTRACTOR SHALL SHAKE A 1" LAYER OFF OF THE SIDES AND BOTTOM OF THE ROOTBALL OF ALL TREES BEFORE PLACING INTO THE PLANTING PIT. DO NOT 'TEASE' ROOTS OUT FROM THE ROOTBALL.
- INSTALL THE TREE ON UNDISTURBED SUBGRADE SO THAT THE TOP OF THE ROOTBALL IS TWO TO FOUR INCHES ABOVE FINISH GRADE. REMOVE ALL OTHER DEBRIS UTILIZING THE EXISTING TOPSOIL FROM ON-SITE. ROCKS LARGER THAN 1" DIA. AND ALL OTHER DEBRIS SHALL BE REMOVED FROM THE SOIL PRIOR TO THE BACKFILL. SHOULD ADDITIONAL SOIL BE REQUIRED TO COMPLETE THIS TASK, USE STORED TOPSOIL FROM ON-SITE OR IMPORT ADDITIONAL TOPSOIL FROM OFF-SITE AT NO ADDITIONAL COST TO THE OWNER. IMPORTED TOPSOIL SHALL BE OF SIMILAR TEXTURAL CLASS AND COMPOSITION IN THE ON-SITE SOIL.
- TREES SHALL NOT BE PLANTED IN SODDED AREAS (SUCH AS HEAVY WALKS OR DRIVEWAYS) UNLESS REQUIRE STAKES TO KEEP TREES UPRIGHT. SHOULD STAKING BE REQUIRED, THE TOTAL NUMBER OF TREE STAKES (BEYOND THE MINIMUMS LISTED BELOW) WILL BE LEFT TO THE LANDSCAPE CONTRACTOR'S DISCRETION. STAKES SHALL BE PLACED ABOVE THE FINISH GRADE. CONTRACTOR SHALL STRAIGHTEN THE TREE, OR REPLACE IT SHOULD IT BECOME DAMAGED. TREE STAKING SHALL ADHERE TO THE FOLLOWING GUIDELINES:
 - 1" X 2" TREES - TWO STAKES PER TREE
 - 2-1/2" X 4" TREES - THREE STAKES PER TREE
 - TREES OVER 4" CALIPER - GUY AS NEEDED
- MULTI-TRUNK TREES - THREE STAKES PER TREE MINIMUM. QUANTITY AND POSITIONS AS NEEDED TO STABILIZE THE TREE.
- UPON COMPLETION OF PLANTING, CONSTRUCT AN EARTH WATERING BASIN AROUND THE TREE TO COVER THE INTERIOR OF THE TREE RING WITH MULCH (TYPE AND DEPTH PER PLANS). UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR PLACE MULCH WITHIN 6" OF THE TRUNK.

D. SHRUB, PERENNIAL, AND GROUNDCOVER PLANTING

- DIG THE PLANTING HOLES TWICE AS WIDE AND 2" LESS DEEP THAN EACH PLANTS' ROOTBALL. INSTALL THE PLANT IN THE HOLE. BACKFILL AROUND THE PLANT WITH SOIL AMENDED PER SOIL TEST RECOMMENDATIONS.
- WHEN PLANTING IS COMPLETE, INSTALL MULCH (TYPE AND DEPTH PER PLANS) OVER ALL PLANTING AREAS (EXCEPT FOR SODDED AND SEEDED AREAS), LEAVING NO EXPOSED GROUND.

F. SODDING

- SOD VARIETY TO BE AS SPECIFIED ON THE LANDSCAPE PLAN.
- LAY SOD WITHIN 24 HOURS FROM THE TIME OF STRIPPING. DO NOT LAY IF THE GRASS IS FROZEN.
- LAY THE SOD TO FORM A SOLID MASS WITH TIGHTLY FITTED JOINTS. BUTT ENDS AND SIDES OF SOD STRIPS - DO NOT OVERLAP. STAGGER STRIPS TO FITSET JOINTS IN ADJACENT COURSES.
- ROLL THE SOD TO ENSURE GOOD CONTACT OF THE SOD'S ROOT SYSTEM WITH THE SOIL UNDERNEATH.
- WATER THE SOD THOROUGHLY WITH A FINE SPRAY IMMEDIATELY AFTER PLANTING TO OBTAIN AT LEAST SIX INCHES OF PENETRATION INTO THE SOIL BELOW THE SOD.

G. MULCH

- INSTALL MULCH TOPDRESSING, TYPE AND DEPTH PER MULCH NOTE, IN ALL PLANTING AREAS AND TREE RINGS.
- DO NOT INSTALL MULCH WITHIN 6" OF TREE ROOT FLARE AND WITHIN 24" OF HABITABLE STRUCTURES, EXCEPT AS MAY BE NOTED ON THESE PLANS. MULCH COVER WITHIN 6" OF CONCRETE WALKS AND CURBS SHALL NOT PROVIDE ABOVE THE FINISH SURFACE OF THE WALKS AND CURBS. MULCH COVER WITHIN 12" OF WALLS SHALL BE AT LEAST 3" LOWER THAN THE TOP OF WALL.

H. CLEAN UP


- DURING LANDSCAPE PREPARATION AND PLANTING, KEEP ALL PAVEMENT CLEAN AND ALL WORK AREAS IN A NEAT, ORDERLY CONDITION.
- DISPOSED LEGALLY OF ALL EXCAVATED MATERIALS OFF THE PROJECT SITE.

I. INSPECTION AND ACCEPTANCE

- UPON COMPLETION OF THE WORK, THE LANDSCAPE CONTRACTOR SHALL PROVIDE THE SITE CLEAN, FREE OF DEBRIS AND TRASH, AND SUITABLE FOR USE AS INTENDED. THE LANDSCAPE CONTRACTOR SHALL THEN REQUEST AN INSPECTION BY THE OWNER TO DETERMINE FINAL ACCEPTABILITY.
- WHEN THE INSPECTED PLANTING WORK DOES NOT COMPLY WITH THE CONTRACT DOCUMENTS, THE LANDSCAPE CONTRACTOR SHALL REPLACE AND/OR REPAIR THE REJECTED WORK TO THE OWNER'S SATISFACTION WITHIN 24 HOURS.
- THE LANDSCAPE MAINTENANCE PERIOD WILL NOT COMMENCE UNTIL THE LANDSCAPE WORK HAS BEEN RE-INSPECTED BY THE OWNER AND FOUND TO BE ACCEPTABLE. AT THAT TIME, A WRITTEN NOTICE OF FINAL ACCEPTANCE WILL BE ISSUED BY THE OWNER, AND THE MAINTENANCE AND GUARANTEE PERIODS WILL COMMENCE.

J. LANDSCAPE MAINTENANCE


- THE LANDSCAPE CONTRACTOR SHALL BE RESPONSIBLE FOR THE MAINTENANCE OF ALL WORK SHOWN ON THESE PLANS FOR 90 DAYS BEYOND FINAL ACCEPTANCE OF ALL LANDSCAPE WORK BY THE OWNER. LANDSCAPE MAINTENANCE SHALL INCLUDE WEEKLY SITE VISITS FOR THE FOLLOWING ACTIONS (AS APPROPRIATE): PROPER PRUNING, RESTAKING OF TREES, RESETTING OF PLANTS THAT HAVE SETTLED, MOWING AND AERATION OF LAWNS, WEEDING, RESEEDING AREAS WHICH HAVE NOT GERMINATED WELL, TREATING FOR INSECTS AND DISEASES, REPLACEMENT OF MULCH, REMOVAL OF LITTER, REPAIRS TO THE IRRIGATION SYSTEM DUE TO FAULTY PARTS AND/OR WORKMANSHIP, AND THE APPROPRIATE WATERING OF ALL PLANTINGS. THE LANDSCAPE CONTRACTOR SHALL MAINTAIN THE IRRIGATION SYSTEM IN PROPER WORKING ORDER, WITH SCHEDULING ADJUSTMENTS BY SEASON TO MAXIMIZE WATER CONSERVATION.
- SHOULD SEEDS AND/OR SODDED AREAS NOT BE COVERED BY AN AUTOMATIC IRRIGATION SYSTEM, THE LANDSCAPE CONTRACTOR SHALL BE RESPONSIBLE FOR WATERING THESE AREAS AND OBTAINING A FULL, HEALTHY STAND OF PLANTS AT NO ADDITIONAL COST TO THE OWNER.
- TO ACHIEVE FINAL ACCEPTANCE AT THE END OF THE MAINTENANCE PERIOD, ALL OF THE FOLLOWING CONDITIONS MUST OCCUR:
 - THE LANDSCAPE SHALL SHOW ACTIVE, HEALTHY GROWTH (WITH EXCEPTIONS MADE FOR SEASONAL DORMANCY). ALL PLANTS NOT MEETING THIS CONDITION SHALL BE REJECTED AND REPLACED BY HEALTHY PLANT MATERIAL PRIOR TO FINAL ACCEPTANCE.
 - ALL HARDSCAPE SHALL BE CLEANED PRIOR TO FINAL ACCEPTANCE.
 - SODDED AREAS MUST BE ACTIVELY GROWING AND MUST REACH A MINIMUM HEIGHT OF 1 1/2 INCHES BEFORE FIRST MOWING. HYDROMULCHED AREAS SHALL SHOW ACTIVE, HEALTHY GROWTH. BARE AREAS LARGER THAN TWELVE SQUARE INCHES MUST BE RESEEDD OR RESEEDD (AS APPROPRIATE) PRIOR TO FINAL ACCEPTANCE. ALL SODDED TURF SHALL BE NEATLY MOWED.
- WARRANTY PERIOD, PLANT GUARANTEE AND REPLACEMENTS
 - THE LANDSCAPE CONTRACTOR SHALL GUARANTEE ALL TREES, SHRUBS, PERENNIALS, SOD, SEEDED/HYDROMULCHED AREAS, AND IRRIGATION SYSTEMS FOR A PERIOD OF ONE YEAR FROM THE DATE OF THE OWNER'S FINAL ACCEPTANCE (90 DAYS FOR ANNUAL PLANTS). THE CONTRACTOR SHALL REPLACE AT HIS OWN EXPENSE AND TO THE SATISFACTION OF THE OWNER ANY PLANTS WHICH DIE IN THAT TIME, OR REPAIR ANY PORTIONS OF THE IRRIGATION SYSTEM WHICH OPERATE IMPROPERLY.
 - AFTER THE INITIAL MAINTENANCE PERIOD AND DURING THE GUARANTEE PERIOD, THE LANDSCAPE CONTRACTOR SHALL ONLY BE RESPONSIBLE FOR REPLACEMENT OF PLANTS WHEN PLANT DEATH CANNOT BE ATTRIBUTED DIRECTLY TO OVERWATERING OR OTHER DAMAGE BY HUMAN ACTIONS.
- PROVIDE A MINIMUM OF (2) COPIES OF RECORD DRAWINGS TO THE OWNER UPON COMPLETION OF WORK. A RECORD DRAWING IS A RECORD OF ALL CHANGES THAT OCCURRED IN THE FIELD AND THAT ARE DOCUMENTED THROUGH CHANGE ORDERS, ADDENDA, OR CONTRACTOR/CONSULTANT DRAWING MARKUPS.




- ROLLED-TOP STEEL EDGING PER PLANS.
- TAPERED STEEL STAKES.
- MULCH, TYPE AND DEPTH PER PLANS.
- FINISH GRADE.

- NOTES:
- INSTALL EDGING SO THAT STAKES WILL BE ON INSIDE OF PLANTING BED.
 - BOTTOM OF EDGING SHALL BE BURIED A MINIMUM OF 1" BELOW FINISH GRADE.
 - TOP OF MULCH SHALL BE 1" LOWER THAN TOP OF EDGING.

D STEEL EDGING
SCALE: NOT TO SCALE



E ROOT BARRIER - PLAN VIEW
SCALE: NOT TO SCALE



NOTE: ALL PLANTS SHALL BE PLANTED AT EQUAL TRIANGULAR SPACING (EXCEPT WHERE SHOWN ON PLANS AS INFORMAL GROUPINGS). REFER TO PLANT LEGEND FOR SPACING DISTANCE BETWEEN PLANTS.


1) STEP 1: DETERMINE TOTAL PLANTS FOR THE AREA WITH THE FOLLOWING FORMULA:
TOTAL AREA / AREA DIVIDER = TOTAL PLANTS

PLANT SPACING	AREA DIVIDER	PLANT SPACING	AREA DIVIDER
6"	0.22	18"	1.95
8"	0.39	24"	3.48
10"	0.60	30"	6.41
12"	0.87	36"	7.79
15"	1.35		

2) STEP 2: SUBTRACT THE ROW (S) OF PLANTS THAT WOULD OCCUR AT THE EDGE OF THE PLANTED AREA WITH THE FOLLOWING FORMULA: TOTAL PERIMETER LENGTH / PLANT SPACING = TOTAL PLANT SUBTRACTION

EXAMPLE: PLANTS AT 18" O.C. IN 100 SF PLANTING AREA, 40 LF PERIMETER
STEP 1: 100 SF / 3.48 = 51 PLANTS
STEP 2: 51 PLANTS - (40 LF / 18" = 21 PLANTS) = 30 PLANTS TOTAL


C PLANT SPACING
SCALE: NTS




- TREE CANOPY.
- CINCH-TIES (24" BOX2" CAL. TREES AND SMALLER) OR 1/2 GAUGE GALVANIZED WIRE WITH NYLON TREE STRAPS AT TREE AND STAKE (36" BOX2" CAL. TREES AND LARGER). SECURE TIES OR STRAPS TO TRUNK JUST ABOVE LOWEST MAJOR BRANCHES.
- 24" X 3/4" P.V.C. MARKERS OVER WIRES.
- GREEN STEEL T-POSTS. EXTEND POSTS 12" MIN. INTO UNDISTURBED SOIL.
- PRESSURE-TREATED WOOD DEADMAN, TWO PER TREE (MIN. BURY OUTSIDE OF PLANTING PIT AND 18" MIN. INTO UNDISTURBED SOIL).
- TRUNK FLARE.
- MULCH, TYPE AND DEPTH PER PLANS. DO NOT PLACE MULCH WITHIN 6" OF TRUNK.
- FINISH GRADE.
- ROOT BALL.
- BACKFILL, AMEND AND FERTILIZE ONLY AS RECOMMENDED IN SOIL FERTILITY ANALYSIS.
- UNDISTURBED NATIVE SOIL.
- 4" HIGH EARTHEN WATERING BASIN.
- FINISH GRADE.

- NOTES:
- SCARIFY SIDES OF PLANTING PIT PRIOR TO SETTING TREE.
 - REMOVE EXCESS SOIL APPLIED ON TOP OF THE ROOTBALL THAT COVERS THE ROOT FLARE. THE PLANTING HOLE DEPTH SHALL BE SUCH THAT THE ROOTBALL RESTS ON UNDISTURBED SOIL, AND THE ROOT FLARE IS 2" ABOVE FINISH GRADE.
 - FOR 8-8 TREES, CUT OFF BOTTOM 15' OF WIRE BASKET BEFORE PLACING TREE IN HOLE. CUT OFF AND REMOVE REMAINDER OF BASKET AFTER TREE IS SET IN HOLE. REMOVE ALL NYLON TIES, TWINE, ROPE, AND OTHER PACKING MATERIAL. REMOVE AS MUCH BURLAP FROM AROUND ROOTBALL AS IS PRACTICAL.
 - REMOVE ALL NURSERY STAKES AFTER PLANTING.
 - FOR TREES 36" CAL. AND LARGER, USE THREE STAKES OR DEADMAN (AS APPROPRIATE), SPACED EVENLY AROUND TREE. STAKING SHALL BE TIGHT ENOUGH TO PREVENT TRUNK FROM BENDING, BUT LOOSE ENOUGH TO ALLOW SOME TRUNK MOVEMENT IN WIND.

A TREE PLANTING
SCALE: NOT TO SCALE



B SHRUB AND PERENNIAL PLANTING
SCALE: NTS



NOTE: ALL PLANTS SHALL BE PLANTED AT EQUAL TRIANGULAR SPACING (EXCEPT WHERE SHOWN ON PLANS AS INFORMAL GROUPINGS). REFER TO PLANT LEGEND FOR SPACING DISTANCE BETWEEN PLANTS.

1) STEP 1: DETERMINE TOTAL PLANTS FOR THE AREA WITH THE FOLLOWING FORMULA:
TOTAL AREA / AREA DIVIDER = TOTAL PLANTS

PLANT SPACING	AREA DIVIDER	PLANT SPACING	AREA DIVIDER
6"	0.22	18"	1.95
8"	0.39	24"	3.48
10"	0.60	30"	6.41
12"	0.87	36"	7.79
15"	1.35		

2) STEP 2: SUBTRACT THE ROW (S) OF PLANTS THAT WOULD OCCUR AT THE EDGE OF THE PLANTED AREA WITH THE FOLLOWING FORMULA: TOTAL PERIMETER LENGTH / PLANT SPACING = TOTAL PLANT SUBTRACTION

EXAMPLE: PLANTS AT 18" O.C. IN 100 SF PLANTING AREA, 40 LF PERIMETER
STEP 1: 100 SF / 3.48 = 51 PLANTS
STEP 2: 51 PLANTS - (40 LF / 18" = 21 PLANTS) = 30 PLANTS TOTAL

C PLANT SPACING
SCALE: NTS

CAUTION NOTICE TO CONTRACTORS

THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL 811 AT LEAST 72 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATIONS OF THE UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATED ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THESE PLANS.

National Presence. Local Expertise.

EVERGREEN DESIGN GROUP
800.610.6130
www.evergreendesigngroup.com
LANDSCAPE ARCHITECTURE
LAND PLANNING • IRRIGATION DESIGN

THE DIMENSION GROUP

ARCHITECTURE • CIVIL ENGINEERING • MEP ENGINEERING
TEL: 214.433.9400 www.dimensiongroup.com

REGISTERED LANDSCAPE ARCHITECT
STATE OF TEXAS
3682
Sharon M. Strassberg

10/06/25

SERVICE AND ARE PROTECTED BY COPYRIGHT LAW. ALL RIGHTS RESERVED. NO PART OF THIS DOCUMENT MAY BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN CONSENT OF THE PROFESSIONAL ENGINEER.

BY	DATE	REVISION DESCRIPTION
SS		approved by
LC	09-11-2025	designed by
SS		approved by

PROJECT NO.	DATE	DATE	DATE
250-340	09-11-2025		

LANDSCAPE PLAN
LOT 18, BLOCK A, CREEKSIDE COMMONS ADDITION
NWC STATE HIGHWAY 205 & F.M. 549
A 0.936 ACRE TRACT OF LAND IN THE WILLIAM W. FORD SURVEY, ABST. NO 80
CITY OF ROCKWALL, ROCKWALL COUNTY, TEXAS
CITY PROJECT #SP2025-039
October 6, 2025

APPROVED:
I hereby certify that the above and foregoing site plan for a development in the City of Rockwall, Texas, was approved by the Planning & Zoning Commission of the City of Rockwall on the ____ day of ____, 2025.

WITNESS OUR HANDS, THIS ____ day of ____, 2025.

Planning & Zoning Commission, Chairman

Director of Planning and Zoning

ENGINEER/APPLICANT
THE DIMENSION GROUP
10755 SANDHILL ROAD
DALLAS, TX, 75238
PHONE: (214) 343-9400
CONTACT: KEATON L. MAI, PE

OWNER
PRUDENT DEVELOPMENT
10755 SANDHILL ROAD
DALLAS, TEXAS 75238
PHONE: (214) 271-4630
CONTACT: MICHAEL HAMPTON

DEVELOPER
VALLEY BELLS ENTERPRISES, LLC
101 E. CHEROKEE STREET
JACKSONVILLE, TX 75766
PHONE: (903) 586-1524
CONTACT: MIKE STRANSBERRY

LANDSCAPE SPECS & DETAILS
TACO BELL
NWC STATE HIGHWAY 205 AND FM 549
ROCKWALL, TEXAS 75092



DEVELOPMENT APPLICATION

City of Rockwall
Planning and Zoning Department
385 S. Goliad Street
Rockwall, Texas 75087

STAFF USE ONLY
PLANNING & ZONING CASE NO.

NOTE: THE APPLICATION IS NOT CONSIDERED ACCEPTED BY THE CITY UNTIL THE PLANNING DIRECTOR AND CITY ENGINEER HAVE SIGNED BELOW.

DIRECTOR OF PLANNING:

CITY ENGINEER:

PLEASE CHECK THE APPROPRIATE BOX BELOW TO INDICATE THE TYPE OF DEVELOPMENT REQUEST (SELECT ONLY ONE BOX):

PLATTING APPLICATION FEES:

- MASTER PLAT (\$100.00 + \$15.00 ACRE) ¹
- PRELIMINARY PLAT (\$200.00 + \$15.00 ACRE) ¹
- FINAL PLAT (\$300.00 + \$20.00 ACRE) ¹
- REPLAT (\$300.00 + \$20.00 ACRE) ¹ (\$565.72)
- AMENDING OR MINOR PLAT (\$150.00)
- PLAT REINSTATEMENT REQUEST (\$100.00)

SITE PLAN APPLICATION FEES:

- SITE PLAN (\$250.00 + \$20.00 ACRE) ¹
- AMENDED SITE PLAN/ELEVATIONS/LANDSCAPING PLAN (\$100.00)

ZONING APPLICATION FEES:

- ZONING CHANGE (\$200.00 + \$15.00 ACRE) ¹
- SPECIFIC USE PERMIT (\$200.00 + \$15.00 ACRE) ^{1&2}
- PD DEVELOPMENT PLANS (\$200.00 + \$15.00 ACRE) ¹

OTHER APPLICATION FEES:

- TREE REMOVAL (\$75.00)
- VARIANCE REQUEST/SPECIAL EXCEPTIONS (\$100.00) ²

NOTES:

¹: IN DETERMINING THE FEE, PLEASE USE THE EXACT ACREAGE WHEN MULTIPLYING BY THE PER ACRE AMOUNT. FOR REQUESTS ON LESS THAN ONE ACRE, ROUND UP TO ONE (1) ACRE.

²: A \$1,000.00 FEE WILL BE ADDED TO THE APPLICATION FEE FOR ANY REQUEST THAT INVOLVES CONSTRUCTION WITHOUT OR NOT IN COMPLIANCE TO AN APPROVED BUILDING PERMIT.

PROPERTY INFORMATION [PLEASE PRINT]

ADDRESS NWC of Hwy 205 and Future FM 549

SUBDIVISION Creekside Commons LOT 15,16 & 18 BLOCK A

GENERAL LOCATION NWC of Hwy 205 and Future FM 549

ZONING, SITE PLAN AND PLATTING INFORMATION [PLEASE PRINT]

CURRENT ZONING Commercial (C) CURRENT USE Undeveloped

PROPOSED ZONING Commercial (C) PROPOSED USE Restaurant w/ drive-through

ACREAGE 13.286 LOTS [CURRENT] 15,16 & 18 LOTS [PROPOSED] 19,20 & 21

SITE PLANS AND PLATS: BY CHECKING THIS BOX YOU ACKNOWLEDGE THAT DUE TO THE PASSAGE OF HB3167 THE CITY NO LONGER HAS FLEXIBILITY WITH REGARD TO ITS APPROVAL PROCESS, AND FAILURE TO ADDRESS ANY OF STAFF'S COMMENTS BY THE DATE PROVIDED ON THE DEVELOPMENT CALENDAR WILL RESULT IN THE DENIAL OF YOUR CASE.

OWNER/APPLICANT/AGENT INFORMATION [PLEASE PRINT/CHECK THE PRIMARY CONTACT/ORIGINAL SIGNATURES ARE REQUIRED]

<input type="checkbox"/> OWNER	Creekside Commons Crossing LP	<input checked="" type="checkbox"/> APPLICANT	The Dimension Group
CONTACT PERSON	Michael Hampton	CONTACT PERSON	Keaton Mai
ADDRESS	[REDACTED]	ADDRESS	[REDACTED]
CITY, STATE & ZIP	[REDACTED]	CITY, STATE & ZIP	[REDACTED]
PHONE	[REDACTED]	PHONE	[REDACTED]
E-MAIL	[REDACTED]	E-MAIL	[REDACTED]

NOTARY VERIFICATION [REQUIRED]

BEFORE ME, THE UNDERSIGNED AUTHORITY, ON THIS DAY PERSONALLY APPEARED Michael Hampton [OWNER] THE UNDERSIGNED, WHO STATED THE INFORMATION ON THIS APPLICATION TO BE TRUE AND CERTIFIED THE FOLLOWING:


I HEREBY CERTIFY THAT I AM THE OWNER FOR THE PURPOSE OF THIS APPLICATION; ALL INFORMATION SUBMITTED HEREIN IS TRUE AND CORRECT; AND THE APPLICATION FEE OF \$ 565.72 TO COVER THE COST OF THIS APPLICATION, HAS BEEN PAID TO THE CITY OF ROCKWALL ON THIS THE 16th DAY OF JANUARY, 2026 BY SIGNING THIS APPLICATION, I AGREE THAT THE CITY OF ROCKWALL (I.E. "CITY") IS AUTHORIZED AND PERMITTED TO PROVIDE INFORMATION CONTAINED WITHIN THIS APPLICATION TO THE PUBLIC. THE CITY IS ALSO AUTHORIZED AND PERMITTED TO REPRODUCE ANY COPYRIGHTED INFORMATION SUBMITTED IN CONJUNCTION WITH THIS APPLICATION, IF SUCH REPRODUCTION IS ASSOCIATED OR IN RESPONSE TO A REQUEST FOR PUBLIC INFORMATION."


GIVEN UNDER MY HAND AND SEAL OF OFFICE ON THIS THE 16th DAY OF January, 2026

OWNER'S SIGNATURE

[Signature of Michael Hampton]
[Signature of Kathy Granberg]

NOTARY PUBLIC IN AND FOR THE STATE OF TEXAS








City of Rockwall

Planning & Zoning Department
 385 S. Goliad Street
 Rockwall, Texas 75087
 (P): (972) 771-7745
 (W): www.rockwall.com

The City of Rockwall GIS maps are continually under development and therefore subject to change without notice. While we endeavor to provide timely and accurate information, we make no guarantees. The City of Rockwall makes no warranty, express or implied, including warranties of merchantability and fitness for a particular purpose. Use of the information is the sole responsibility of the user.






PARCEL CURVE TABLE

CURVE #	LENGTH	RADIUS	DELTA	CHORD
C1	81.75'	1155.00'	4°03'19"	S58° 43' 21"W 81.73'
C2	160.34'	1110.00'	8°16'36"	S56° 38' 44"W 160.20'
C3	28.00'	36.00'	44°33'46"	S66° 35' 16"W 27.30'

PARCEL LINE TABLE

LINE #	LENGTH	DIRECTION
L1	114.68'	S33°19'17"E
L2	25.09'	S29°29'58"E
L3	269.61'	S44°06'48"W
L4	228.23'	N45°52'18"W
L5	269.64'	N44°08'20"E
L6	22.85'	N45°51'55"W
L7	121.80'	N1°07'51"W
L8	217.17'	S1°14'47"E
L9	45.15'	S88°52'09"W
L10	21.83'	S44°43'37"W
L11	169.64'	N45°51'55"W
L12	81.31'	S45°51'55"E



LEGEND:

IRF IRON ROD FOUND
PC "TXDOT" IRON ROD FOUND WITH PINK CAP STAMPED "TXDOT"
YC "TXHS" IRON ROD FOUND WITH YELLOW CAP STAMPED "TXHS"
IRS IRON ROD SET WITH YELLOW CAP STAMPED "TXHS"
-CM- CONTROLLING MONUMENT
D.R.R.C.T. DEED RECORDS, ROCKWALL COUNTY, TEXAS
M.R.R.C.T. MAP RECORDS, ROCKWALL COUNTY, TEXAS
O.P.R.R.C.T. OFFICIAL PUBLIC RECORDS, ROCKWALL COUNTY, TEXAS
INST. NO. INSTRUMENT NUMBER
VOL., PG. VOLUME, PAGE

ENGINEER
THE DIMENSION GROUP
10755 SANDHILL ROAD
DALLAS, TEXAS 75238
attn: KEATON MAI

OWNER
CREEKSIDE COMMONS CROSSING, LP
10755 SANDHILL ROAD
DALLAS, TEXAS 75238



SURVEYOR
TEXAS HERITAGE
SURVEYING, LLC

10610 Metric Drive, Suite 124, Dallas, TX 75243
Office 214-340-9700 Fax 214-340-9710
txheritage.com
Firm No. 10169300

FINAL PLAT
LOTS 19-21, BLOCK A
CREEKSIDE COMMONS ADDITION
BEING A REPLAT OF
LOTS 15, 16, & 18, BLOCK A,
CREEKSIDE COMMONS ADDITION
BEING 3 LOTS
13.286 ACRES / 578,731 SF
SITUATED IN THE
W. W. FORD SURVEY, ABSTRACT NO. 80
CITY OF ROCKWALL, ROCKWALL COUNTY, TEXAS

PARCEL CURVE TABLE				
CURVE #	LENGTH	RADIUS	DELTA	CHORD
C4	28.00'	36.00'	44°33'46"	S66° 35' 16"W 27.30'
C5	5.02'	25.00'	11°30'57"	N5° 51' 30"W 5.02'
C6	39.77'	25.00'	91°09'19"	S45° 40' 41"E 35.71'
C7	39.22'	25.00'	89°53'04"	S43° 48' 41"W 35.32'
C8	47.03'	20.00'	134°44'04"	S21° 30' 07"W 36.92'
C9	28.32'	20.00'	81°08'24"	S86° 26' 06"E 26.02'
C10	21.46'	49.00'	25°05'14"	N65° 32' 19"E 21.28'
C11	9.22'	49.00'	10°47'12"	N83° 28' 33"E 9.21'

PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L16	15.00'	N44°07'42"E
L17	52.07'	N45°52'18"W
L18	20.00'	N45°54'27"W
L19	51.04'	N43°59'07"E
L20	22.38'	N1°00'53"W
L21	153.66'	N43°59'07"E
L22	11.87'	N45°30'22"W
L23	19.90'	N44°29'38"E
L24	11.70'	S46°00'53"E
L25	31.45'	N43°59'07"E

PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L26	35.20'	N46°00'53"W
L27	20.00'	N44°08'05"E
L28	35.15'	S45°51'55"E
L29	12.34'	N43°59'07"E
L30	35.29'	N88°52'09"E
L31	5.01'	N1°06'12"W
L32	20.00'	N88°52'09"E
L33	5.00'	S1°06'12"E
L34	453.33'	N88°52'09"E
L35	301.80'	S54°13'54"E



PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L36	18.16'	S29°14'52"E
L37	20.00'	S60°45'12"W
L38	13.73'	S29°14'52"E
L39	290.70'	N54°13'54"W
L40	493.69'	S88°52'09"W
L41	220.81'	S43°59'07"W
L42	22.38'	S1°00'53"E
L43	59.36'	S43°59'07"W
L44	134.56'	N88°52'09"E
L45	20.01'	N2°38'25"W

PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L46	586.72'	S88°52'09"W
L47	20.00'	S1°13'55"E
L48	25.89'	S44°06'48"W
L49	10.00'	S44°06'48"W
L50	16.89'	N45°53'12"W
L51	15.09'	S89°06'48"W
L52	200.57'	N45°53'12"W
L53	10.32'	N44°08'20"E
L54	196.43'	S45°47'38"E
L55	15.09'	N89°06'48"E


PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L56	21.03'	S45°53'12"E
L57	12.00'	N88°45'13"E
L58	193.03'	N88°45'13"E
L59	5.00'	S1°14'47"E
L60	192.63'	S88°45'13"W
L61	168.03'	N88°45'13"E
L62	24.00'	S1°14'47"E
L63	168.18'	S88°45'13"W
L64	74.45'	N1°07'51"W
L65	10.00'	N88°45'13"E

PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L66	182.71'	S1°14'47"E
L67	9.99'	S88°52'09"W
L68	12.02'	S1°14'47"E
L69	34.64'	S88°52'09"W
L70	71.67'	N45°51'55"W
L71	44.60'	N88°52'09"E
L72	11.98'	S1°14'47"E

PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L13	22.85'	N45°51'55"W
L14	45.15'	S88°52'09"W
L15	21.83'	S44°43'37"W




- LEGEND:
- IRF IRON ROD FOUND
 - PC "TXDOT" IRON ROD FOUND WITH PINK CAP STAMPED "TXDOT"
 - IRS IRON ROD SET WITH YELLOW CAP STAMPED "TXHS"
 - <CM> CONTROLLING MONUMENT
 - D.R.R.C.T. DEED RECORDS, ROCKWALL COUNTY, TEXAS
 - M.R.R.C.T. MAP RECORDS, ROCKWALL COUNTY, TEXAS
 - O.P.R.R.C.T. OFFICIAL PUBLIC RECORDS, ROCKWALL COUNTY, TEXAS
 - INST. NO. INSTRUMENT NUMBER
 - VOL., PG. VOLUME, PAGE
 - ESMT. EASEMENT
 - WSEL WATER SURFACE ELEVATION
 - MIN. F.F.E. MINIMUM FINISHED FLOOR ELEVATION



BLOCK 1
SOMERSET PARK
INST. NO. 2018000001707
O.P.R.R.C.T.

BLOCK A
EDWARDS ACRES SUBDIVISION
INST. NO. 2014000006510
O.P.R.R.C.T.



SYLVANPARK DRIVE
(83' RIGHT-OF-WAY)

SANITARY SEWER ESMT.
INST. NO. 20170000002409
O.P.R.R.C.T.


10' ELECTRIC &
TELEPHONE ESMT.
INST. NO. 2014000006510
O.P.R.R.C.T.

15' WATER LINE ESMT.
INST. NO. 2014000006510
O.P.R.R.C.T.

BLOCK A
EDWARDS ACRES SUBDIVISION
INST. NO. 2014000006510
O.P.R.R.C.T.

10' ELECTRIC &
TELEPHONE ESMT.
INST. NO. 2014000006510
O.P.R.R.C.T.

15' WATER LINE ESMT.
INST. NO. 2014000006510
O.P.R.R.C.T.



STATE HIGHWAY 549
(VARIABLE WIDTH RIGHT-OF-WAY)

N 88°45'13" E 1358.95'

100-YR WSEL = 519.58

15' BUILDING LINE
INST. NO. 20230000008813
O.P.R.R.C.T.

LOT 21
476,460 SQ. FT.
10.938 ACRES
MIN. F.F.E. = 528.93

DETENTION ESMT.
INST. NO. 20240000004925
O.P.R.R.C.T.

SANITARY SEWER ESMT.
INST. NO. 20150000003475
D.R.R.C.T.

SANITARY SEWER ESMT.
INST. NO. 20150000003475
D.R.R.C.T.

30' WASTEWATER ESMT.
INST. NO. 20230000008813
O.P.R.R.C.T.


15' WATER PIPELINE ESMT.
R.C.H. WATER SUPPLY CORP.
VOL. 64, PG. 319
D.R.R.C.T.

MIN. F.F.E. = 521.54

20' LANDSCAPE BUFFER
INST. NO. 20230000008813
O.P.R.R.C.T.

MATCH LINE PG 2

WILLIAM W. FORD SURVEY,
ABSTRACT NO. 80




100-YR WSEL = 526.93

20' WATER ESMT.
INST. NO. 20230000008813
O.P.R.R.C.T.

10' UTILITY ESMT.
INST. NO. 20230000008813
O.P.R.R.C.T.

25' BUILDING LINE
INST. NO. 20230000008813
O.P.R.R.C.T.



CREEKSIDE COMMONS ADDITION
BLOCK A

578,731 SQ. FT.
13.286 ACRES

CREEKSIDE COMMONS CROSSING, LP
INST. NO. 20220000021201
O.P.R.R.C.T.

20' DRAINAGE ESMT.
INST. NO. 20240000004925
O.P.R.R.C.T.


1/2" IRF
YC *TXHS*
S 29°29'58" E
25.09'

S 60°46'14" W 382.65'

STATE HIGHWAY 549
(VARIABLE WIDTH RIGHT-OF-WAY)

MATCH LINE PG 5

MATCH LINE PG 2



VISIBILITY ESMT.
INST. NO. 2024000004925
O.P.R.R.C.T.

VISIBILITY ESMT.
INST. NO. 2024000004925
O.P.R.R.C.T.

1/2" IRF
YC 'SUMMIT'

STATE OF TEXAS
INST. NO. 20180000021509
O.P.R.R.C.T.

STATE HIGHWAY 205
(VARIABLE WIDTH RIGHT-OF-WAY)

STATE OF TEXAS
INST. NO. 20210000017067
O.P.R.R.C.T.

LOT 19
S 44°06'48" W
269.61'

LOT 14
BLOCK A
CREEKSIDE COMMONS
INST. NO. 2024000004925
O.P.R.R.C.T.

20' DRAINAGE ESMT.
INST. NO. 2024000004925
O.P.R.R.C.T.

24' FIRELANE, ACCESS,
& UTILITY ESMT.
INST. NO. 20230000008813
O.P.R.R.C.T.

549 CROSSING, LP
INST. NO. 20210000028395
O.P.R.R.C.T.

LOT 1
BLOCK A
CREEKSIDE COMMONS
INST. NO. 20230000008813
O.P.R.R.C.T.

15' UTILITY ESMT.
INST. NO. 20230000008813
O.P.R.R.C.T.

25' BUILDING LINE
INST. NO. 20230000008813
O.P.R.R.C.T.

20' LANDSCAPE BUFFER
INST. NO. 20230000008813
O.P.R.R.C.T.

DETENTION ESMT.
INST. NO. 20230000008813
O.P.R.R.C.T.

GENERAL NOTES:

1) Subdivider's Statement: Selling a portion of this addition by metes and bounds is unlawful and a violation of the Subdivision Ordinance of the City of Rockwall and Chapter 212, Municipal Regulation of Subdivisions and Property Development, of the Texas Local Government Code, and shall be subject to the City of Rockwall withholding utilities and building permits.

2) Public Improvement Statement: It shall be the policy of the City of Rockwall to withhold issuing building permits until all streets, water, sewer and storm drainage systems have been accepted by the City. The approval of a subdivision plat by the City does not constitute any representation, assurance or guarantee that any building within such plat shall be approved, authorized or permit issued, nor shall such approval constitute any representation, assurance or guarantee by the City of Rockwall of the adequacy and availability for water and sanitary sewer for personal use and fire protection within such subdivision plat, as required under the Subdivision Ordinance of the City of Rockwall.

3) Drainage and Detention Easements: Property owner shall be responsible for maintaining, repairing, and replacing and shall bear sole liability of all systems within the drainage and detention easements.

4) Fire Lanes: All Fire Lanes will be constructed, maintained, repaired and replaced by the property owner. Fire Lanes shall be constructed in accordance with the approved Civil Engineering Plans for both on-site and off-site Fire Lane improvements.

5) Street Appurtenances: All decorative signage, posts, or lights installed in public right-of-way shall be installed, maintained, repaired, and replaced by the homeowner's association (HOA).

6) Bearings are based upon the Texas State Plane Coordinate System, Texas North Central Zone (4202), North American Datum of 1983 (2011).

7) The purpose of this replat is to create easements and change lot boundary lines.

8) Benchmarks:

COR-8: Aluminum disk stamped "City of Rockwall Survey Monument" at the northerly intersection of Silver View Lane and Diamond Way Drive ± 1 foot north of curb line in center of curve.
N= 7,018,063.113; E= 2,609,533.682; Elevation= 600.48'

COR-9: Brass disk stamped "City of Rockwall Survey Monument" on the south side of Discovery Boulevard at the southeaster corner of curb inlet ± 180 feet east intersection of Discovery/Corporate.
N= 7,020,550.132; E= 2,607,463.893; Elevation= 595.63'


9) Zoning: Commercial (C) District

10) Base Flood Elevation information per FEMA GIS, FIRM Panel #48397C0045L.

11) All Visibility Easements are 30'x30' unless otherwise noted.

12) WSEL information based upon Floodplain / Detention Study NDMCE No. 23-014 by Nathan D. Maier Consulting Engineers, Inc. completed December of 2023.

MATCH LINE PG 5



MATCH LINE PG 3

MATCH LINE PG 4

OWNER'S CERTIFICATE:

STATE OF TEXAS
COUNTY OF ROCKWALL

WHEREAS, Creekside Commons Crossing, LP is the owner of that tract of land situated in the William W. Ford Survey, Abstract No. 80, City of Rockwall, Rockwall County, Texas, being Lots 15, 16, & 18, Block A of Creekside Commons, an addition to the City of Rockwall, Rockwall County, Texas according to the plat thereof recorded in Instrument Number 2024000004925 of the Official Public Records of Rockwall County, Texas, and being a part of that tract of land described in Special Warranty Deed to Creekside Commons Crossing, LP recorded in Instrument Number 2022000021201 of the Official Public Records of Rockwall County, Texas, and being more particularly described by metes and bounds as follows:

Commencing at a 1/2 inch iron rod with yellow plastic cap stamped "TXHS" found for corner, said corner being in the northeast corner of that tract of land described as Parcel 1 Part 1 in deed to the State of Texas recorded in Instrument Number 2018000021509 of the Official Public Records of Rockwall County, Texas, said corner also being the northwest corner of Lot 17, Block A of said Creekside Commons Addition, said corner also being in the south right-of-way line of existing State Highway 549 (variable width right-of-way);

Thence North 88 degrees 45 minutes 13 seconds East, along the south right-of-way line of said existing State Highway 549, a distance of 491.43 feet to an "X" found for corner, said corner being the northeast corner of said Lot 17, Block A, said corner being the POINT OF BEGINNING;

Thence North 88 degrees 45 minutes 13 seconds East, along the south right-of-way line of said existing State Highway 549, a distance of 1,358.95 feet to a 5/8 inch iron rod with pink plastic cap stamped "TXDOT" found for corner, said corner being the northwest corner of that tract of land described as Parcel 1 Part 2 in deed to the State of Texas recorded in Instrument Number 2018000021509 of the Official Public Records of Rockwall County, Texas, said corner also being the most northerly northeast corner of said Lot 18, Block A, said corner also being in a northwest right-of-way line of new State Highway 549 (variable width right-of-way);

Thence, along the northwest line of said State of Texas Parcel 1 Part 2 tract and along the northwest line of said new State Highway 549, the following courses and distances:

Thence South 33 degrees 19 minutes 17 seconds East, a distance of 114.68 feet to a 1/2 inch iron rod with yellow plastic cap stamped "TXHS" found for corner, said corner being the beginning of a non-tangent curve to the right, having a delta of 04 degrees 03 minutes 19 seconds, a radius of 1,155.00 feet and a chord bearing and distance of South 58 degrees 43 minutes 21 seconds West, 81.73 feet;

Thence, in a southwesterly direction, along said curve to the right, an arc length of 81.75 feet to a 5/8 inch iron rod with pink plastic cap stamped "TXDOT" found for corner;

Thence South 60 degrees 46 minutes 14 seconds West, a distance of 382.65 feet to a 1/2 inch iron rod with yellow plastic cap stamped "TXHS" found for corner;

Thence South 29 degrees 29 minutes 58 seconds East, a distance of 25.09 feet to a 1/2 inch iron rod with yellow plastic cap stamped "TXHS" found for corner;

Thence South 60 degrees 45 minutes 08 seconds West, a distance of 437.07 feet to a "X" found for corner, said corner being the beginning of a non-tangent curve to the left, having a delta of 08 degrees 16 minutes 36 seconds, a radius of 1,110.00 feet and a chord bearing and distance of South 56 degrees 38 minutes 44 seconds West, 160.20 feet;

Thence, in a southwesterly direction, along said curve to the left, an arc length of 160.34 feet to a 1/2 inch iron rod with yellow plastic cap stamped "TXHS" found for corner, said corner being the east corner of Lot 1, Block A of said Creekside Commons, an addition to the City of Rockwall, Rockwall County, Texas according to the plat thereof recorded in Instrument Number 2023000008813 of the Official Public Records of Rockwall County, Texas;

Thence North 45 degrees 53 minutes 13 seconds West, along the northeast line of said Lot 1, Block A, a distance of 261.06 feet to an "X" found for corner, said corner being the north corner of said Lot 1, Block A, said corner also being the east corner of Lot 14, Block A of said Creekside Commons Addition (Inst. No. 2024000004925);

Thence North 45 degrees 51 minutes 55 seconds West, along the northeast line of said Lot 14, Block A, a distance of 202.16 feet to an "X" found for corner, said corner being the north corner of said Lot 14, Block A;


Thence South 44 degrees 06 minutes 48 seconds West, along the northwest line of said Lot 14, Block A, a distance of 269.61 feet to a 1/2 inch iron rod with cap stamped "SUMMIT" found for corner, said corner being the west corner of said Lot 14, Block A, said corner also being in the northeast line of said State of Texas Parcel 1 Part 1 tract;

Thence North 45 degrees 52 minutes 18 seconds West, along a northeast line of said State of Texas Parcel 1 Part 1 tract, a distance of 228.23 feet to a 1/2 inch iron rod with yellow plastic cap stamped "TXHS" found for corner, said corner being the south corner of said Lot 17, Block A;

Thence North 44 degrees 08 minutes 20 seconds East, along the southeast line of said Lot 17, Block A, a distance of 269.64 feet to an "X" found for corner, said corner being the east corner of said Lot 17, Block A;

Thence North 45 degrees 51 minutes 55 seconds West, along the easterly line of said Lot 17, Block A, a distance of 22.85 feet to an "X" found for corner;

Thence North 01 degrees 07 minutes 51 seconds West, along the easterly line of said Lot 17, Block A, a distance of 121.80 feet to the POINT OF BEGINNING and containing 578,731 square feet or 13.286 acres of land.



OWNER'S DEDICATION:

NOW THEREFORE, KNOW ALL MEN BY THESE PRESENTS:

STATE OF TEXAS
COUNTY OF ROCKWALL

I the undersigned owner of the land shown on this plat, and designated herein as the CREEKSIDE COMMONS ADDITION subdivision to the City of Rockwall, Texas, and whose name is subscribed hereto, hereby dedicate to the use of the public forever all streets, alleys, parks, water courses, drains, easements and public places thereon shown on the purpose and consideration therein expressed. I further certify that all other parties who have a mortgage or lien interest in the CREEKSIDE COMMONS ADDITION subdivision have been notified and signed this plat. I understand and do hereby reserve the easement strips shown on this plat for the purposes stated and for the mutual use and accommodation of all utilities desiring to use or using same. I also understand the following;

1. No buildings shall be constructed or placed upon, over, or across the utility easements as described herein.
2. Any public utility shall have the right to remove and keep removed all or part of any buildings, fences, trees, shrubs, or other growths or improvements which in any way endanger or interfere with construction, maintenance or efficiency of their respective system on any of these easement strips; and any public utility shall at all times have the right of ingress or egress to, from and upon the said easement strips for purposes of construction, reconstruction, inspecting, patrolling, maintaining, and either adding to or removing all or part of their respective system without the necessity of, at any time, procuring the permission of anyone.
3. The City of Rockwall will not be responsible for any claims of any nature resulting from or occasioned by the establishment of grade of streets in the subdivision.
4. The developer/property owner and subdivision engineer shall bear total responsibility for storm drain improvements.
5. The developer/property owner shall be responsible for the necessary facilities to provide drainage patterns and drainage controls such that properties within the drainage area are not adversely affected by storm drainage from the development.
6. No house dwelling unit, or other structure shall be constructed on any lot in this addition by the owner or any other person until the developer and/or owner has complied with all requirements of the Subdivision Regulations of the City of Rockwall regarding improvements with respect to the entire block on the street or streets on which property abuts, including the actual installation of streets with the required base and paving, curb and gutter, water and sewer, drainage structures, storm structures, storm sewers, and alleys, all according to the specifications of the City of Rockwall; or

Until an escrow deposit, sufficient to pay for the cost of such improvements, as determined by the city's engineer and/or city administrator, computed on a private commercial rate basis, has been made with the city secretary, accompanied by an agreement signed by the developer and/or owner, authorizing the city to make such improvements at prevailing private commercial rates, or have the same made by a contractor and pay for the same out of the escrow deposit, should the developer and/or owner fail or refuse to install the required improvements within the time stated in such written agreement, but in no case shall the City be obligated to make such improvements itself. Such deposit may be used by the owner and/or developer as progress payments as the work progresses in making such improvements by making certified requisitions to the city secretary, supported by evidence of work done; or

Until the developer and/or owner files a corporate surety bond with the city secretary in a sum equal to the cost of such improvements for the designated area, guaranteeing the installation thereof within the time stated in the bond, which time shall be fixed by the city council of the City of Rockwall.

I further acknowledge that the dedications and/or exaction's made herein are proportional to the impact of the Subdivision upon the public services required in order that the development will comport with the present and future growth needs of the City; I, my successors and assigns hereby waive any claim, damage or cause of action that I may have as a result of the dedication of exactions made herein.

Creekside Commons Crossing, LP

Jassem Setayesh
President/CEO

STATE OF TEXAS
COUNTY OF DALLAS

BEFORE ME, the undersigned authority, on this day personally appeared Jassem Setayesh, a Texas limited liability company, known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that he executed the same for the purposes and considerations therein stated.

GIVEN UNDER MY HAND AND SEAL OF OFFICE, this _____ day of _____, 2026.

Notary Signature

SURVEYORS CERTIFICATE:

I, J. R. January, do hereby certify that I prepared this plat from an actual and accurate survey of the land, and that the corner monuments shown thereon were properly placed under my personal supervision.

J. R. January, R.P.L.S. No. 5382

APPROVED: I hereby certify that the above and foregoing Subdivision Plat was reviewed by the Planning and Zoning Commission and approved by the City Council of the City of Rockwall, Texas for the preparation of a Final Plat on the _____ day of _____, 2026.

Mayor of the City of Rockwall

Planning and Zoning Chairman

City Secretary

City Engineer

ENGINEER
THE DIMENSION GROUP
10755 SANDHILL ROAD
DALLAS, TEXAS 75238
attn: KEATON MAI


OWNER
CREEKSIDE COMMONS CROSSING, LP
10755 SANDHILL ROAD
DALLAS, TEXAS 75238



SURVEYOR
TEXAS HERITAGE
SURVEYING, LLC
10610 Metric Drive, Suite 124, Dallas, TX 75243
Office 214-340-9700 Fax 214-340-9710
txheritage.com
Firm No. 10169300

FINAL PLAT
LOTS 19-21, BLOCK A
CREEKSIDE COMMONS ADDITION
BEING A REPLAT OF
LOTS 15, 16, & 18, BLOCK A,
CREEKSIDE COMMONS ADDITION
BEING 3 LOTS
13.286 ACRES / 578,731 SF
SITUATED IN THE
W. W. FORD SURVEY, ABSTRACT NO. 80
CITY OF ROCKWALL, ROCKWALL COUNTY, TEXAS

STATE HIGHWAY 549 (VARIABLE WIDTH RIGHT-OF-WAY)



LANDSCAPE CALCULATIONS

PERMITTING AUTHORITY: CITY OF ROCKWALL, TX
 ZONING: C
 ADJACENT ZONING: C

OVERALL
 TOTAL SITE AREA: 40,751 SF
 LANDSCAPE AREA REQUIRED: 8,150 SF (20% OF SITE AREA)
 LANDSCAPE AREA PROVIDED: 8,594 SF
 % OF REQ. AREA IN FRONT AND SIDE YARDS: 91.7% (MIN 50%)
 IMPERVIOUS AREA ON SITE: 32,157 SF

LANDSCAPE BUFFER ALONG S FM 549, MIN. WIDTH 10'
 LENGTH OF FRONTAGE: 192 LF (NOT INCL WIDTH OF DRIVEWAY)
 CANOPY TREES REQUIRED: 4 CANOPY TREES (1 PER 50 LF)
 CANOPY TREES PROVIDED: 4 CANOPY TREES
 ACCENT TREES REQUIRED: 4 ACCENT TREES (1 PER 50 LF)
 ACCENT TREES PROVIDED: 4 ACCENT TREES
 SHRUBS REQUIRED: 48 SHRUBS PROVIDED
 BERM REQUIRED: 30' BERM - SEE CIVIL PLANS FOR FINAL GRADES
 NOTE: ADDITIONAL SHRUBS HAVE BEEN ADDED TO PROVIDE AN ENHANCED SCREEN AT THE DRIVE THROUGH.

PARKING LOT HEAD LIGHT SCREENING
 PROVIDED AS REQUIRED.

PARKING LOT LANDSCAPING
 SIZE OF PARKING AND MANEUVERING AREA: 22,382 SF
 QUANTITY OF PARKING SPACES: 27 PARKING SPACES
 CANOPY TREES REQUIRED: 3 CANOPY TREES (1 PER 10 PARKING SPACES)
 CANOPY TREES PROVIDED: 3 CANOPY TREES
 NOTE: NO PARKING SPACE MAY BE MORE THAN 80 LF FROM THE TRUNK OF A CANOPY TREE.

GENERAL GRADING AND PLANTING NOTES

- BY SUBMITTING A PROPOSAL FOR THE LANDSCAPE PLANTING SCOPE OF WORK, THE CONTRACTOR CONFIRMS THAT HE HAS READ, AND WILL COMPLY WITH, THE ASSOCIATED NOTES, SPECIFICATIONS, AND DETAILS WITH THIS PROJECT.
- THE GENERAL CONTRACTOR IS RESPONSIBLE FOR REMOVING ALL EXISTING VEGETATION (EXCEPT WHERE NOTED TO REMAIN).
- IN THE CONTEXT OF THESE PLANS, NOTES, AND SPECIFICATIONS, "FINISH GRADE" REFERS TO THE FINAL ELEVATION OF THE SOIL SURFACE (NOT TOP OF MULCH) AS INDICATED ON THE GRADING PLANS.
 - BEFORE STARTING WORK, THE LANDSCAPE CONTRACTOR SHALL VERIFY THAT THE ROUGH GRADES OF ALL LANDSCAPE AREAS ARE WITHIN +/-0.1' OF FINISH GRADE. SEE SPECIFICATIONS FOR MORE DETAILED INSTRUCTION ON TURF AREA AND PLANTING BED PREPARATION.
 - CONSTRUCT AND MAINTAIN FINISH GRADES AS SHOWN ON GRADING PLANS, AND CONSTRUCT AND MAINTAIN SLOPES AS RECOMMENDED BY THE GEOTECHNICAL REPORT. ALL LANDSCAPE AREAS SHALL HAVE POSITIVE DRAINAGE AWAY FROM STRUCTURES AT THE MINIMUM SLOPE SPECIFIED IN THE REPORT AND ON THE GRADING PLANS, AND AREAS OF POTENTIAL PONDING SHALL BE REGRADED TO BLEND IN WITH THE SURROUNDING GRADES AND ELIMINATE PONDING POTENTIAL.
 - THE LANDSCAPE CONTRACTOR SHALL DETERMINE WHETHER OR NOT THE EXPORT OF ANY SOIL WILL BE NEEDED, TAKING INTO ACCOUNT THE ROUGH GRADE PROVIDED, THE AMOUNT OF SOIL AMENDMENTS TO BE ADDED (BASED ON A SOIL TEST, PER SPECIFICATIONS), AND THE FINISH GRADES TO BE ESTABLISHED.
 - ENSURE THAT THE FINISH GRADE IN SHRUB AREAS IMMEDIATELY ADJACENT TO WALKS AND OTHER WALKING SURFACES, AFTER INSTALLING SOIL AMENDMENTS, IS 3" BELOW THE ADJACENT FINISH SURFACE, IN ORDER TO ALLOW FOR PROPER MULCH DEPTH. TAPER THE SOIL SURFACE TO MEET FINISH GRADE, AS SPECIFIED ON THE GRADING PLANS, AT APPROXIMATELY 18" AWAY FROM THE WALKS.
 - ENSURE THAT THE FINISH GRADE IN TURF AREAS IMMEDIATELY ADJACENT TO WALKS AND OTHER WALKING SURFACES, AFTER INSTALLING SOIL AMENDMENTS, IS 1" BELOW THE FINISH SURFACE OF THE WALKS. TAPER THE SOIL SURFACE TO MEET FINISH GRADE, AS SPECIFIED ON THE GRADING PLANS, AT APPROXIMATELY 18" AWAY FROM THE WALKS.
 - SHOULD ANY CONFLICTS AND/OR DISCREPANCIES ARISE BETWEEN THE GRADING PLANS, GEOTECHNICAL REPORT, THESE NOTES AND PLANS, AND ACTUAL CONDITIONS, THE CONTRACTOR SHALL IMMEDIATELY BRING SUCH ITEMS TO THE ATTENTION OF THE LANDSCAPE ARCHITECT, GENERAL CONTRACTOR, AND OWNER.
- ALL PLANT LOCATIONS ARE DIAGRAMMATIC. ACTUAL LOCATIONS SHALL BE VERIFIED WITH THE LANDSCAPE ARCHITECT OR DESIGNER PRIOR TO PLANTING. THE LANDSCAPE CONTRACTOR SHALL ENSURE THAT ALL REQUIREMENTS OF THE PERMITTING AUTHORITY ARE MET (I.E., MINIMUM PLANT QUANTITIES, PLANTING METHODS, TREE PROTECTION METHODS, ETC.).
 - THE LANDSCAPE CONTRACTOR IS RESPONSIBLE FOR DETERMINING PLANT QUANTITIES; PLANT QUANTITIES SHOWN ON LEGENDS AND CALLOUTS ARE FOR GENERAL INFORMATION ONLY. IN THE EVENT OF A DISCREPANCY BETWEEN THE PLAN AND THE PLANT LEGEND, THE PLANT QUANTITY AS SHOWN ON THE PLAN (FOR INDIVIDUAL SYMBOLS) OR CALLOUT (FOR GROUNDCOVER PATTERNS) SHALL TAKE PRECEDENCE.
 - NO SUBSTITUTIONS OF PLANT MATERIALS SHALL BE ALLOWED WITHOUT THE WRITTEN PERMISSION OF THE LANDSCAPE ARCHITECT. IF SOME OF THE PLANTS ARE NOT AVAILABLE, THE LANDSCAPE CONTRACTOR SHALL NOTIFY THE LANDSCAPE ARCHITECT IN WRITING (VIA PROPER CHANNELS).
 - THE CONTRACTOR SHALL, AT A MINIMUM, PROVIDE REPRESENTATIVE PHOTOS OF ALL PLANTS PROPOSED FOR THE PROJECT. THE CONTRACTOR SHALL ALLOW THE LANDSCAPE ARCHITECT AND THE OWNER/OWNER'S REPRESENTATIVE TO INSPECT, AND APPROVE OR REJECT, ALL PLANTS DELIVERED TO THE JOBSITE. REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS FOR SUBMITTALS.
- CONTRACTOR SHALL PROVIDE AND INSTALL SOLID SOD IN ALL RIGHT-OF-WAYS AND PARKWAYS (UNLESS NOT ALLOWED BY THE LOCAL JURISDICTION) AND SHALL PROVIDE WATERING AND MAINTENANCE UNTIL THE TURF IS ESTABLISHED AND HAS BEEN ACCEPTED BY OWNER.
- THE CONTRACTOR SHALL MAINTAIN THE LANDSCAPE IN A HEALTHY CONDITION FOR 90 DAYS AFTER ACCEPTANCE BY THE OWNER. REFER TO SPECIFICATIONS FOR CONDITIONS OF ACCEPTANCE FOR THE START OF THE MAINTENANCE PERIOD, AND FOR FINAL ACCEPTANCE AT THE END OF THE MAINTENANCE PERIOD.
- SEE SPECIFICATIONS AND DETAILS FOR FURTHER REQUIREMENTS.

ROOT BARRIERS

THE CONTRACTOR SHALL INSTALL ROOT BARRIERS NEAR ALL NEWLY-PLANTED TREES THAT ARE LOCATED WITHIN FIVE (5) FEET OF PAVING, CURBS, WATER, STORM, OR SANITARY SEWER UTILITIES. ROOT BARRIERS SHALL BE "CENTURY" OR "DEEP-ROOT" 24" DEEP PANELS (OR EQUAL). BARRIERS SHALL BE LOCATED IMMEDIATELY ADJACENT TO HARDSCAPE. INSTALL PANELS PER MANUFACTURER'S RECOMMENDATIONS. UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR USE ROOT BARRIERS OF A TYPE THAT COMPLETELY ENCIRCLE THE ROOTBALL.

MULCHES

AFTER ALL PLANTING IS COMPLETE, CONTRACTOR SHALL INSTALL 2" THICK LAYER OF 1-1/2" SHREDDED WOOD MULCH, NATURAL (UNDYED), OVER LANDSCAPE FABRIC IN ALL PLANTING AREAS (EXCEPT FOR TURF AND SEEDED AREAS). CONTRACTOR SHALL SUBMIT SAMPLES OF ALL MULCHES TO LANDSCAPE ARCHITECT AND OWNER FOR APPROVAL PRIOR TO CONSTRUCTION. ABSOLUTELY NO EXPOSED GROUND SHALL BE LEFT SHOWING ANYWHERE ON THE PROJECT AFTER MULCH HAS BEEN INSTALLED (SUBJECT TO THE CONDITIONS AND REQUIREMENTS OF THE "GENERAL GRADING AND PLANTING NOTES" AND SPECIFICATIONS).

PLANTING & IRRIGATION GUARANTEE

THE LANDSCAPE CONTRACTOR SHALL GUARANTEE THAT ALL NEWLY INSTALLED AND EXISTING PLANTS SHALL SURVIVE FOR ONE YEAR AFTER FINAL OWNER ACCEPTANCE OF THE INSTALLATION WORK. THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR APPROPRIATE WATERING OF THE LANDSCAPE THROUGH INSTALLATION OF A PROPERLY DESIGNED IRRIGATION SYSTEM. THE OWNER SHALL APPROVE THE SYSTEM DESIGN BEFORE INSTALLATION OF PLANTS OR IRRIGATION.

IRRIGATION CONCEPT

- AN AUTOMATIC IRRIGATION SYSTEM SHALL BE INSTALLED AND OPERATIONAL BY THE TIME OF FINAL INSPECTION. THE ENTIRE IRRIGATION SYSTEM SHALL BE INSTALLED BY A LICENSED AND QUALIFIED IRRIGATION CONTRACTOR.
- THE IRRIGATION SYSTEM WILL MEET THE REQUIREMENTS OF THE UDC.
- THE IRRIGATION SYSTEM WILL OPERATE ON POTABLE WATER, AND THE SYSTEM WILL HAVE APPROPRIATE BACKFLOW PREVENTION DEVICES INSTALLED TO PREVENT CONTAMINATION OF THE POTABLE SOURCE.
- ALL NON-TURF PLANTED AREAS SHALL BE DRIP IRRIGATED. SODDED AND SEEDED AREAS SHALL BE IRRIGATED WITH SPRAY OR ROTOR HEADS AT 100% HEAD-TO-HEAD COVERAGE.
- ALL PLANTS SHARING SIMILAR HYDROZONE CHARACTERISTICS SHALL BE PLACED ON A VALVE DEDICATED TO PROVIDE THE NECESSARY WATER REQUIREMENTS SPECIFIC TO THAT HYDROZONE.
- THE IRRIGATION SYSTEM SHALL BE DESIGNED AND INSTALLED, TO THE MAXIMUM EXTENT POSSIBLE, TO CONSERVE WATER BY USING THE FOLLOWING DEVICES AND SYSTEMS: MATCHED PRECIPITATION RATE TECHNOLOGY ON ROTOR AND SPRAY HEADS (WHEREVER POSSIBLE), RAIN SENSORS, AND MULTI-PROGRAM COMPUTERIZED IRRIGATION CONTROLLERS FEATURING SENSORY INPUT CAPABILITIES.

PLANT SCHEDULE						
SYMBOL	KEY	QTY	BOTANICAL NAME	COMMON NAME	SIZE	SPACING
TREES						
CL	4	4	CHILOPSIS LINEARIS 'TIMELESS BEAUTY'	TIMELESS BEAUTY DESERT WILLOW	MIN. 4' HT.	PER PLAN
QB	4	4	QUERCUS BUCKLEYI	TEXAS RED OAK	MIN. 4" CAL.	PER PLAN
UC	3	3	ULMUS CRASSIFOLIA	CEDAR ELM	MIN. 4" CAL.	PER PLAN
SHRUBS						
AG	64	64	ABELIA GRANDIFLORA 'ROSE CREEK'	ROSE CREEK ABELIA	5 GAL.	2' O.C.
IV	53	53	ILEX VOMITORIA 'NANA'	DWARF YAUPON HOLLY	5 GAL.	3' O.C.
MC	39	39	MYRICA CERIFERA 'DON'S DWARF'	DON'S DWARF WAX MYRTLE	5 GAL.	4' O.C.
GROUNDCOVER						
6733	SF	SOD: CYNODON DACTYLON 'TIF TUF'	TIF TUF BERMUDA GRASS	SOD		

CAUTION NOTICE TO CONTRACTORS
 THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL 811 AT LEAST 72 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATIONS OF THE UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THESE PLANS.



10/06/25

BY	REVISION DESCRIPTION	DATE
SS	approved by	
LC	designed by	
SMS	drawn by	

LANDSCAPE PLAN
 LOT 18, BLOCK A, CREEKSIDE COMMONS ADDITION
 NWC STATE HIGHWAY 205 & F.M. 549
 A 0.936 ACRE TRACT OF LAND IN THE WILLIAM W. FORD SURVEY, ABST. NO 80
 CITY OF ROCKWALL, ROCKWALL COUNTY, TEXAS
 CITY PROJECT #SP2025-039
 October 6, 2025

APPROVED:
 I hereby certify that the above and foregoing site plan for a development in the City of Rockwall, Texas, was approved by the Planning & Zoning Commission of the City of Rockwall on the ____ day of ____, 2025.
 WITNESS OUR HANDS, this ____ day of ____, 2025.
 Planning & Zoning Commission, Chairman Director of Planning and Zoning

ENGINEER/APPLICANT
 THE DIMENSION GROUP
 10755 SANDHILL ROAD
 DALLAS, TX, 75238
 PHONE: (214) 343-9400
 CONTACT: KEATON L. MAI, PE


OWNER
 PRUDENT DEVELOPMENT
 10755 SANDHILL ROAD
 DALLAS, TEXAS 75238
 PHONE: (214) 271-4630
 CONTACT: MICHAEL HAMPTON

DEVELOPER
 VALLEY BELLS ENTERPRISES, LLC
 101 E. CHEROKEE STREET
 JACKSONVILLE, TX 75766
 PHONE: (903) 586-1524
 CONTACT: MIKE STRANSBERRY

LANDSCAPE PLAN
 TACO BELL
 NWC STATE HIGHWAY 205 AND FM 549
 ROCKWALL, TEXAS 75082
 SHEET
LP-1


PLANTING SPECIFICATIONS

- GENERAL**
- A. QUALIFICATIONS OF LANDSCAPE CONTRACTOR**
- ALL LANDSCAPE WORK SHOWN ON THESE PLANS SHALL BE PERFORMED BY A SINGLE FIRM SPECIALIZING IN LANDSCAPE PLANTING.
 - A LIST OF SUCCESSFULLY COMPLETED PROJECTS OF THIS TYPE, SIZE AND NATURE MAY BE REQUESTED BY THE OWNER FOR FURTHER QUALIFICATION MEASURES.
 - THE LANDSCAPE CONTRACTOR SHALL HOLD A VALID NURSERY AND FLORAL CERTIFICATE ISSUED BY THE TEXAS DEPARTMENT OF AGRICULTURE, AS WELL AS OPERATE UNDER A COMMERCIAL PESTICIDE APPLICATOR LICENSE ISSUED BY EITHER THE TEXAS DEPARTMENT OF AGRICULTURE OR THE TEXAS STRUCTURAL PEST CONTROL BOARD.
- B. SCOPE OF WORK**
- WORK COVERED BY THESE SECTIONS INCLUDES THE FURNISHING AND PAYMENT OF ALL MATERIALS, LABOR, SERVICES, EQUIPMENT, LICENSES, TAXES AND ANY OTHER ITEMS THAT ARE NECESSARY FOR THE EXECUTION, INSTALLATION AND COMPLETION OF ALL WORK, SPECIFIED HEREIN AND / OR SHOWN ON THE LANDSCAPE PLANS, NOTES, AND DETAILS.
 - ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH ALL APPLICABLE LAWS, CODES AND REGULATIONS REQUIRED BY AUTHORITIES HAVING JURISDICTION OVER SUCH WORK, INCLUDING ALL INSPECTIONS AND PERMITS REQUIRED BY FEDERAL, STATE AND LOCAL AUTHORITIES IN SUPPLY, TRANSPORTATION AND INSTALLATION OF MATERIALS.
 - THE LANDSCAPE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL UNDERGROUND UTILITY LINES (WATER, SEWER, ELECTRICAL, TELEPHONE, GAS, CABLE, TELEVISION, ETC.) PRIOR TO THE START OF ANY WORK.
- PRODUCTS**
- A. ALL MANUFACTURED PRODUCTS SHALL BE NEW.**
- B. CONTAINER AND BALLED-AND-BURLAPPED PLANTS:**
- FURNISH NURSERY-GROWN PLANTS COMPLYING WITH ANSI Z60.1-2014. PROVIDE WELL-SHAPED, FULLY BRANCHED, HEALTHY, VIGOROUS STOCK FREE OF DISEASE, INSECTS, EGGS, LARVAE, AND DEFECTS SUCH AS KNOTS, SUN SCALD, INJURIES, ABRASIONS, AND DISFIGUREMENT. ALL PLANTS WITH A SPECIES SHALL HAVE SIMILAR SIZE, AND SHALL BE OF A FORM TYPICAL FOR THE SPECIES. ALL TREES SHALL BE OBTAINED FROM SOURCES WITHIN 200 MILES OF THE PROJECT SITE, AND WITH SIMILAR CLIMATIC CONDITIONS.
 - ROOT SYSTEMS SHALL BE HEALTHY, DENSELY BRANCHED ROOT SYSTEMS, NON-POT-BOUND, FREE FROM ENCIRCLING AND/OR GIRDLING ROOTS, AND FREE FROM ANY OTHER ROOT DEFECTS (SUCH AS J-SHAPED ROOTS).
 - TREES MAY BE PLANTED FROM CONTAINERS OR BALLED-AND-BURLAPPED (BBB), UNLESS SPECIFIED ON THE PLANTING LEGEND. BARE-ROOT TREES ARE NOT ACCEPTABLE.
 - ANY PLANT DEEMED UNACCEPTABLE BY THE LANDSCAPE ARCHITECT OR OWNER SHALL BE IMMEDIATELY REMOVED FROM THE SITE AND SHALL BE REPLACED WITH AN ACCEPTABLE PLANT OF LIKE TYPE AND SIZE AT THE CONTRACTOR'S OWN EXPENSE. ANY PLANTS APPEARING TO BE UNHEALTHY, EVEN IF DETERMINED TO STILL BE ALIVE, SHALL NOT BE ACCEPTED. THE LANDSCAPE ARCHITECT AND OWNER SHALL BE THE ACCEPTABILITY OF PLANT MATERIAL.
 - ALL TREES SHALL BE STANDARD IN FORM, UNLESS OTHERWISE SPECIFIED. TREES WITH CENTRAL LEADERS WILL NOT BE ACCEPTED IF LEADER IS DAMAGED OR REMOVED. PRUNE ALL DAMAGED TWIGS AFTER PLANTING.
 - CALIPER MEASUREMENTS FOR STANDARD (SINGLE TRUNK) TREES SHALL BE AS FOLLOWS: SIX INCHES ABOVE THE ROOT FLARE FOR TREES UP TO AND INCLUDING FOUR INCHES IN CALIPER, AND TWELVE INCHES ABOVE THE ROOT FLARE FOR TREES EXCEEDING FOUR INCHES IN CALIPER.
 - MULTI-TRUNK TREES SHALL BE MEASURED BY THEIR OVERALL HEIGHT, MEASURED FROM THE TOP OF THE ROOT BALL, WHERE CALIPER MEASUREMENTS ARE USED, THE CALIPER SHALL BE CALCULATED AS ONE-HALF OF THE SUM OF THE CALIPER OF THE THREE LARGEST TRUNKS.
 - ANY TREE OR SHRUB SHOWN TO HAVE EXCESS SOIL PLACED ON TOP OF THE ROOT BALL, SO THAT THE ROOT FLARE HAS BEEN COMPLETELY COVERED, SHALL BE REJECTED.
- C. SEED:** PROVIDE BLEND OF SPECIES AND VARIETIES AS NOTED ON THE PLANS, WITH MAXIMUM PERCENTAGES OF PURITY, GERMINATION, AND MINIMUM PERCENTAGE OF WEED SEED AS INDICATED ON PLANS. EACH BAG OF SEED SHALL BE ACCOMPANIED BY A TAG FROM THE SUPPLIER INDICATING THE COMPOSITION OF THE SEED.
- D. TOPSOIL:** SANDY TO CLAY LOAM TOPSOIL, FREE OF STONES LARGER THAN 1/2 INCH, FOREIGN MATTER, PLANTS, ROOTS, AND SEEDS.
- E. COMPOST:** WELL-COMPOSTED, STABLE, AND WEED-FREE ORGANIC MATTER, pH RANGE OF 5.5 TO 6.5, MOISTURE CONTENT 35 TO 55 PERCENT BY WEIGHT, 100 PERCENT PASSING THROUGH 3/4-INCH SIEVE; SOLUBLE SALT CONTENT OF 5 TO 10 DECISEMENS/M; NOT EXCEEDING 0.5 PERCENT INERT CONTAMINANTS AND FREE OF SUBSTANCES TOXIC TO PLANTINGS. NO MANURE OR ANIMAL-BASED PRODUCTS SHALL BE USED.
- F. FERTILIZER:** GRANULAR FERTILIZER CONSISTING OF NITROGEN, PHOSPHORUS, POTASSIUM, AND OTHER NUTRIENTS IN PROPORTIONS, AMOUNTS, AND RELEASE RATES RECOMMENDED IN A SOIL REPORT FROM A QUALIFIED SOIL-TESTING AGENCY (SEE BELOW).
- G. MULCH:** SIZE AND TYPE AS INDICATED ON PLANS, FREE FROM DELETERIOUS MATERIALS AND SUITABLE AS TOP DRESSING OF TREES AND SHRUBS.
- H. TREE STAKING AND GUYING**
- STAKES: 1/2" LONG GREEN METAL T-POSTS.
 - GUY AND TIE WIRE: ASTM A 641, CLASS 1, GALVANIZED-STEEL WIRE, 2-STRAND, TWISTED, 0.106 INCH DIAMETER.
 - STRAP CHAINING GUARD: REINFORCED NYLON OR CANVAS AT LEAST 1-1/2 INCH WIDE, WITH GROMMETS TO PROTECT TREE TRUNKS FROM DAMAGE.
- J. STEEL EDGING:** PROFESSIONAL STEEL EDGING, 14 GAUGE THICK X 4 INCHES WIDE, FACTORY PAINTED DARK GREEN. ACCEPTABLE MANUFACTURERS INCLUDE COL-MET OR APPROVED EQUAL.
- K. PRE-EMERGENT HERBICIDES:** ANY GRANULAR, NON-STAINING PRE-EMERGENT HERBICIDE THAT IS LABELED FOR THE SPECIFIC ORNAMENTALS OR TURF ON WHICH IT WILL BE UTILIZED. PRE-EMERGENT HERBICIDES SHALL BE APPLIED PER THE MANUFACTURER'S LABELED RATES.
- METHODS**
- A. SOIL PREPARATION**
- BEFORE STARTING WORK, THE LANDSCAPE CONTRACTOR SHALL VERIFY THAT THE GRADE OF ALL LANDSCAPE AREAS ARE WITHIN +0.0' OF FINISH GRADE. THE CONTRACTOR SHALL NOTIFY THE OWNER IMMEDIATELY SHOULD ANY DISCREPANCIES EXIST.
 - SOIL TESTING:
 - AFTER FINISH GRADES HAVE BEEN ESTABLISHED, CONTRACTOR SHALL HAVE SOIL SAMPLES FROM THE PROJECT'S LANDSCAPE AREAS TESTED BY AN ESTABLISHED SOIL TESTING LABORATORY. EACH SAMPLE SUBMITTED TO THE LAB SHALL CONTAIN NO LESS THAN ONE QUART OF SOIL, TAKEN FROM BETWEEN THE SOIL SURFACE AND 6" DEPTH. IF NO SAMPLE LOCATIONS ARE INDICATED ON THE PLANS, THE CONTRACTOR SHALL TAKE A MINIMUM OF THREE SAMPLES FROM VARIOUS REPRESENTATIVE LOCATIONS FOR TESTING.
 - THE CONTRACTOR SHALL HAVE THE SOIL TESTING LABORATORY PROVIDE RESULTS FOR THE FOLLOWING: SOIL TEXTURAL CLASS, GENERAL SOIL FERTILITY, pH, ORGANIC MATTER CONTENT, SALT (CEC), LIME, SODIUM ADSORPTION RATIO (SAR) AND BORON CONTENT.
 - THE CONTRACTOR SHALL ALSO SUBMIT THE PROJECT'S PLANT LIST TO THE LABORATORY ALONG WITH THE SOIL SAMPLES.
 - THE SOIL REPORT PRODUCED BY THE LABORATORY SHALL CONTAIN RECOMMENDATIONS FOR THE FOLLOWING (AS APPROPRIATE): SEPARATE SOIL PREPARATION AND BACKFILL, MIX RECOMMENDATIONS FOR ORNAMENTAL PLANTS, SERIC PLANTS, TURF, AND NATIVE SEED, AS WELL AS PRE-PLANT FERTILIZER APPLICATIONS AND RECOMMENDATIONS FOR ANY OTHER SOIL RELATED ISSUES. THE REPORT SHALL ALSO PROVIDE A FERTILIZER PROGRAM FOR THE ESTABLISHMENT PERIOD AND FOR LONG-TERM MAINTENANCE.
 - THE CONTRACTOR SHALL INSTALL SOIL AMENDMENTS AND FERTILIZERS PER THE SOILS REPORT RECOMMENDATIONS. ANY CHANGE IN COST DUE TO THE SOIL REPORT RECOMMENDATIONS, EITHER INCREASE OR DECREASE, SHALL BE SUBMITTED TO THE OWNER WITH THE REPORT.
 - FOR BIDDING PURPOSES ONLY, THE SOIL PREPARATION SHALL CONSIST OF THE FOLLOWING:
 - TURF: INCORPORATE THE FOLLOWING AMENDMENTS INTO THE TOP 8" OF SOIL BY MEANS OF ROTOTILLING AFTER CROSS-RIPPING:
 - NITROGEN STABILIZED ORGANIC AMENDMENT - 4 CU. YDS. PER 1,000 S.F.
 - PREPLANT TURF FERTILIZER (10-20-10 OR SIMILAR, SLOW RELEASE, ORGANIC) - 15 LBS PER 1,000 S.F.
 - "CLAY BUSTER" OR EQUAL - USE MANUFACTURER'S RECOMMENDED RATE
 - TREES, SHRUBS, AND PERENNIALS: INCORPORATE THE FOLLOWING AMENDMENTS INTO THE TOP 8" OF SOIL BY MEANS OF ROTOTILLING AFTER CROSS-RIPPING:
 - NITROGEN STABILIZED ORGANIC AMENDMENT - 4 CU. YDS. PER 1,000 S.F.
 - 12-12-12 FERTILIZER (OR SIMILAR, ORGANIC, SLOW RELEASE) - 10 LBS. PER CU. YD.
 - "CLAY BUSTER" OR EQUAL - USE MANUFACTURER'S RECOMMENDED RATE
 - IRON SULPHATE - 2 LBS. PER CU. YD.
- IN THE CONTEXT OF THESE PLANS, NOTES, AND SPECIFICATIONS, "FINISH GRADE" REFERS TO THE FINAL ELEVATION OF THE SOIL SURFACE (NOT TOP OF MULCH) AS INDICATED ON THE GRADING PLANS. BEFORE STARTING WORK, THE LANDSCAPE CONTRACTOR SHALL VERIFY THAT THE ROUGH GRADES OF ALL LANDSCAPE AREAS ARE WITHIN +0.0' OF FINISH GRADE. SEE SPECIFICATIONS FOR MORE DETAILED INSTRUCTION ON TURF AREA AND PLANTING BED PREPARATION.
- CONSTRUCT AND MAINTAIN FINISH GRADES AS SHOWN ON GRADING PLANS, AND CONSTRUCT AND MAINTAIN SLOPES AS RECOMMENDED BY THE GEOTECHNICAL REPORT. ALL LANDSCAPE AREAS SHALL HAVE POSITIVE DRAINAGE AWAY FROM STRUCTURES AT THE MINIMUM SLOPE SPECIFIED IN THE REPORT AND ON THE GRADING PLANS, AND AREAS OF POTENTIAL PONDING SHALL BE REGRADED TO BLEND IN WITH THE SURROUNDING GRADES AND ELIMINATE PONDING POTENTIAL.
 - THE LANDSCAPE CONTRACTOR SHALL DETERMINE WHETHER OR NOT THE EXPORT OF ANY SOIL WILL BE NEEDED, TAKING INTO ACCOUNT THE ROUGH GRADE PROVIDED, AND THE FINISH GRADES TO BE ESTABLISHED.
 - AFTER INSTALLING SOIL AMENDMENTS IN SHRUB AREAS, AND IN ORDER TO ALLOW FOR PROPER MULCH DEPTH, ENSURE THAT THE FINISH GRADE IMMEDIATELY ADJACENT TO WALKS AND OTHER WALKING SURFACES IS 0" BELOW FINISH GRADE, TAPERING TO MEET FINISH GRADE AT APPROXIMATELY 18" AWAY FROM THE SURFACE.
 - AFTER INSTALLING SOIL AMENDMENTS IN TURF AREAS, ENSURE THAT THE FINISH GRADE IN TURF AREAS IMMEDIATELY ADJACENT TO WALKS AND OTHER WALKING SURFACES IS 1" BELOW FINISH GRADE, TAPERING TO MEET FINISH GRADE AT APPROXIMATELY 18" AWAY FROM THE SURFACE.
 - SHOULD ANY CONFLICTS AND/OR DISCREPANCIES ARISE BETWEEN THE GRADING PLANS, GEOTECHNICAL REPORT, THESE NOTES AND PLANS, AND ACTUAL CONDITIONS, THE CONTRACTOR SHALL IMMEDIATELY BRING SUCH ITEMS TO THE ATTENTION OF THE LANDSCAPE ARCHITECT, GENERAL CONTRACTOR, AND OWNER.
 - ONCE SOIL PREPARATION IS COMPLETE, THE LANDSCAPE CONTRACTOR SHALL ENSURE THAT THERE ARE NO DEBRIS, TRASH, OR STONES LARGER THAN 1" REMAINING IN THE TOP 6" OF SOIL.




- ROLLED-TOP STEEL EDGING PER PLANS.
- TAPERED STEEL STAKES.
- MULCH, TYPE AND DEPTH PER PLANS.
- FINISH GRADE.

D STEEL EDGING
SCALE: NOT TO SCALE



E ROOT BARRIER - PLAN VIEW
SCALE: NOT TO SCALE



NOTE: ALL PLANTS SHALL BE PLANTED AT EQUAL TRIANGULAR SPACING (EXCEPT WHERE SHOWN ON PLANS AS INFORMAL GROUPINGS). REFER TO PLANT LEGEND FOR SPACING DISTANCE BETWEEN PLANTS.


1) STEP 1: DETERMINE TOTAL PLANTS FOR THE AREA WITH THE FOLLOWING FORMULA:
TOTAL AREA / AREA DIVIDER = TOTAL PLANTS

PLANT SPACING	AREA DIVIDER	PLANT SPACING	AREA DIVIDER
6"	0.22	18"	1.95
8"	0.39	24"	3.49
10"	0.60	30"	5.41
12"	0.87	36"	7.79
15"	1.35		


2) STEP 2: SUBTRACT THE ROW (S) OF PLANTS THAT WOULD OCCUR AT THE EDGE OF THE PLANTED AREA WITH THE FOLLOWING FORMULA: TOTAL PERIMETER LENGTH / PLANT SPACING = TOTAL PLANT SUBTRACTION

EXAMPLE: PLANTS AT 18" O.C. IN 100 SF PLANTING AREA, 40 LF PERIMETER
STEP 1: 100 SF / 3.49 = 51 PLANTS
STEP 2: 51 PLANTS - (40 LF / 18" = 21 PLANTS) = 30 PLANTS TOTAL

C PLANT SPACING
SCALE: NTS




- TREE CANOPY.
- CINCH-TIES (24" BOX2" CAL. TREES AND SMALLER) OR 1/2 GAUGE GALVANIZED WIRE WITH NYLON TREE STRAPS AT TREE AND STAKE (36" BOX2" CAL. TREES AND LARGER). SECURE TIES OR STRAPS TO TRUNK JUST ABOVE LOWEST MAJOR BRANCHES.
- 24" X 3/4" P.V.C. MARKERS OVER WIRES.
- GREEN STEEL T-POSTS. EXTEND POSTS 12" MIN. INTO UNDISTURBED SOIL.
- PRESSURE-TREATED WOOD DEADMAN, TWO PER TREE (MIN. BURY OUTSIDE OF PLANTING PIT AND 18" MIN. INTO UNDISTURBED SOIL.
- TRUNK FLARE.
- MULCH, TYPE AND DEPTH PER PLANS. DO NOT PLACE MULCH WITHIN 6" OF TRUNK.
- FINISH GRADE.
- ROOT BALL.
- BACKFILL. AMEND AND FERTILIZE ONLY AS RECOMMENDED IN SOIL FERTILITY ANALYSIS.
- UNDISTURBED NATIVE SOIL.
- 4" HIGH EARTHEN WATERING BASIN.
- FINISH GRADE.




A TREE PLANTING
SCALE: NOT TO SCALE

- NOTES:
- SCARIFY SIDES OF PLANTING PIT PRIOR TO SETTING TREE.
 - REMOVE EXCESS SOIL APPLIED ON TOP OF THE ROOTBALL THAT COVERS THE ROOT FLARE. THE PLANTING HOLE DEPTH SHALL BE SUCH THAT THE ROOTBALL RESTS ON UNDISTURBED SOIL, AND THE ROOT FLARE IS 2"-4" ABOVE FINISH GRADE.
 - FOR 8-8 TREES, CUT OFF BOTTOM 15" OF WIRE BASKET BEFORE PLACING TREE IN HOLE. CUT OFF AND REMOVE REMAINDER OF BASKET AFTER TREE IS SET IN HOLE. REMOVE ALL NYLON TIES, TWINE, ROPE, AND OTHER PACKING MATERIAL. REMOVE AS MUCH BURLAP FROM AROUND ROOTBALL AS IS PRACTICAL.
 - REMOVE ALL NURSERY STAKES AFTER PLANTING.
 - FOR TREES 36" CAL. AND LARGER, USE THREE STAKES OR DEADMAN (AS APPROPRIATE), SPACED EVENLY AROUND TREE. STAKING SHALL BE TIGHT ENOUGH TO PREVENT TRUNK FROM BENDING, BUT LOOSE ENOUGH TO ALLOW SOME TRUNK MOVEMENT IN WIND.

1) INSTALL EDGING SO THAT STAKES WILL BE ON INSIDE OF PLANTING BED.
2) BOTTOM OF EDGING SHALL BE BURIED A MINIMUM OF 1" BELOW FINISH GRADE.
3) TOP OF MULCH SHALL BE 1" LOWER THAN TOP OF EDGINGS.



B SHRUB AND PERENNIAL PLANTING
SCALE: NTS



- SHRUB, PERENNIAL, OR ORNAMENTAL GRASS.
- MULCH, TYPE AND DEPTH PER PLANS. PLACE NO MORE THAN 1" OF MULCH WITHIN 6" OF PLANT CENTER.
- FINISH GRADE.
- ROOT BALL.
- BACKFILL. AMEND AND FERTILIZE ONLY AS RECOMMENDED IN SOIL FERTILITY ANALYSIS.
- UNDISTURBED NATIVE SOIL.
- 3" HIGH EARTHEN WATERING BASIN.
- WEED FABRIC UNDER MULCH.

NOTES:

- INSTALL ROOT BARRIERS NEAR ALL NEWLY-PLANTED TREES THAT ARE LOCATED WITHIN FIVE (5) FEET OF PAVING OR CURBS. BARRIERS SHALL BE LOCATED IMMEDIATELY ADJACENT TO HARDSCAPE. UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR USE ROOT BARRIERS OF A TYPE THAT COMPLETELY ENCIRCLE THE ROOTBALL.

CAUTION NOTICE TO CONTRACTORS

THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL 811 AT LEAST 72 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATIONS OF THE UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THESE PLANS.

National Presence. Local Expertise.

EVERGREEN DESIGN GROUP
800.610.6130
www.evergreendesigngroup.com
LANDSCAPE ARCHITECTURE
LAND PLANNING • IRRIGATION DESIGN

THE DIMENSION GROUP

ARCHITECTURE • CIVIL ENGINEERING • MEP ENGINEERING
TEL: 214.433.9400 www.dimensiongroup.com

REGISTERED LANDSCAPE ARCHITECT
STATE OF TEXAS
3682
Sharon M. Stransberry

10/06/25

SERVICE AND ARE PROTECTED BY COPYRIGHT LAW. ALL RIGHTS RESERVED. NO PART OF THIS DOCUMENT MAY BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN CONSENT OF THE PROFESSIONAL ENGINEER.

BY	DATE	DESCRIPTION
SS		approved by
LC	09-11-2025	designed by
SS		approved by

PROJECT NO.	DATE	DATE
250-340	09-11-2025	

DATE	DESCRIPTION

LANDSCAPE PLAN
LOT 18, BLOCK A, CREEKSIDE COMMONS ADDITION
NWC STATE HIGHWAY 205 & F.M. 549
A 0.936 ACRE TRACT OF LAND IN THE WILLIAM W. FORD SURVEY, ABST. NO 80
CITY OF ROCKWALL, ROCKWALL COUNTY, TEXAS
CITY PROJECT #SP2025-039
October 6, 2025

APPROVED:
I hereby certify that the above and foregoing site plan for a development in the City of Rockwall, Texas, was approved by the Planning & Zoning Commission of the City of Rockwall on the ____ day of ____, 2025.

WITNESS OUR HANDS, THIS ____ day of ____, 2025.

Planning & Zoning Commission, Chairman

Director of Planning and Zoning

ENGINEER/APPLICANT
THE DIMENSION GROUP
10755 SANDHILL ROAD
DALLAS, TX, 75238
PHONE: (214) 343-9400
CONTACT: KEATON L. MAI, PE

OWNER
PRUDENT DEVELOPMENT
10755 SANDHILL ROAD
DALLAS, TEXAS 75238
PHONE: (214) 271-4630
CONTACT: MICHAEL HAMPTON

DEVELOPER
VALLEY BELLS ENTERPRISES, LLC
101 E. CHEROKEE STREET
JACKSONVILLE, TX 75766
PHONE: (903) 586-1524
CONTACT: MIKE STRANSBERRY

LANDSCAPE SPECS & DETAILS

TACO BELL
NWC STATE HIGHWAY 205 AND FM 549
ROCKWALL, TEXAS 75082

SHEET
LP-2

PROJECT COMMENTS



CITY OF ROCKWALL
385 S. GOLIAD STREET
ROCKWALL, TEXAS 75087
PHONE: (972) 771-7700

DATE: 1/22/2026

PROJECT NUMBER: P2026-004
PROJECT NAME: Replat for Lots 19-21, Block A, Creekside Commons Addition
SITE ADDRESS/LOCATIONS: NWC of Highway 205 and Future FM 549

CASE CAPTION: Consider a request by Keaton Mai of Dimension Group on behalf of Michael Hampton of Creekside Commons Crossing, LP for the approval of a Replat for Lots 19-21, Block A, Creekside Commons Addition being a 13.286-acre tract of land identified as Lots 15, 16 & 18, Block A, Creekside Commons Addition, City of Rockwall, Rockwall County, Texas, zoned Commercial (C) District, generally located at the southwest corner of the intersection of FM-549 and S. Goliad Street [SH-205], and take any action necessary.

DEPARTMENT	REVIEWER	DATE OF REVIEW	STATUS OF PROJECT
PLANNING	Henry Lee	01/22/2026	Needs Review

01/22/2026: Please address the following comments (M= Mandatory Comments; I = Informational Comments)

I.1 This is a request for the approval of a Replat for Lots 19-21, Block A, Creekside Commons Addition being a 13.286-acre tract of land identified as Lots 15, 16 & 18, Block A, Creekside Commons Addition, City of Rockwall, Rockwall County, Texas, zoned Commercial (C) District, generally located at the southwest corner of the intersection of FM-549 and S. Goliad Street [SH-205].

I.2 For questions or comments concerning this case please contact Henry Lee in the Planning Department at (972) 772-6434 or email hlee@rockwall.com.

M.3 For reference, include the case number (P2026-004) in the lower right-hand corner of all pages on future submittals.

M.4 Please delineate and label the City Limit line. (Section 38-7, Subdivision and Platting Procedures, of the Municipal Code of Ordinances)

I.5 Staff has identified the aforementioned items necessary to continue the submittal process. Please make all revisions and corrections and return to staff as soon as possible for a subsequent review prior to approval.

I.6 All meetings will be held in the Rockwall City Council Chambers at 385 S. Goliad Street at 6:00 PM. The meeting schedule for this case is as follows:

Planning and Zoning: January 27, 2026

City Council Meeting: February 2, 2026

I.7 Please note that a representative is required to be present for the meeting to answer any questions the Planning and Zoning Commission may have regarding your request. Once the Replat has been approved by the Planning and Zoning Commission and City Council, the case will be considered to be conditionally approved pending all of staff's comments from all City Departments and any applicable conditions of approval contained in staff's case memo are addressed prior to the subdivision plat being filed.

DEPARTMENT	REVIEWER	DATE OF REVIEW	STATUS OF PROJECT
ENGINEERING	Madelyn Price	01/20/2026	Approved w/ Comments

- 01/20/2026: 1. List width (min 24').
 2. Call this area out as a 24' fire lane and access easement too.
 3. Label this proposed easement here too.
 4. Remove.

DEPARTMENT	REVIEWER	DATE OF REVIEW	STATUS OF PROJECT
BUILDING	Craig Foshee	01/22/2026	Approved

No Comments

DEPARTMENT	REVIEWER	DATE OF REVIEW	STATUS OF PROJECT
FIRE	Ariana Kistner	01/20/2026	Approved

No Comments

DEPARTMENT	REVIEWER	DATE OF REVIEW	STATUS OF PROJECT
GIS	Lance Singleton	01/20/2026	Approved

No Comments

DEPARTMENT	REVIEWER	DATE OF REVIEW	STATUS OF PROJECT
POLICE	Chris Cleveland	01/20/2026	Approved

No Comments

DEPARTMENT	REVIEWER	DATE OF REVIEW	STATUS OF PROJECT
PARKS	Henry Lee	01/22/2026	N/A

No Comments

PARCEL CURVE TABLE				
CURVE #	LENGTH	RADIUS	DELTA	CHORD
C4	28.00'	36.00'	44°33'46"	S66° 35' 16"W 27.30'
C5	5.02'	25.00'	11°30'57"	N5° 51' 30"W 5.02'
C6	39.77'	25.00'	91°09'19"	S45° 40' 41"E 35.71'
C7	39.22'	25.00'	89°53'04"	S43° 48' 41"W 35.32'
C8	47.03'	20.00'	134°44'04"	S21° 30' 07"W 36.92'
C9	28.32'	20.00'	81°08'24"	S86° 26' 06"E 26.02'
C10	21.46'	49.00'	25°05'14"	N65° 32' 19"E 21.28'
C11	9.22'	49.00'	10°47'12"	N83° 28' 33"E 9.21'

PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L16	15.00'	N44°07'42"E
L17	52.07'	N45°52'18"W
L18	20.00'	N45°54'27"W
L19	51.04'	N43°59'07"E
L20	22.38'	N1°00'53"W
L21	153.66'	N43°59'07"E
L22	11.87'	N45°30'22"W
L23	19.90'	N44°29'38"E
L24	11.70'	S46°00'53"E
L25	31.45'	N43°59'07"E

PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L26	35.20'	N46°00'53"W
L27	20.00'	N44°08'05"E
L28	35.15'	S45°51'55"E
L29	12.34'	N43°59'07"E
L30	35.29'	N88°52'09"E
L31	5.01'	N1°06'12"W
L32	20.00'	N88°52'09"E
L33	5.00'	S1°06'12"E
L34	453.33'	N88°52'09"E
L35	301.80'	S54°13'54"E



PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L36	18.16'	S29°14'52"E
L37	20.00'	S60°45'12"W
L38	13.73'	S29°14'52"E
L39	290.70'	N54°13'54"W
L40	493.69'	S88°52'09"W
L41	220.81'	S43°59'07"W
L42	22.38'	S1°00'53"E
L43	59.36'	S43°59'07"W
L44	134.56'	N88°52'09"E
L45	20.01'	N2°38'25"W

PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L46	586.72'	S88°52'09"W
L47	20.00'	S1°13'55"E
L48	25.89'	S44°06'48"W
L49	10.00'	S44°06'48"W
L50	16.89'	N45°53'12"W
L51	15.09'	S89°06'48"W
L52	200.57'	N45°53'12"W
L53	10.32'	N44°08'20"E
L54	196.43'	S45°47'38"E
L55	15.09'	N89°06'48"E

PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L56	21.03'	S45°53'12"E
L57	12.00'	N88°45'13"E
L58	193.03'	N88°45'13"E
L59	5.00'	S1°14'47"E
L60	192.63'	S88°45'13"W
L61	168.03'	N88°45'13"E
L62	24.00'	S1°14'47"E
L63	168.18'	S88°45'13"W
L64	74.45'	N1°07'51"W
L65	10.00'	N88°45'13"E

PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L66	182.71'	S1°14'47"E
L67	9.99'	S88°52'09"W
L68	12.02'	S1°14'47"E
L69	34.64'	S88°52'09"W
L70	71.67'	N45°51'55"W
L71	44.60'	N88°52'09"E
L72	11.98'	S1°14'47"E


PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L13	22.85'	N45°51'55"W
L14	45.15'	S88°52'09"W
L15	21.83'	S44°43'37"W



LEGEND:

- IRF IRON ROD FOUND
- PC "TXDOT" IRON ROD FOUND WITH PINK CAP STAMPED "TXDOT"
- IRS IRON ROD SET WITH YELLOW CAP STAMPED "TXHS"
- <CM> CONTROLLING MONUMENT
- D.R.R.C.T. DEED RECORDS, ROCKWALL COUNTY, TEXAS
- M.R.R.C.T. MAP RECORDS, ROCKWALL COUNTY, TEXAS
- O.P.R.R.C.T. OFFICIAL PUBLIC RECORDS, ROCKWALL COUNTY, TEXAS
- INST. NO. INSTRUMENT NUMBER
- VOL., PG. VOLUME, PAGE
- ESMT. EASEMENT
- WSEL WATER SURFACE ELEVATION
- MIN. F.F.E. MINIMUM FINISHED FLOOR ELEVATION

MATCH LINE PG 2



VISIBILITY ESMT.
INST. NO. 2024000004925
O.P.R.R.C.T.

VISIBILITY ESMT.
INST. NO. 2024000004925
O.P.R.R.C.T.

1/2" IRF
YC 'SUMMIT'

STATE OF TEXAS
INST. NO. 20180000021509
O.P.R.R.C.T.

STATE HIGHWAY 205
(VARIABLE WIDTH RIGHT-OF-WAY)

STATE OF TEXAS
INST. NO. 20210000017067
O.P.R.R.C.T.

Label this proposed
easement here too.

20' DRAINAGE ESMT.
INST. NO. 2024000004925
O.P.R.R.C.T.

LOT 14
BLOCK A
CREEKSIDE COMMONS
INST. NO. 2024000004925
O.P.R.R.C.T.

24' FIRELANE, ACCESS,
& UTILITY ESMT.
INST. NO. 20230000008813
O.P.R.R.C.T.

549 CROSSING, LP
INST. NO. 20210000028395
O.P.R.R.C.T.

LOT 1
BLOCK A
CREEKSIDE COMMONS
INST. NO. 20230000008813
O.P.R.R.C.T.

15' UTILITY ESMT.
INST. NO. 20230000008813
O.P.R.R.C.T.

25' BUILDING LINE
INST. NO. 20230000008813
O.P.R.R.C.T.

20' LANDSCAPE BUFFER
INST. NO. 20230000008813
O.P.R.R.C.T.

DETENTION ESMT.
INST. NO. 20230000008813
O.P.R.R.C.T.

GENERAL NOTES:

1) Subdivider's Statement: Selling a portion of this addition by metes and bounds is unlawful and a violation of the Subdivision Ordinance of the City of Rockwall and Chapter 212, Municipal Regulation of Subdivisions and Property Development, of the Texas Local Government Code, and shall be subject to the City of Rockwall withholding utilities and building permits.

2) Public Improvement Statement: It shall be the policy of the City of Rockwall to withhold issuing building permits until all streets, water, sewer and storm drainage systems have been accepted by the City. The approval of a subdivision plat by the City does not constitute any representation, assurance or guarantee that any building within such plat shall be approved, authorized or permit issued, nor shall such approval constitute any representation, assurance or guarantee by the City of Rockwall of the adequacy and availability for water and sanitary sewer for personal use and fire protection within such subdivision plat, as required under the Subdivision Ordinance of the City of Rockwall.

3) Drainage and Detention Easements: Property owner shall be responsible for maintaining, repairing, and replacing and shall bear sole liability of all systems within the drainage and detention easements.

4) Fire Lanes: All Fire Lanes will be constructed, maintained, repaired and replaced by the property owner. Fire Lanes shall be constructed in accordance with the approved Civil Engineering Plans for both on-site and off-site Fire Lane improvements.

5) Street Appurtenances: All decorative signage, posts, or lights installed in public right-of-way shall be installed, maintained, repaired, and replaced by the homeowner's association (HOA).

6) Bearings are based upon the Texas State Plane Coordinate System, Texas North Central Zone (4202), North American Datum of 1983 (2011).

7) The purpose of this replat is to create easements and change lot boundary lines.

8) Benchmarks:

COR-8: Aluminum disk stamped "City of Rockwall Survey Monument" at the northerly intersection of Silver View Lane and Diamond Way Drive ± 1 foot north of curb line in center of curve.
N= 7,018,063.113; E= 2,609,533.682; Elevation= 600.48'

COR-9: Brass disk stamped "City of Rockwall Survey Monument" on the south side of Discovery Boulevard at the southeaster corner of curb inlet ± 180 feet east intersection of Discovery/Corporate.
N= 7,020,550.132; E= 2,607,463.893; Elevation= 595.63'

9) Zoning: Commercial (C) District


10) Base Flood Elevation information per FEMA GIS, FIRM Panel #48397C0045L.

11) All Visibility Easements are 30'x30' unless otherwise noted.

12) WSEL information based upon Floodplain / Detention Study NDMCE No. 23-014 by Nathan D. Maier Consulting Engineers, Inc. completed December of 2023.

MATCH LINE PG 5

STATE HIGHWAY 549 (VARIABLE WIDTH RIGHT-OF-WAY)



LANDSCAPE CALCULATIONS

PERMITTING AUTHORITY:	CITY OF ROCKWALL, TX
ZONING:	C
ADJACENT ZONING:	C
OVERALL	
TOTAL SITE AREA:	40,751 SF
LANDSCAPE AREA REQUIRED:	8,150 SF (20% OF SITE AREA)
LANDSCAPE AREA PROVIDED:	8,594 SF
% OF REQ. AREA IN FRONT AND SIDE YARDS:	91.7% (MIN 50%)
IMPERVIOUS AREA ON SITE:	32,157 SF
LANDSCAPE BUFFER ALONG S FM 549, MIN. WIDTH 10'	
LENGTH OF FRONTAGE:	192 LF (NOT INCL WIDTH OF DRIVEWAY)
CANOPY TREES REQUIRED:	4 CANOPY TREES (1 PER 50 LF)
CANOPY TREES PROVIDED:	4 CANOPY TREES
ACCENT TREES REQUIRED:	4 ACCENT TREES (1 PER 50 LF)
ACCENT TREES PROVIDED:	4 ACCENT TREES
SHRUBS REQUIRED:	48 SHRUBS PROVIDED
BERM REQUIRED:	30' BERM - SEE CIVIL PLANS FOR FINAL GRADES
NOTE: ADDITIONAL SHRUBS HAVE BEEN ADDED TO PROVIDE AN ENHANCED SCREEN AT THE DRIVE	

T HEAD LIGHT SCREENING

S REQUIRED.

T LANDSCAPING

KING AND MAINTENANCE AREA:	22,382 SF
PARKING SPACES:	27 PARKING SPACES
TREES REQUIRED:	3 CANOPY TREES (1 PER 10 PARKING SPACES)
TREES PROVIDED:	3 CANOPY TREES
PARKING SPACE MAY BE MORE THAN 80 LF FROM THE TRUNK OF A CANOPY TREE.	

L GRADING AND PLANTING NOTES

- BY SUBMITTING A PROPOSAL FOR THE LANDSCAPE PLANTING SCOPE OF WORK, THE CONTRACTOR CONFIRMS THAT HE HAS READ, AND WILL COMPLY WITH, THE ASSOCIATED SPECIFICATIONS, AND DETAILS WITH THIS PROJECT. GENERAL CONTRACTOR IS RESPONSIBLE FOR REMOVING ALL EXISTING VEGETATION (EXCEPT WHERE NOTED TO REMAIN). CONTEXT OF THESE PLANS, NOTES, AND SPECIFICATIONS, "FINISH GRADE" REFERS TO THE FINAL ELEVATION OF THE SOIL SURFACE (NOT TOP OF MULCH) AS INDICATED IN GRADING PLANS.
- BEFORE STARTING WORK, THE LANDSCAPE CONTRACTOR SHALL VERIFY THAT THE ROUGH GRADES OF ALL LANDSCAPE AREAS ARE WITHIN +/-0.1' OF FINISH GRADE. SEE SPECIFICATIONS FOR MORE DETAILED INSTRUCTION ON TURF AREA AND PLANTING BED PREPARATION.
- CONSTRUCT AND MAINTAIN FINISH GRADES AS SHOWN ON GRADING PLANS, AND CONSTRUCT AND MAINTAIN SLOPES AS RECOMMENDED BY THE GEOTECHNICAL REPORT. ALL LANDSCAPE AREAS SHALL HAVE POSITIVE DRAINAGE AWAY FROM STRUCTURES AT THE MINIMUM SLOPE SPECIFIED IN THE REPORT AND ON THE GRADING PLANS, AND AREAS OF POTENTIAL PONDING SHALL BE REGRADED TO BLEND IN WITH THE SURROUNDING GRADES AND ELIMINATE PONDING POTENTIAL.
 - THE LANDSCAPE CONTRACTOR SHALL DETERMINE WHETHER OR NOT THE EXPORT OF ANY SOIL WILL BE NEEDED, TAKING INTO ACCOUNT THE ROUGH GRADE PROVIDED, THE AMOUNT OF SOIL AMENDMENTS TO BE ADDED (BASED ON A SOIL TEST, PER SPECIFICATIONS), AND THE FINISH GRADES TO BE ESTABLISHED.
 - ENSURE THAT THE FINISH GRADE IN SHRUB AREAS IMMEDIATELY ADJACENT TO WALKS AND OTHER WALKING SURFACES, AFTER INSTALLING SOIL AMENDMENTS, IS 3" BELOW THE ADJACENT FINISH SURFACE, IN ORDER TO ALLOW FOR PROPER MULCH DEPTH. TAPER THE SOIL SURFACE TO MEET FINISH GRADE, AS SPECIFIED ON THE GRADING PLANS. AT APPROXIMATELY 18" AWAY FROM THE WALKS.
 - ENSURE THAT THE FINISH GRADE IN TURF AREAS IMMEDIATELY ADJACENT TO WALKS AND OTHER WALKING SURFACES, AFTER INSTALLING SOIL AMENDMENTS, IS 1" BELOW THE FINISH SURFACE OF THE WALKS. TAPER THE SOIL SURFACE TO MEET FINISH GRADE, AS SPECIFIED ON THE GRADING PLANS, AT APPROXIMATELY 18" AWAY FROM THE WALKS.
 - SHOULD ANY CONFLICTS AND/OR DISCREPANCIES ARISE BETWEEN THE GRADING PLANS, GEOTECHNICAL REPORT, THESE NOTES AND PLANS, AND ACTUAL CONDITIONS, THE CONTRACTOR SHALL IMMEDIATELY BRING SUCH ITEMS TO THE ATTENTION OF THE LANDSCAPE ARCHITECT, GENERAL CONTRACTOR, AND OWNER.
 - ALL PLANT LOCATIONS ARE DIAGRAMMATIC. ACTUAL LOCATIONS SHALL BE VERIFIED WITH THE LANDSCAPE ARCHITECT OR DESIGNER PRIOR TO PLANTING. THE LANDSCAPE CONTRACTOR SHALL ENSURE THAT ALL REQUIREMENTS OF THE PERMITTING AUTHORITY ARE MET (I.E., MINIMUM PLANT QUANTITIES, PLANTING METHODS, TREE PROTECTION METHODS, ETC.).
 - THE LANDSCAPE CONTRACTOR IS RESPONSIBLE FOR DETERMINING PLANT QUANTITIES; PLANT QUANTITIES SHOWN ON LEGENDS AND CALLOUTS ARE FOR GENERAL INFORMATION ONLY. IN THE EVENT OF A DISCREPANCY BETWEEN THE PLAN AND THE PLANT LEGEND, THE PLANT QUANTITY AS SHOWN ON THE PLAN (FOR INDIVIDUAL SYMBOLS) OR CALLOUT (FOR GROUNDCOVER PATTERNS) SHALL TAKE PRECEDENCE.
 - NO SUBSTITUTIONS OF PLANT MATERIALS SHALL BE ALLOWED WITHOUT THE WRITTEN PERMISSION OF THE LANDSCAPE ARCHITECT. IF SOME OF THE PLANTS ARE NOT AVAILABLE, THE LANDSCAPE CONTRACTOR SHALL NOTIFY THE LANDSCAPE ARCHITECT IN WRITING (VIA PROPER CHANNELS).
 - THE CONTRACTOR SHALL, AT A MINIMUM, PROVIDE REPRESENTATIVE PHOTOS OF ALL PLANTS PROPOSED FOR THE PROJECT. THE CONTRACTOR SHALL ALLOW THE LANDSCAPE ARCHITECT AND THE OWNER/OWNER'S REPRESENTATIVE TO INSPECT, AND APPROVE OR REJECT, ALL PLANTS DELIVERED TO THE JOBSITE. REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS FOR SUBMITTALS.
 - CONTRACTOR SHALL PROVIDE AND INSTALL SOLID SOD IN ALL RIGHT-OF-WAYS AND PARKWAYS (UNLESS NOT ALLOWED BY THE LOCAL JURISDICTION) AND SHALL PROVIDE WATERING AND MAINTENANCE UNTIL THE TURF IS ESTABLISHED AND HAS BEEN ACCEPTED BY OWNER.
 - THE CONTRACTOR SHALL MAINTAIN THE LANDSCAPE IN A HEALTHY CONDITION FOR 90 DAYS AFTER ACCEPTANCE BY THE OWNER. REFER TO SPECIFICATIONS FOR CONDITIONS OF ACCEPTANCE FOR THE START OF THE MAINTENANCE PERIOD, AND FOR FINAL ACCEPTANCE AT THE END OF THE MAINTENANCE PERIOD.
 - SEE SPECIFICATIONS AND DETAILS FOR FURTHER REQUIREMENTS.

ROOT BARRIERS

THE CONTRACTOR SHALL INSTALL ROOT BARRIERS NEAR ALL NEWLY-PLANTED TREES THAT ARE LOCATED WITHIN FIVE (5) FEET OF PAVING, CURBS, WATER, STORM, OR SANITARY SEWER UTILITIES. ROOT BARRIERS SHALL BE "CENTURY" OR "DEEP-ROOT" 24" DEEP PANELS (OR EQUAL). BARRIERS SHALL BE LOCATED IMMEDIATELY ADJACENT TO HARDSCAPE. INSTALL PANELS PER MANUFACTURER'S RECOMMENDATIONS. UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR USE ROOT BARRIERS OF A TYPE THAT COMPLETELY ENCIRCLE THE ROOTBALL.

MULCHES

AFTER ALL PLANTING IS COMPLETE, CONTRACTOR SHALL INSTALL 2" THICK LAYER OF 1-1/2" SHREDDED WOOD MULCH, NATURAL (UNDYED), OVER LANDSCAPE FABRIC IN ALL PLANTING AREAS (EXCEPT FOR TURF AND SEEDED AREAS). CONTRACTOR SHALL SUBMIT SAMPLES OF ALL MULCHES TO LANDSCAPE ARCHITECT AND OWNER FOR APPROVAL PRIOR TO CONSTRUCTION. ABSOLUTELY NO EXPOSED GROUND SHALL BE LEFT SHOWING ANYWHERE ON THE PROJECT AFTER MULCH HAS BEEN INSTALLED (SUBJECT TO THE CONDITIONS AND REQUIREMENTS OF THE "GENERAL GRADING AND PLANTING NOTES" AND SPECIFICATIONS).

PLANTING & IRRIGATION GUARANTEE

THE LANDSCAPE CONTRACTOR SHALL GUARANTEE THAT ALL NEWLY INSTALLED AND EXISTING PLANTS SHALL SURVIVE FOR ONE YEAR AFTER FINAL OWNER ACCEPTANCE OF THE INSTALLATION WORK. THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR APPROPRIATE WATERING OF THE LANDSCAPE THROUGH INSTALLATION OF A PROPERLY DESIGNED IRRIGATION SYSTEM. THE OWNER SHALL APPROVE THE SYSTEM DESIGN BEFORE INSTALLATION OF PLANTS OR IRRIGATION.

IRRIGATION CONCEPT

- AN AUTOMATIC IRRIGATION SYSTEM SHALL BE INSTALLED AND OPERATIONAL BY THE TIME OF FINAL INSPECTION. THE ENTIRE IRRIGATION SYSTEM SHALL BE INSTALLED BY A LICENSED AND QUALIFIED IRRIGATION CONTRACTOR.
- THE IRRIGATION SYSTEM WILL MEET THE REQUIREMENTS OF THE UDC.
- THE IRRIGATION SYSTEM WILL OPERATE ON POTABLE WATER, AND THE SYSTEM WILL HAVE APPROPRIATE BACKFLOW PREVENTION DEVICES INSTALLED TO PREVENT CONTAMINATION OF THE POTABLE SOURCE.
- ALL NON-TURF PLANTED AREAS SHALL BE DRIP IRRIGATED. SODDED AND SEEDED AREAS SHALL BE IRRIGATED WITH SPRAY OR ROTOR HEADS AT 100% HEAD-TO-HEAD COVERAGE.
- ALL PLANTS SHARING SIMILAR HYDROZONE CHARACTERISTICS SHALL BE PLACED ON A VALVE DEDICATED TO PROVIDE THE NECESSARY WATER REQUIREMENTS SPECIFIC TO THAT HYDROZONE.
- THE IRRIGATION SYSTEM SHALL BE DESIGNED AND INSTALLED, TO THE MAXIMUM EXTENT POSSIBLE, TO CONSERVE WATER BY USING THE FOLLOWING DEVICES AND SYSTEMS: MATCHED PRECIPITATION RATE TECHNOLOGY ON ROTOR AND SPRAY HEADS (WHEREVER POSSIBLE), RAIN SENSORS, AND MULTI-PROGRAM-COMPUTERIZED IRRIGATION CONTROLLERS FEATURING SENSORY INPUT CAPABILITIES.

PLANT SCHEDULE						
SYMBOL	KEY	QTY	BOTANICAL NAME	COMMON NAME	SIZE	SPACING
TREES						
CL	4	4	CHILOPSIS LINEARIS 'TIMELESS BEAUTY'	TIMELESS BEAUTY DESERT WILLOW	MIN. 4' HT.	PER PLAN
QB	4	4	QUERCUS BUCKLEYI	TEXAS RED OAK	MIN. 4" CAL.	PER PLAN
UC	3	3	ULMUS CRASSIFOLIA	CEDAR ELM	MIN. 4" CAL.	PER PLAN
SHRUBS						
AG	64	64	ABELIA GRANDIFLORA 'ROSE CREEK'	ROSE CREEK ABELIA	5 GAL.	2' O.C.
IV	53	53	ILEX VOMITORIA 'NANA'	DWARF YAUPON HOLLY	5 GAL.	3' O.C.
MC	39	39	MYRICA CERIFERA 'DON'S DWARF'	DON'S DWARF WAX MYRTLE	5 GAL.	4' O.C.
GROUNDCOVER						
6733	SF	SOD: CYNODON DACTYLON 'TIF TUF'	TIF TUF BERMUDA GRASS	SOD		

CAUTION NOTICE TO CONTRACTORS
THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL 811 AT LEAST 72 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATIONS OF THE UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THESE PLANS.



10/06/25

BY	REVISION DESCRIPTION	DATE
SS	approved by	
LC	designed by	
SMS	drawn by	

LANDSCAPE PLAN
LOT 18, BLOCK A, CREEKSIDE COMMONS ADDITION
NWC STATE HIGHWAY 205 & F.M. 549
A 0.936 ACRE TRACT OF LAND IN THE WILLIAM W. FORD SURVEY, ABST. NO 80
CITY OF ROCKWALL, ROCKWALL COUNTY, TEXAS
CITY PROJECT #SP2025-039
October 6, 2025

APPROVED:
I hereby certify that the above and foregoing site plan for a development in the City of Rockwall, Texas, was approved by the Planning & Zoning Commission of the City of Rockwall on the ____ day of ____, 2025.
WITNESS OUR HANDS, this ____ day of ____, 2025.

Planning & Zoning Commission, Chairman Director of Planning and Zoning

ENGINEER/APPLICANT
THE DIMENSION GROUP
10755 SANDHILL ROAD
DALLAS, TX, 75238
PHONE: (214) 343-9400
CONTACT: KEATON L. MAI, PE

OWNER
PRUDENT DEVELOPMENT
10755 SANDHILL ROAD
DALLAS, TEXAS 75238
PHONE: (214) 271-4630
CONTACT: MICHAEL HAMPTON

DEVELOPER
VALLEY BELLS ENTERPRISES, LLC
101 E. CHEROKEE STREET
JACKSONVILLE, TX 75766
PHONE: (903) 586-1524
CONTACT: MIKE STRANSBERRY


SHEET
LP-1

PLANTING SPECIFICATIONS


- GENERAL**
- A. QUALIFICATIONS OF LANDSCAPE CONTRACTOR**
- ALL LANDSCAPE WORK SHOWN ON THESE PLANS SHALL BE PERFORMED BY A SINGLE FIRM SPECIALIZING IN LANDSCAPE PLANTING.
 - A LIST OF SUCCESSFULLY COMPLETED PROJECTS OF THIS TYPE, SIZE AND NATURE MAY BE REQUESTED BY THE OWNER FOR FURTHER QUALIFICATION MEASURES.
 - THE LANDSCAPE CONTRACTOR SHALL HOLD A VALID NURSERY AND FLORAL CERTIFICATE ISSUED BY THE TEXAS DEPARTMENT OF AGRICULTURE, AS WELL AS OPERATE UNDER A COMMERCIAL PESTICIDE APPLICATOR LICENSE ISSUED BY EITHER THE TEXAS DEPARTMENT OF AGRICULTURE OR THE TEXAS STRUCTURAL PEST CONTROL BOARD.
- B. SCOPE OF WORK**
- WORK COVERED BY THESE SECTIONS INCLUDES THE FURNISHING AND PAYMENT OF ALL MATERIALS, LABOR, SERVICES, EQUIPMENT, LICENSES, TAXES AND ANY OTHER ITEMS THAT ARE NECESSARY FOR THE EXECUTION, INSTALLATION AND COMPLETION OF ALL WORK SPECIFIED HEREIN AND / OR SHOWN ON THE LANDSCAPE PLANS, NOTES, AND DETAILS.
 - ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH ALL APPLICABLE LAWS, CODES AND REGULATIONS REQUIRED BY AUTHORITIES HAVING JURISDICTION OVER SUCH WORK, INCLUDING ALL INSPECTIONS AND PERMITS REQUIRED BY FEDERAL, STATE AND LOCAL AUTHORITIES IN SUPPLY, TRANSPORTATION AND INSTALLATION OF MATERIALS.
 - THE LANDSCAPE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL UNDERGROUND UTILITY LINES (WATER, SEWER, ELECTRICAL, TELEPHONE, GAS, CABLE, TELEVISION, ETC.) PRIOR TO THE START OF ANY WORK.
- PRODUCTS**
- A. ALL MANUFACTURED PRODUCTS SHALL BE NEW.**
- B. CONTAINER AND BALLED-AND-BURLAPPED PLANTS:**
- FURNISH NURSERY-GROWN PLANTS COMPLYING WITH ANSI Z60.1-2014. PROVIDE WELL-SHAPED, FULLY BRANCHED, HEALTHY, VIGOROUS STOCK FREE OF DISEASE, INSECTS, EGGS, LARVAE, AND DEFECTS SUCH AS KNOTS, SUN SCALD, INJURIES, ABRASIONS, AND DISFIGUREMENT. ALL PLANTS WITH A SPECIES SHALL HAVE SIMILAR SIZE, AND SHALL BE OF A FORM TYPICAL FOR THE SPECIES. ALL TREES SHALL BE OBTAINED FROM SOURCES WITHIN 200 MILES OF THE PROJECT SITE, AND WITH SIMILAR CLIMATIC CONDITIONS.
 - ROOT SYSTEMS SHALL BE HEALTHY, DENSELY BRANCHED ROOT SYSTEMS, NON-POT-BOUND, FREE FROM ENCIRCLING AND/OR GIRDLING ROOTS, AND FREE FROM ANY OTHER ROOT DEFECTS (SUCH AS J-SHAPED ROOTS).
 - TREES MAY BE PLANTED FROM CONTAINERS OR BALLED-AND-BURLAPPED (BBB), UNLESS SPECIFIED ON THE PLANTING LEGEND. BARE-ROOT TREES ARE NOT ACCEPTABLE.
 - ANY PLANT DEEMED UNACCEPTABLE BY THE LANDSCAPE ARCHITECT OR OWNER SHALL BE IMMEDIATELY REMOVED FROM THE SITE AND SHALL BE REPLACED WITH AN ACCEPTABLE PLANT OF LIKE TYPE AND SIZE AT THE CONTRACTOR'S OWN EXPENSE. ANY PLANTS APPEARING TO BE UNHEALTHY, EVEN IF DETERMINED TO STILL BE ALIVE, SHALL NOT BE ACCEPTED. THE LANDSCAPE ARCHITECT AND OWNER SHALL BE AS THE ACCEPTABILITY OF PLANT MATERIAL.
 - ALL TREES SHALL BE STANDARD IN FORM, UNLESS OTHERWISE SPECIFIED. TREES WITH CENTRAL LEADERS WILL NOT BE ACCEPTED IF LEADER IS DAMAGED OR REMOVED. PRUNE ALL DAMAGED TWIGS AFTER PLANTING.
 - CALIPER MEASUREMENTS FOR STANDARD (SINGLE TRUNK) TREES SHALL BE AS FOLLOWS: SIX INCHES ABOVE THE ROOT FLARE FOR TREES UP TO AND INCLUDING FOUR INCHES IN CALIPER, AND TWELVE INCHES ABOVE THE ROOT FLARE FOR TREES EXCEEDING FOUR INCHES IN CALIPER.
 - MULTI-TRUNK TREES SHALL BE MEASURED BY THEIR OVERALL HEIGHT, MEASURED FROM THE TOP OF THE ROOT BALL, WHERE CALIPER MEASUREMENTS ARE USED, THE CALIPER SHALL BE CALCULATED AS ONE-HALF OF THE SUM OF THE CALIPER OF THE THREE LARGEST TRUNKS.
 - ANY TREE OR SHRUB SHOWN TO HAVE EXCESS SOIL PLACED ON TOP OF THE ROOT BALL, SO THAT THE ROOT FLARE HAS BEEN COMPLETELY COVERED, SHALL BE REJECTED.
- C. SEED:** PROVIDE BLEND OF SPECIES AND VARIETIES AS NOTED ON THE PLANS, WITH MAXIMUM PERCENTAGES OF PURITY, GERMINATION, AND MINIMUM PERCENTAGE OF WEED SEED AS INDICATED ON PLANS. EACH BAG OF SEED SHALL BE ACCOMPANIED BY A TAG FROM THE SUPPLIER INDICATING THE COMPOSITION OF THE SEED.
- D. TOPSOIL:** SANDY TO CLAY LOAM TOPSOIL, FREE OF STONES LARGER THAN 1/2 INCH, FOREIGN MATTER, PLANTS, ROOTS, AND SEEDS. WELL-COMPOSTED, STABLE, AND WEED-FREE ORGANIC MATTER, pH RANGE OF 5.5 TO 6.5. MOISTURE CONTENT 35 TO 55 PERCENT BY WEIGHT; 100 PERCENT PASSING THROUGH 3/4-INCH SIEVE; SOLUBLE SALT CONTENT OF 5 TO 10 DECISEMENS/M; NOT EXCEEDING 0.5 PERCENT INERT CONTAMINANTS AND FREE OF SUBSTANCES TOXIC TO PLANTINGS. NO MANURE OR ANIMAL-BASED PRODUCTS SHALL BE USED.
- F. FERTILIZER:** GRANULAR FERTILIZER CONSISTING OF NITROGEN, PHOSPHORUS, POTASSIUM, AND OTHER NUTRIENTS IN PROPORTIONS, AMOUNTS, AND RELEASE RATES RECOMMENDED IN A SOIL REPORT FROM A QUALIFIED SOIL-TESTING AGENCY (SEE BELOW).
- G. MULCH:** SIZE AND TYPE AS INDICATED ON PLANS, FREE FROM DELETERIOUS MATERIALS AND SUITABLE AS TOP DRESSING OF TREES AND SHRUBS.
- H. TREE STAKING AND GUYING**
- STAKES: 1/2" LONG GREEN METAL T-POSTS.
 - GUY AND TIE WIRE: ASTM A 641, CLASS 1, GALVANIZED-STEEL WIRE, 2-STRAND, TWISTED, 0.106 INCH DIAMETER.
 - STRAP CHAIRING GUARD: REINFORCED NYLON OR CANVAS AT LEAST 1-1/2 INCH WIDE, WITH GROMMETS TO PROTECT TREE TRUNKS FROM DAMAGE.
- J. STEEL EDGING:** PROFESSIONAL STEEL EDGING, 14 GAUGE THICK X 4 INCHES WIDE, FACTORY PAINTED DARK GREEN. ACCEPTABLE MANUFACTURERS INCLUDE COL-MET OR APPROVED EQUAL.
- K. PRE-EMERGENT HERBICIDES:** ANY GRANULAR, NON-STAINING PRE-EMERGENT HERBICIDE THAT IS LABELED FOR THE SPECIFIC ORNAMENTALS OR TURF ON WHICH IT WILL BE UTILIZED. PRE-EMERGENT HERBICIDES SHALL BE APPLIED PER THE MANUFACTURER'S LABELED RATES.
- METHODS**
- A. SOIL PREPARATION**
- BEFORE STARTING WORK, THE LANDSCAPE CONTRACTOR SHALL VERIFY THAT THE GRADE OF ALL LANDSCAPE AREAS ARE WITHIN +0.1' OF FINISH GRADE. THE CONTRACTOR SHALL NOTIFY THE OWNER IMMEDIATELY SHOULD ANY DISCREPANCIES EXIST.
 - SOIL TESTING:
 - AFTER FINISH GRADES HAVE BEEN ESTABLISHED, CONTRACTOR SHALL HAVE SOIL SAMPLES FROM THE PROJECT'S LANDSCAPE AREAS TESTED BY AN ESTABLISHED SOIL TESTING LABORATORY. EACH SAMPLE SUBMITTED TO THE LAB SHALL CONTAIN NO LESS THAN ONE QUART OF SOIL, TAKEN FROM BETWEEN THE SOIL SURFACE AND 6" DEPTH. IF NO SAMPLE LOCATIONS ARE INDICATED ON THE PLANS, THE CONTRACTOR SHALL TAKE A MINIMUM OF THREE SAMPLES FROM VARIOUS REPRESENTATIVE LOCATIONS FOR TESTING.
 - THE CONTRACTOR SHALL HAVE THE SOIL TESTING LABORATORY PROVIDE RESULTS FOR THE FOLLOWING: SOIL TEXTURAL CLASS, GENERAL SOIL FERTILITY, pH, ORGANIC MATTER CONTENT, SALT (CEC), LIME, SODIUM ADSORPTION RATIO (SAR) AND BORON CONTENT.
 - THE CONTRACTOR SHALL ALSO SUBMIT THE PROJECT'S PLANT LIST TO THE LABORATORY ALONG WITH THE SOIL SAMPLES.
 - THE SOIL REPORT PRODUCED BY THE LABORATORY SHALL CONTAIN RECOMMENDATIONS FOR THE FOLLOWING (AS APPROPRIATE): SEPARATE SOIL PREPARATION AND BACKFILL, MIX RECOMMENDATIONS FOR ORNAMENTAL PLANTS, SERIC PLANTS, TURF, AND NATIVE SEED, AS WELL AS PRE-PLANT FERTILIZER APPLICATIONS AND RECOMMENDATIONS FOR ANY OTHER SOIL RELATED ISSUES. THE REPORT SHALL ALSO PROVIDE A FERTILIZER PROGRAM FOR THE ESTABLISHMENT PERIOD AND FOR LONG-TERM MAINTENANCE.
 - THE CONTRACTOR SHALL INSTALL SOIL AMENDMENTS AND FERTILIZERS PER THE SOIL REPORT RECOMMENDATIONS. ANY CHANGE IN COST DUE TO THE SOIL REPORT RECOMMENDATIONS, EITHER INCREASE OR DECREASE, SHALL BE SUBMITTED TO THE OWNER WITH THE REPORT.
 - FOR BIDDING PURPOSES ONLY, THE SOIL PREPARATION SHALL CONSIST OF THE FOLLOWING:
 - TURF: INCORPORATE THE FOLLOWING AMENDMENTS INTO THE TOP 8" OF SOIL BY MEANS OF ROTOTILLING AFTER CROSS-RIPPING:
 - NITROGEN STABILIZED ORGANIC AMENDMENT - 4 CU. YDS. PER 1,000 S.F.
 - PREPLANT TURF FERTILIZER (10-20-10 OR SIMILAR, SLOW RELEASE, ORGANIC) - 15 LBS PER 1,000 S.F.
 - "CLAY BUSTER" OR EQUAL - USE MANUFACTURER'S RECOMMENDED RATE
 - TREES, SHRUBS, AND PERENNIALS: INCORPORATE THE FOLLOWING AMENDMENTS INTO THE TOP 8" OF SOIL BY MEANS OF ROTOTILLING AFTER CROSS-RIPPING:
 - NITROGEN STABILIZED ORGANIC AMENDMENT - 4 CU. YDS. PER 1,000 S.F.
 - 12-12-12 FERTILIZER (OR SIMILAR, ORGANIC, SLOW RELEASE) - 10 LBS. PER CU. YD.
 - "CLAY BUSTER" OR EQUAL - USE MANUFACTURER'S RECOMMENDED RATE
 - IRON SULPHATE - 2 LBS. PER CU. YD.
- IN THE CONTEXT OF THESE PLANS, NOTES, AND SPECIFICATIONS, "FINISH GRADE" REFERS TO THE FINAL ELEVATION OF THE SOIL SURFACE (NOT TOP OF MULCH) AS INDICATED ON THE GRADING PLANS. BEFORE STARTING WORK, THE LANDSCAPE CONTRACTOR SHALL VERIFY THAT THE ROUGH GRADES OF ALL LANDSCAPE AREAS ARE WITHIN +0.1' OF FINISH GRADE. SEE SPECIFICATIONS FOR MORE DETAILED INSTRUCTION ON TURF AREA AND PLANTING BED PREPARATION.
- CONSTRUCT AND MAINTAIN FINISH GRADES AS SHOWN ON GRADING PLANS, AND CONSTRUCT AND MAINTAIN SLOPES AS RECOMMENDED BY THE GEOTECHNICAL REPORT. ALL LANDSCAPE AREAS SHALL HAVE POSITIVE DRAINAGE AWAY FROM STRUCTURES AT THE MINIMUM SLOPE SPECIFIED IN THE REPORT AND ON THE GRADING PLANS, AND AREAS OF POTENTIAL PONDING SHALL BE REGRADED TO BLEND IN WITH THE SURROUNDING GRADES AND ELIMINATE PONDING POTENTIAL.
 - THE LANDSCAPE CONTRACTOR SHALL DETERMINE WHETHER OR NOT THE EXPORT OF ANY SOIL WILL BE NEEDED, TAKING INTO ACCOUNT THE ROUGH GRADE PROVIDED, THE AMOUNT OF SOIL AMENDMENTS TO BE ADDED (BASED ON A SOIL TEST, PER SPECIFICATIONS), AND THE FINISH GRADES TO BE ESTABLISHED.
 - AFTER INSTALLING SOIL AMENDMENTS IN SHRUB AREAS, AND IN ORDER TO ALLOW FOR PROPER MULCH DEPTH, ENSURE THAT THE FINISH GRADE IMMEDIATELY ADJACENT TO WALKS AND OTHER WALKING SURFACES IS 7" BELOW FINISH GRADE, TAPERING TO MEET FINISH GRADE AT APPROXIMATELY 18" AWAY FROM THE SURFACE.
 - AFTER INSTALLING SOIL AMENDMENTS IN TURF AREAS, ENSURE THAT THE FINISH GRADE IN TURF AREAS IMMEDIATELY ADJACENT TO WALKS AND OTHER WALKING SURFACES IS 1" BELOW FINISH GRADE, TAPERING TO MEET FINISH GRADE AT APPROXIMATELY 18" AWAY FROM THE SURFACE.
 - SHOULD ANY CONFLICTS AND/OR DISCREPANCIES ARISE BETWEEN THE GRADING PLANS, GEOTECHNICAL REPORT, THESE NOTES AND PLANS, AND ACTUAL CONDITIONS, THE CONTRACTOR SHALL IMMEDIATELY BRING SUCH ITEMS TO THE ATTENTION OF THE LANDSCAPE ARCHITECT, GENERAL CONTRACTOR, AND OWNER.
 - ONCE SOIL PREPARATION IS COMPLETE, THE LANDSCAPE CONTRACTOR SHALL ENSURE THAT THERE ARE NO DEBRIS, TRASH, OR STONES LARGER THAN 1" REMAINING IN THE TOP 6" OF SOIL.

Remove.

OPEN LANDSCAPE



E ROOT BARRIER - PLAN VIEW
SCALE: NOT TO SCALE



NOTE: ALL PLANTS SHALL BE PLANTED AT EQUAL TRIANGULAR SPACING (EXCEPT WHERE SHOWN ON PLANS AS INFORMAL GROUPINGS). REFER TO PLANT LEGEND FOR SPACING DISTANCE BETWEEN PLANTS.


1) STEP 1: DETERMINE TOTAL PLANTS FOR THE AREA WITH THE FOLLOWING FORMULA:
TOTAL AREA / AREA DIVIDER = TOTAL PLANTS

PLANT SPACING	AREA DIVIDER	PLANT SPACING	AREA DIVIDER
6"	0.22	18"	1.95
8"	0.39	24"	3.48
10"	0.60	30"	5.41
12"	0.87	36"	7.79
15"	1.35		

2) STEP 2: SUBTRACT THE ROW (S) OF PLANTS THAT WOULD OCCUR AT THE EDGE OF THE PLANTED AREA WITH THE FOLLOWING FORMULA: TOTAL PERIMETER LENGTH / PLANT SPACING = TOTAL PLANT SUBTRACTION

EXAMPLE: PLANTS AT 18" O.C. IN 100 SF PLANTING AREA, 40 LF PERIMETER
STEP 1: 100 SF / 3.48 = 51 PLANTS
STEP 2: 51 PLANTS - (40 LF / 18" = 21 PLANTS) = 30 PLANTS TOTAL

C PLANT SPACING
SCALE: NTS




A TREE PLANTING
SCALE: NOT TO SCALE

NOTES:

- SCARIFY SIDES OF PLANTING PIT PRIOR TO SETTING TREE.
- REMOVE EXCESS SOIL APPLIED ON TOP OF THE ROOTBALL THAT COVERS THE ROOT FLARE. THE PLANTING HOLE DEPTH SHALL BE SUCH THAT THE ROOTBALL RESTS ON UNDISTURBED SOIL, AND THE ROOT FLARE IS 2" ABOVE FINISH GRADE.
- FOR BAR TREES, CUT OFF 1/2" OF WIRE BASKET BEFORE PLACING TREE IN HOLE. CUT OFF AND REMOVE REMAINDER OF BASKET AFTER TREE IS SET IN HOLE. REMOVE ALL NYLON TIES, TWINE, ROPE, AND OTHER PACKING MATERIAL. REMOVE AS MUCH BURLAP FROM AROUND ROOTBALL AS IS PRACTICAL.
- REMOVE ALL NURSERY STAKES AFTER PLANTING.
- FOR TREES 3" CAL. AND LARGER, USE THREE STAKES OR DEADEN (AS APPROPRIATE), SPACED EVENLY AROUND TREE. STAKING SHALL BE TIGHT ENOUGH TO PREVENT TRUNK FROM BENDING, BUT LOOSE ENOUGH TO ALLOW SOME TRUNK MOVEMENT IN WIND.

B SHRUB AND PERENNIAL PLANTING
SCALE: NTS



NOTES:

- INSTALL ROOT BARRIERS NEAR ALL NEWLY PLANTED TREES THAT ARE LOCATED WITHIN FIVE (5) FEET OF PAVING OR CURBS. BARRIERS SHALL BE LOCATED IMMEDIATELY ADJACENT TO HARDSCAPE. UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR USE ROOT BARRIERS OF A TYPE THAT COMPLETELY ENCLOSE THE ROOTBALL.

- SHRUB, PERENNIAL, OR ORNAMENTAL GRASS.
- MULCH, TYPE AND DEPTH PER PLANS. PLACE NO MORE THAN 1" OF MULCH WITHIN 6" OF PLANT CENTER.
- FINISH GRADE.
- ROOT BALL.
- BACKFILL, AMEND AND FERTILIZE ONLY AS RECOMMENDED IN SOIL FERTILITY ANALYSIS.
- UNDISTURBED NATIVE SOIL.
- 3" HIGH EARTHEN WATERING BASIN.
- WEED FABRIC UNDER MULCH.

National Presence. Local Expertise.

EVERGREEN DESIGN GROUP
800.460.6830
www.evergreendesigngroup.com
LANDSCAPE ARCHITECTURE
PLANNING • IRRIGATION DESIGN

THE DIMENSION GROUP
ARCHITECTURE • CIVIL ENGINEERING • MEP ENGINEERING
1700 SANDHILL ROAD DALLAS, TEXAS 75238
PHONE: (214) 343-9400 www.dimensiongroup.com

REGISTERED LANDSCAPE ARCHITECT
STATE OF TEXAS
3682
Shyam M. Shrivastava

10/06/25

SERVICE AND ARE PROTECTED BY COPYRIGHT LAW. ALL RIGHTS RESERVED. INCLUDING COPYRIGHT. THEY MAY NOT BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, WITHOUT THE WRITTEN CONSENT OF THE PROFESSIONAL PERSONNEL.

BY	DATE	REVISION DESCRIPTION
SS		approved by
LC	09-11-2025	designed by
SS		approved by

PROJECT NO.	DATE	DATE	DATE
250-340	09-11-2025		

LANDSCAPE PLAN
LOT 18, BLOCK A, CREEKSIDE COMMONS ADDITION
NWC STATE HIGHWAY 205 & F.M. 549
A 0.936 ACRE TRACT OF LAND IN THE WILLIAM W. FORD SURVEY, ABST. NO 80
CITY OF ROCKWALL, ROCKWALL COUNTY, TEXAS
CITY PROJECT #SP2025-039
October 6, 2025

APPROVED:
I hereby certify that the above and foregoing site plan for a development in the City of Rockwall, Texas, was approved by the Planning & Zoning Commission of the City of Rockwall on the ____ day of ____, 2025.

WITNESS OUR HANDS, THIS ____ day of ____, 2025.

Planning & Zoning Commission, Chairman

Director of Planning and Zoning

ENGINEER/APPLICANT
THE DIMENSION GROUP
10755 SANDHILL ROAD
DALLAS, TX, 75238
PHONE: (214) 343-9400
CONTACT: KEATON L. MAI, PE

OWNER
PRUDENT DEVELOPMENT
10755 SANDHILL ROAD
DALLAS, TEXAS 75238
PHONE: (214) 271-4630
CONTACT: MICHAEL HAMPTON

DEVELOPER
VALLEY BELLS ENTERPRISES, LLC
101 E. CHEROKEE STREET
JACKSONVILLE, TX 75766
PHONE: (903) 586-1524
CONTACT: MIKE STRANSBERRY

CAUTION NOTICE TO CONTRACTORS
THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL 811 AT LEAST 72 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATIONS OF THE UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATED ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THESE PLANS.

LANDSCAPE SPECS & DETAILS
TACO BELL
NWC STATE HIGHWAY 205 AND FM 549
ROCKWALL, TEXAS 75082
SHEET
LP-2



CITY OF ROCKWALL

PLANNING AND ZONING COMMISSION CASE MEMO

PLANNING AND ZONING DEPARTMENT

385 S. GOLIAD STREET • ROCKWALL, TX 75087

PHONE: (972) 771-7745 • EMAIL: PLANNING@ROCKWALL.COM

TO: Planning and Zoning Commission
DATE: January 27, 2026
APPLICANT: Keaton Mai; *Dimension Group*
CASE NUMBER: P2026-004; *Replat for Lots 19-21, Block A, Creekside Commons Addition*

SUMMARY

Consider a request by Keaton Mai of Dimension Group on behalf of Michael Hampton of Creekside Commons Crossing, LP for the approval of a Replat for Lots 19-21, Block A, Creekside Commons Addition being a 13.286-acre tract of land identified as Lots 15, 16 & 18, Block A, Creekside Commons Addition, City of Rockwall, Rockwall County, Texas, zoned Commercial (C) District, generally located at the southwest corner of the intersection of FM-549 and S. Goliad Street [SH-205], and take any action necessary.

PLAT INFORMATION

- Purpose. The applicant is requesting approval of a Replat for three (3) existing parcels of land on 13.286-acres (*i.e. Lots 15-18, Block A, Creekside Commons Addition*) in order to establish three (3) new lots (*i.e. Lots 19-21, Block A, Creekside Commons Addition*). The purpose of the Replat is to dedicate new easements and adjust the lot lines of the three (3) existing lots in order to facilitate the future development of the subject property.
- Background. The subject property was annexed on May 19, 1986 by *Ordinance No. 86-37 [Case No. A1986-005]*. On March 4, 2013, the City Council approved a zoning case [*Case No. Z2013-002*] that rezoned the subject property from an Agricultural (AG) District to a Commercial (C) District. A preliminary plat [*Case No. P2021-027*] was approved by the City Council on June 7, 2021. This preliminary plat was amended by the City Council through *Case No. P2022-030* on July 5, 2022. On November 7, 2022, the City Council approved a final plat [*Case No. P2022-052*] that established the subject property as Lots 2-6, Block A, Creekside Commons Addition. On February 4, 2024, the City Council approved a replat that establish the subject property as Lots 15-18, Block A, Creekside Commons Addition. On October 14, 2025, the Planning and Zoning Commission approved a site plan [*Case No. SP2025-039*] to allow the construction of a *Restaurant Greater than 2,000 SF, with a Drive Through or Drive-In* on a portion of the subject property.
- Conformance to the Subdivision Ordinance. The surveyor has completed the majority of the technical revisions requested by staff, and this plat -- *conforming to the requirements for plats as stipulated by the Subdivision Ordinance in the Municipal Code of Ordinances* -- is recommended for conditional approval pending the completion of final technical modifications, submittal requirements, and conformance to the items listed in the Conditions of Approval section of this case memo.
- Conditions of Approval. Conditional approval of this Replat by the City Council shall constitute approval subject to the conditions stipulated in the Conditions of Approval section below.

CONDITIONS OF APPROVAL

If the Planning and Zoning Commission chooses to recommend approval of a Replat for *Lots 19-21, Block A, Creekside Commons Addition*, staff would propose the following conditions of approval:

- (1) All technical comments from City Staff (*i.e. Engineering, Planning and Fire Department*) shall be addressed prior to submittal of civil engineering plans; and,

- (2) Any construction resulting from the approval of this Replat shall conform to the requirements set forth by the Unified Development Code (UDC), the International Building Code (IBC), the Rockwall Municipal Code of Ordinances, city adopted engineering and fire codes and with all other applicable regulatory requirements administered and/or enforced by the state and federal government.



DEVELOPMENT APPLICATION

City of Rockwall
Planning and Zoning Department
385 S. Goliad Street
Rockwall, Texas 75087

STAFF USE ONLY
PLANNING & ZONING CASE NO.

NOTE: THE APPLICATION IS NOT CONSIDERED ACCEPTED BY THE CITY UNTIL THE PLANNING DIRECTOR AND CITY ENGINEER HAVE SIGNED BELOW.

DIRECTOR OF PLANNING:

CITY ENGINEER:

PLEASE CHECK THE APPROPRIATE BOX BELOW TO INDICATE THE TYPE OF DEVELOPMENT REQUEST (SELECT ONLY ONE BOX):

PLATTING APPLICATION FEES:

- MASTER PLAT (\$100.00 + \$15.00 ACRE) ¹
- PRELIMINARY PLAT (\$200.00 + \$15.00 ACRE) ¹
- FINAL PLAT (\$300.00 + \$20.00 ACRE) ¹
- REPLAT (\$300.00 + \$20.00 ACRE) ¹ (\$565.72)
- AMENDING OR MINOR PLAT (\$150.00)
- PLAT REINSTATEMENT REQUEST (\$100.00)

SITE PLAN APPLICATION FEES:

- SITE PLAN (\$250.00 + \$20.00 ACRE) ¹
- AMENDED SITE PLAN/ELEVATIONS/LANDSCAPING PLAN (\$100.00)

ZONING APPLICATION FEES:

- ZONING CHANGE (\$200.00 + \$15.00 ACRE) ¹
- SPECIFIC USE PERMIT (\$200.00 + \$15.00 ACRE) ^{1&2}
- PD DEVELOPMENT PLANS (\$200.00 + \$15.00 ACRE) ¹

OTHER APPLICATION FEES:

- TREE REMOVAL (\$75.00)
- VARIANCE REQUEST/SPECIAL EXCEPTIONS (\$100.00) ²

NOTES:

¹: IN DETERMINING THE FEE, PLEASE USE THE EXACT ACREAGE WHEN MULTIPLYING BY THE PER ACRE AMOUNT. FOR REQUESTS ON LESS THAN ONE ACRE, ROUND UP TO ONE (1) ACRE.

²: A \$1,000.00 FEE WILL BE ADDED TO THE APPLICATION FEE FOR ANY REQUEST THAT INVOLVES CONSTRUCTION WITHOUT OR NOT IN COMPLIANCE TO AN APPROVED BUILDING PERMIT.

PROPERTY INFORMATION [PLEASE PRINT]

ADDRESS NWC of Hwy 205 and Future FM 549

SUBDIVISION Creekside Commons LOT 15,16 & 18 BLOCK A

GENERAL LOCATION NWC of Hwy 205 and Future FM 549

ZONING, SITE PLAN AND PLATTING INFORMATION [PLEASE PRINT]

CURRENT ZONING Commercial (C) CURRENT USE Undeveloped

PROPOSED ZONING Commercial (C) PROPOSED USE Restaurant w/ drive-through

ACREAGE 13.286 LOTS [CURRENT] 15,16 & 18 LOTS [PROPOSED] 19,20 & 21

SITE PLANS AND PLATS: BY CHECKING THIS BOX YOU ACKNOWLEDGE THAT DUE TO THE PASSAGE OF HB3167 THE CITY NO LONGER HAS FLEXIBILITY WITH REGARD TO ITS APPROVAL PROCESS, AND FAILURE TO ADDRESS ANY OF STAFF'S COMMENTS BY THE DATE PROVIDED ON THE DEVELOPMENT CALENDAR WILL RESULT IN THE DENIAL OF YOUR CASE.

OWNER/APPLICANT/AGENT INFORMATION [PLEASE PRINT/CHECK THE PRIMARY CONTACT/ORIGINAL SIGNATURES ARE REQUIRED]

<input type="checkbox"/> OWNER	Creekside Commons Crossing LP	<input checked="" type="checkbox"/> APPLICANT	The Dimension Group
CONTACT PERSON	Michael Hampton	CONTACT PERSON	Keaton Mai
ADDRESS	[REDACTED]	ADDRESS	[REDACTED]
CITY, STATE & ZIP	[REDACTED]	CITY, STATE & ZIP	[REDACTED]
PHONE	[REDACTED]	PHONE	[REDACTED]
E-MAIL	[REDACTED]	E-MAIL	[REDACTED]

NOTARY VERIFICATION [REQUIRED]

BEFORE ME, THE UNDERSIGNED AUTHORITY, ON THIS DAY PERSONALLY APPEARED Michael Hampton [OWNER] THE UNDERSIGNED, WHO STATED THE INFORMATION ON THIS APPLICATION TO BE TRUE AND CERTIFIED THE FOLLOWING:


I HEREBY CERTIFY THAT I AM THE OWNER FOR THE PURPOSE OF THIS APPLICATION; ALL INFORMATION SUBMITTED HEREIN IS TRUE AND CORRECT; AND THE APPLICATION FEE OF \$ 565.72 TO COVER THE COST OF THIS APPLICATION, HAS BEEN PAID TO THE CITY OF ROCKWALL ON THIS THE 16th DAY OF JANUARY, 2026 BY SIGNING THIS APPLICATION, I AGREE THAT THE CITY OF ROCKWALL (I.E. "CITY") IS AUTHORIZED AND PERMITTED TO PROVIDE INFORMATION CONTAINED WITHIN THIS APPLICATION TO THE PUBLIC. THE CITY IS ALSO AUTHORIZED AND PERMITTED TO REPRODUCE ANY COPYRIGHTED INFORMATION SUBMITTED IN CONJUNCTION WITH THIS APPLICATION, IF SUCH REPRODUCTION IS ASSOCIATED OR IN RESPONSE TO A REQUEST FOR PUBLIC INFORMATION."


GIVEN UNDER MY HAND AND SEAL OF OFFICE ON THIS THE 16th DAY OF January, 2026

OWNER'S SIGNATURE

[Signature of Michael Hampton]
[Signature of Kathy Granberg]

NOTARY PUBLIC IN AND FOR THE STATE OF TEXAS





P2026-004: Replat for Lots 19-21, Block A, Creekside Commons Addition

Case Location Map = 






City of Rockwall

Planning & Zoning Department
 385 S. Goliad Street
 Rockwall, Texas 75087
 (P): (972) 771-7745
 (W): www.rockwall.com


The City of Rockwall GIS maps are continually under development and therefore subject to change without notice. While we endeavor to provide timely and accurate information, we make no guarantees. The City of Rockwall makes no warranty, express or implied, including warranties of merchantability and fitness for a particular purpose. Use of the information is the sole responsibility of the user.





CURVE #	LENGTH	RADIUS	DELTA	CHORD
C1	81.75'	1155.00'	4°03'19"	S58° 43' 21"W 81.73'
C2	160.34'	1110.00'	8°16'36"	S56° 38' 44"W 160.20'
C3	28.00'	36.00'	44°33'46"	S66° 35' 16"W 27.30'

LINE #	LENGTH	DIRECTION
L1	114.68'	S33°19'17"E
L2	25.09'	S29°29'58"E
L3	269.61'	S44°06'48"W
L4	228.23'	N45°52'18"W
L5	269.64'	N44°08'20"E
L6	22.85'	N45°51'55"W
L7	121.80'	N1°07'51"W
L8	217.17'	S1°14'47"E
L9	45.15'	S88°52'09"W
L10	21.83'	S44°43'37"W
L11	169.64'	N45°51'55"W
L12	81.31'	S45°51'55"E



LEGEND:

IRF IRON ROD FOUND
PC "TXDOT" IRON ROD FOUND WITH PINK CAP STAMPED "TXDOT"
YC "TXHS" IRON ROD FOUND WITH YELLOW CAP STAMPED "TXHS"
IRS IRON ROD SET WITH YELLOW CAP STAMPED "TXHS"
-CM- CONTROLLING MONUMENT
D.R.R.C.T. DEED RECORDS, ROCKWALL COUNTY, TEXAS
M.R.R.C.T. MAP RECORDS, ROCKWALL COUNTY, TEXAS
O.P.R.R.C.T. OFFICIAL PUBLIC RECORDS, ROCKWALL COUNTY, TEXAS
INST. NO. INSTRUMENT NUMBER
VOL., PG. VOLUME, PAGE

ENGINEER
THE DIMENSION GROUP
10755 SANDHILL ROAD
DALLAS, TEXAS 75238
attn: KEATON MAI

OWNER
CREEKSIDE COMMONS CROSSING, LP
10755 SANDHILL ROAD
DALLAS, TEXAS 75238



SURVEYOR
TEXAS HERITAGE
SURVEYING, LLC

10610 Metric Drive, Suite 124, Dallas, TX 75243
Office 214-340-9700 Fax 214-340-9710
txheritage.com
Firm No. 10169300

FINAL PLAT
LOTS 19-21, BLOCK A
CREEKSIDE COMMONS ADDITION
BEING A REPLAT OF
LOTS 15, 16, & 18, BLOCK A,
CREEKSIDE COMMONS ADDITION
BEING 3 LOTS
13.286 ACRES / 578,731 SF
SITUATED IN THE
W. W. FORD SURVEY, ABSTRACT NO. 80
CITY OF ROCKWALL, ROCKWALL COUNTY, TEXAS

PARCEL CURVE TABLE				
CURVE #	LENGTH	RADIUS	DELTA	CHORD
C4	28.00'	36.00'	44°33'46"	S66° 35' 16"W 27.30'
C5	5.02'	25.00'	11°30'57"	N5° 51' 30"W 5.02'
C6	39.77'	25.00'	91°09'19"	S45° 40' 41"E 35.71'
C7	39.22'	25.00'	89°53'04"	S43° 48' 41"W 35.32'
C8	47.03'	20.00'	134°44'04"	S21° 30' 07"W 36.92'
C9	28.32'	20.00'	81°08'24"	S86° 26' 06"E 26.02'
C10	21.46'	49.00'	25°05'14"	N65° 32' 19"E 21.28'
C11	9.22'	49.00'	10°47'12"	N83° 28' 33"E 9.21'

PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L16	15.00'	N44°07'42"E
L17	52.07'	N45°52'18"W
L18	20.00'	N45°54'27"W
L19	51.04'	N43°59'07"E
L20	22.38'	N1°00'53"W
L21	153.66'	N43°59'07"E
L22	11.87'	N45°30'22"W
L23	19.90'	N44°29'38"E
L24	11.70'	S46°00'53"E
L25	31.45'	N43°59'07"E

PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L26	35.20'	N46°00'53"W
L27	20.00'	N44°08'05"E
L28	35.15'	S45°51'55"E
L29	12.34'	N43°59'07"E
L30	35.29'	N88°52'09"E
L31	5.01'	N1°06'12"W
L32	20.00'	N88°52'09"E
L33	5.00'	S1°06'12"E
L34	453.33'	N88°52'09"E
L35	301.80'	S54°13'54"E



PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L36	18.16'	S29°14'52"E
L37	20.00'	S60°45'12"W
L38	13.73'	S29°14'52"E
L39	290.70'	N54°13'54"W
L40	493.69'	S88°52'09"W
L41	220.81'	S43°59'07"W
L42	22.38'	S1°00'53"E
L43	59.36'	S43°59'07"W
L44	134.56'	N88°52'09"E
L45	20.01'	N2°38'25"W

PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L46	586.72'	S88°52'09"W
L47	20.00'	S1°13'55"E
L48	25.89'	S44°06'48"W
L49	10.00'	S44°06'48"W
L50	16.89'	N45°53'12"W
L51	15.09'	S89°06'48"W
L52	200.57'	N45°53'12"W
L53	10.32'	N44°08'20"E
L54	196.43'	S45°47'38"E
L55	15.09'	N89°06'48"E


PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L56	21.03'	S45°53'12"E
L57	12.00'	N88°45'13"E
L58	193.03'	N88°45'13"E
L59	5.00'	S1°14'47"E
L60	192.63'	S88°45'13"W
L61	168.03'	N88°45'13"E
L62	24.00'	S1°14'47"E
L63	168.18'	S88°45'13"W
L64	74.45'	N1°07'51"W
L65	10.00'	N88°45'13"E

PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L66	182.71'	S1°14'47"E
L67	9.99'	S88°52'09"W
L68	12.02'	S1°14'47"E
L69	34.64'	S88°52'09"W
L70	71.67'	N45°51'55"W
L71	44.60'	N88°52'09"E
L72	11.98'	S1°14'47"E

PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L13	22.85'	N45°51'55"W
L14	45.15'	S88°52'09"W
L15	21.83'	S44°43'37"W




- LEGEND:
- IRF: IRON ROD FOUND
 - PC "TXDOT": IRON ROD FOUND WITH PINK CAP STAMPED "TXDOT"
 - IRS: IRON ROD SET WITH YELLOW CAP STAMPED "TXHS"
 - <CM>: CONTROLLING MONUMENT
 - D.R.R.C.T.: DEED RECORDS, ROCKWALL COUNTY, TEXAS
 - M.R.R.C.T.: MAP RECORDS, ROCKWALL COUNTY, TEXAS
 - O.P.R.R.C.T.: OFFICIAL PUBLIC RECORDS, ROCKWALL COUNTY, TEXAS
 - INST. NO.: INSTRUMENT NUMBER
 - VOL., PG.: VOLUME, PAGE
 - ESMT.: EASEMENT
 - WSEL: WATER SURFACE ELEVATION
 - MIN. F.F.E.: MINIMUM FINISHED FLOOR ELEVATION



BLOCK 1
SOMERSET PARK
INST. NO. 2018000001707
O.P.R.R.C.T.

BLOCK A
EDWARDS ACRES SUBDIVISION
INST. NO. 2014000006510
O.P.R.R.C.T.



SYLVANPARK DRIVE
(83' RIGHT-OF-WAY)

SANITARY SEWER ESMT.
INST. NO. 2017000002409
O.P.R.R.C.T.



10' ELECTRIC &
TELEPHONE ESMT.
INST. NO. 2014000006510
O.P.R.R.C.T.

15' WATER LINE ESMT.
INST. NO. 2014000006510
O.P.R.R.C.T.

BLOCK A
EDWARDS ACRES SUBDIVISION
INST. NO. 2014000006510
O.P.R.R.C.T.

10' ELECTRIC &
TELEPHONE ESMT.
INST. NO. 2014000006510
O.P.R.R.C.T.

15' WATER LINE ESMT.
INST. NO. 2014000006510
O.P.R.R.C.T.



LOT 21
476,460 SQ. FT.
10.938 ACRES
MIN. F.F.E. = 528.93

DETENTION ESMT.
INST. NO. 2024000004925
O.P.R.R.C.T.

SANITARY SEWER ESMT.
INST. NO. 2015000003475
D.R.R.C.T.

SANITARY SEWER ESMT.
INST. NO. 2015000003475
D.R.R.C.T.

100-YR WSEL = 519.58


15' WATER PIPELINE ESMT.
R.C.H. WATER SUPPLY CORP.
VOL. 64, PG. 319
D.R.R.C.T.

MIN. F.F.E. = 521.54

20' LANDSCAPE BUFFER
INST. NO. 2023000008813
O.P.R.R.C.T.

MATCH LINE PG 2

WILLIAM W. FORD SURVEY,
ABSTRACT NO. 80



100-YR WSEL = 526.93

20' WATER ESMT.
INST. NO. 2023000008813
O.P.R.R.C.T.

30' WASTEWATER ESMT.
INST. NO. 2023000008813
O.P.R.R.C.T.

100-YR WSEL = 518.87

10' UTILITY ESMT.
INST. NO. 2023000008813
O.P.R.R.C.T.

25' BUILDING LINE
INST. NO. 2023000008813
O.P.R.R.C.T.

CH=S58°43'21"W 81.73'
L=81.75', R=1155.00'
A=4°03'19"

CREEKSIDE COMMONS ADDITION
BLOCK A

578,731 SQ. FT.
13.286 ACRES

CREEKSIDE COMMONS CROSSING, LP
INST. NO. 2022000021201
O.P.R.R.C.T.


20' DRAINAGE ESMT.
INST. NO. 2024000004925
O.P.R.R.C.T.

1/2" IRF
YC *TXHS*
S 29°29'58" E
25.09'

STATE HIGHWAY 549
(VARIABLE WIDTH RIGHT-OF-WAY)

MATCH LINE PG 5

MATCH LINE PG 2



VISIBILITY ESMT.
INST. NO. 2024000004925
O.P.R.R.C.T.

VISIBILITY ESMT.
INST. NO. 2024000004925
O.P.R.R.C.T.

1/2" IRF
YC 'SUMMIT'

STATE OF TEXAS
INST. NO. 20180000021509
O.P.R.R.C.T.

STATE HIGHWAY 205
(VARIABLE WIDTH RIGHT-OF-WAY)

STATE OF TEXAS
INST. NO. 20210000017067
O.P.R.R.C.T.

VISIBILITY ESMT.
INST. NO. 2024000004925
O.P.R.R.C.T.

VISIBILITY ESMT.
INST. NO. 2024000004925
O.P.R.R.C.T.

1/2" IRF
YC 'SUMMIT'

STATE OF TEXAS
INST. NO. 20180000021509
O.P.R.R.C.T.

STATE HIGHWAY 205
(VARIABLE WIDTH RIGHT-OF-WAY)

STATE OF TEXAS
INST. NO. 20210000017067
O.P.R.R.C.T.

20' DRAINAGE ESMT.
INST. NO. 2024000004925
O.P.R.R.C.T.

LOT 14
BLOCK A
CREEKSIDE COMMONS
INST. NO. 2024000004925
O.P.R.R.C.T.

24' FIRELANE, ACCESS,
& UTILITY ESMT.
INST. NO. 20230000008813
O.P.R.R.C.T.

549 CROSSING, LP
INST. NO. 20210000028395
O.P.R.R.C.T.

LOT 1
BLOCK A
CREEKSIDE COMMONS
INST. NO. 20230000008813
O.P.R.R.C.T.

15' UTILITY ESMT.
INST. NO. 20230000008813
O.P.R.R.C.T.

25' BUILDING LINE
INST. NO. 20230000008813
O.P.R.R.C.T.

20' LANDSCAPE BUFFER
INST. NO. 20230000008813
O.P.R.R.C.T.

DETENTION ESMT.
INST. NO. 20230000008813
O.P.R.R.C.T.

GENERAL NOTES:

1) Subdivider's Statement: Selling a portion of this addition by metes and bounds is unlawful and a violation of the Subdivision Ordinance of the City of Rockwall and Chapter 212, Municipal Regulation of Subdivisions and Property Development, of the Texas Local Government Code, and shall be subject to the City of Rockwall withholding utilities and building permits.

2) Public Improvement Statement: It shall be the policy of the City of Rockwall to withhold issuing building permits until all streets, water, sewer and storm drainage systems have been accepted by the City. The approval of a subdivision plat by the City does not constitute any representation, assurance or guarantee that any building within such plat shall be approved, authorized or permit issued, nor shall such approval constitute any representation, assurance or guarantee by the City of Rockwall of the adequacy and availability for water and sanitary sewer for personal use and fire protection within such subdivision plat, as required under the Subdivision Ordinance of the City of Rockwall.

3) Drainage and Detention Easements: Property owner shall be responsible for maintaining, repairing, and replacing and shall bear sole liability of all systems within the drainage and detention easements.

4) Fire Lanes: All Fire Lanes will be constructed, maintained, repaired and replaced by the property owner. Fire Lanes shall be constructed in accordance with the approved Civil Engineering Plans for both on-site and off-site Fire Lane improvements.

5) Street Appurtenances: All decorative signage, posts, or lights installed in public right-of-way shall be installed, maintained, repaired, and replaced by the homeowner's association (HOA).

6) Bearings are based upon the Texas State Plane Coordinate System, Texas North Central Zone (4202), North American Datum of 1983 (2011).

7) The purpose of this replat is to create easements and change lot boundary lines.

8) Benchmarks:

COR-8: Aluminum disk stamped "City of Rockwall Survey Monument" at the northerly intersection of Silver View Lane and Diamond Way Drive ± 1 foot north of curb line in center of curve.
N= 7,018,063.113; E= 2,609,533.682; Elevation= 600.48'

COR-9: Brass disk stamped "City of Rockwall Survey Monument" on the south side of Discovery Boulevard at the southeaster corner of curb inlet ± 180 feet east intersection of Discovery/Corporate.
N= 7,020,550.132; E= 2,607,463.893; Elevation= 595.63'


9) Zoning: Commercial (C) District

10) Base Flood Elevation information per FEMA GIS, FIRM Panel #48397C0045L.

11) All Visibility Easements are 30'x30' unless otherwise noted.

12) WSEL information based upon Floodplain / Detention Study NDMCE No. 23-014 by Nathan D. Maier Consulting Engineers, Inc. completed December of 2023.

MATCH LINE PG 5



MATCH LINE PG 3

MATCH LINE PG 4

OWNER'S CERTIFICATE:

STATE OF TEXAS
COUNTY OF ROCKWALL

WHEREAS, Creekside Commons Crossing, LP is the owner of that tract of land situated in the William W. Ford Survey, Abstract No. 80, City of Rockwall, Rockwall County, Texas, being Lots 15, 16, & 18, Block A of Creekside Commons, an addition to the City of Rockwall, Rockwall County, Texas according to the plat thereof recorded in Instrument Number 20240000004925 of the Official Public Records of Rockwall County, Texas, and being a part of that tract of land described in Special Warranty Deed to Creekside Commons Crossing, LP recorded in Instrument Number 20220000021201 of the Official Public Records of Rockwall County, Texas, and being more particularly described by metes and bounds as follows:

Commencing at a 1/2 inch iron rod with yellow plastic cap stamped "TXHS" found for corner, said corner being in the northeast corner of that tract of land described as Parcel 1 Part 1 in deed to the State of Texas recorded in Instrument Number 20180000021509 of the Official Public Records of Rockwall County, Texas, said corner also being the northwest corner of Lot 17, Block A of said Creekside Commons Addition, said corner also being in the south right-of-way line of existing State Highway 549 (variable width right-of-way);

Thence North 88 degrees 45 minutes 13 seconds East, along the south right-of-way line of said existing State Highway 549, a distance of 491.43 feet to an "X" found for corner, said corner being the northeast corner of said Lot 17, Block A, said corner being the POINT OF BEGINNING;

Thence North 88 degrees 45 minutes 13 seconds East, along the south right-of-way line of said existing State Highway 549, a distance of 1,358.95 feet to a 5/8 inch iron rod with pink plastic cap stamped "TXDOT" found for corner, said corner being the northwest corner of that tract of land described as Parcel 1 Part 2 in deed to the State of Texas recorded in Instrument Number 20180000021509 of the Official Public Records of Rockwall County, Texas, said corner also being the most northerly northeast corner of said Lot 18, Block A, said corner also being in a northwest right-of-way line of new State Highway 549 (variable width right-of-way);

Thence, along the northwest line of said State of Texas Parcel 1 Part 2 tract and along the northwest line of said new State Highway 549, the following courses and distances:

Thence South 33 degrees 19 minutes 17 seconds East, a distance of 114.68 feet to a 1/2 inch iron rod with yellow plastic cap stamped "TXHS" found for corner, said corner being the beginning of a non-tangent curve to the right, having a delta of 04 degrees 03 minutes 19 seconds, a radius of 1,155.00 feet and a chord bearing and distance of South 58 degrees 43 minutes 21 seconds West, 81.73 feet;

Thence, in a southwesterly direction, along said curve to the right, an arc length of 81.75 feet to a 5/8 inch iron rod with pink plastic cap stamped "TXDOT" found for corner;

Thence South 60 degrees 46 minutes 14 seconds West, a distance of 382.65 feet to a 1/2 inch iron rod with yellow plastic cap stamped "TXHS" found for corner;

Thence South 29 degrees 29 minutes 58 seconds East, a distance of 25.09 feet to a 1/2 inch iron rod with yellow plastic cap stamped "TXHS" found for corner;

Thence South 60 degrees 45 minutes 08 seconds West, a distance of 437.07 feet to a "X" found for corner, said corner being the beginning of a non-tangent curve to the left, having a delta of 08 degrees 16 minutes 36 seconds, a radius of 1,110.00 feet and a chord bearing and distance of South 56 degrees 38 minutes 44 seconds West, 160.20 feet;

Thence, in a southwesterly direction, along said curve to the left, an arc length of 160.34 feet to a 1/2 inch iron rod with yellow plastic cap stamped "TXHS" found for corner, said corner being the east corner of Lot 1, Block A of said Creekside Commons, an addition to the City of Rockwall, Rockwall County, Texas according to the plat thereof recorded in Instrument Number 20230000008813 of the Official Public Records of Rockwall County, Texas;

Thence North 45 degrees 53 minutes 13 seconds West, along the northeast line of said Lot 1, Block A, a distance of 261.06 feet to an "X" found for corner, said corner being the north corner of said Lot 1, Block A, said corner also being the east corner of Lot 14, Block A of said Creekside Commons Addition (Inst. No. 20240000004925);

Thence North 45 degrees 51 minutes 55 seconds West, along the northeast line of said Lot 14, Block A, a distance of 202.16 feet to an "X" found for corner, said corner being the north corner of said Lot 14, Block A;


Thence South 44 degrees 06 minutes 48 seconds West, along the northwest line of said Lot 14, Block A, a distance of 269.61 feet to a 1/2 inch iron rod with cap stamped "SUMMIT" found for corner, said corner being the west corner of said Lot 14, Block A, said corner also being in the northeast line of said State of Texas Parcel 1 Part 1 tract;

Thence North 45 degrees 52 minutes 18 seconds West, along a northeast line of said State of Texas Parcel 1 Part 1 tract, a distance of 228.23 feet to a 1/2 inch iron rod with yellow plastic cap stamped "TXHS" found for corner, said corner being the south corner of said Lot 17, Block A;

Thence North 44 degrees 08 minutes 20 seconds East, along the southeast line of said Lot 17, Block A, a distance of 269.64 feet to an "X" found for corner, said corner being the east corner of said Lot 17, Block A;

Thence North 45 degrees 51 minutes 55 seconds West, along the easterly line of said Lot 17, Block A, a distance of 22.85 feet to an "X" found for corner;

Thence North 01 degrees 07 minutes 51 seconds West, along the easterly line of said Lot 17, Block A, a distance of 121.80 feet to the POINT OF BEGINNING and containing 578,731 square feet or 13.286 acres of land.



OWNER'S DEDICATION:

NOW THEREFORE, KNOW ALL MEN BY THESE PRESENTS:

STATE OF TEXAS
COUNTY OF ROCKWALL

I the undersigned owner of the land shown on this plat, and designated herein as the CREEKSIDE COMMONS ADDITION subdivision to the City of Rockwall, Texas, and whose name is subscribed hereto, hereby dedicate to the use of the public forever all streets, alleys, parks, water courses, drains, easements and public places thereon shown on the purpose and consideration therein expressed. I further certify that all other parties who have a mortgage or lien interest in the CREEKSIDE COMMONS ADDITION subdivision have been notified and signed this plat. I understand and do hereby reserve the easement strips shown on this plat for the purposes stated and for the mutual use and accommodation of all utilities desiring to use or using same. I also understand the following;

1. No buildings shall be constructed or placed upon, over, or across the utility easements as described herein.
2. Any public utility shall have the right to remove and keep removed all or part of any buildings, fences, trees, shrubs, or other growths or improvements which in any way endanger or interfere with construction, maintenance or efficiency of their respective system on any of these easement strips; and any public utility shall at all times have the right of ingress or egress to, from and upon the said easement strips for purposes of construction, reconstruction, inspecting, patrolling, maintaining, and either adding to or removing all or part of their respective system without the necessity of, at any time, procuring the permission of anyone.
3. The City of Rockwall will not be responsible for any claims of any nature resulting from or occasioned by the establishment of grade of streets in the subdivision.
4. The developer/property owner and subdivision engineer shall bear total responsibility for storm drain improvements.
5. The developer/property owner shall be responsible for the necessary facilities to provide drainage patterns and drainage controls such that properties within the drainage area are not adversely affected by storm drainage from the development.
6. No house dwelling unit, or other structure shall be constructed on any lot in this addition by the owner or any other person until the developer and/or owner has complied with all requirements of the Subdivision Regulations of the City of Rockwall regarding improvements with respect to the entire block on the street or streets on which property abuts, including the actual installation of streets with the required base and paving, curb and gutter, water and sewer, drainage structures, storm structures, storm sewers, and alleys, all according to the specifications of the City of Rockwall; or

Until an escrow deposit, sufficient to pay for the cost of such improvements, as determined by the city's engineer and/or city administrator, computed on a private commercial rate basis, has been made with the city secretary, accompanied by an agreement signed by the developer and/or owner, authorizing the city to make such improvements at prevailing private commercial rates, or have the same made by a contractor and pay for the same out of the escrow deposit, should the developer and/or owner fail or refuse to install the required improvements within the time stated in such written agreement, but in no case shall the City be obligated to make such improvements itself. Such deposit may be used by the owner and/or developer as progress payments as the work progresses in making such improvements by making certified requisitions to the city secretary, supported by evidence of work done; or

Until the developer and/or owner files a corporate surety bond with the city secretary in a sum equal to the cost of such improvements for the designated area, guaranteeing the installation thereof within the time stated in the bond, which time shall be fixed by the city council of the City of Rockwall.

I further acknowledge that the dedications and/or exaction's made herein are proportional to the impact of the Subdivision upon the public services required in order that the development will comport with the present and future growth needs of the City; I, my successors and assigns hereby waive any claim, damage or cause of action that I may have as a result of the dedication of exactions made herein.

Creekside Commons Crossing, LP

Jassem Setayesh
President/CEO

STATE OF TEXAS
COUNTY OF DALLAS

BEFORE ME, the undersigned authority, on this day personally appeared Jassem Setayesh, a Texas limited liability company, known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that he executed the same for the purposes and considerations therein stated.

GIVEN UNDER MY HAND AND SEAL OF OFFICE, this _____ day of _____, 2026.

Notary Signature

SURVEYORS CERTIFICATE:

I, J. R. January, do hereby certify that I prepared this plat from an actual and accurate survey of the land, and that the corner monuments shown thereon were properly placed under my personal supervision.

J. R. January, R.P.L.S. No. 5382

APPROVED: I hereby certify that the above and foregoing Subdivision Plat was reviewed by the Planning and Zoning Commission and approved by the City Council of the City of Rockwall, Texas for the preparation of a Final Plat on the _____ day of _____, 2026.

Mayor of the City of Rockwall

Planning and Zoning Chairman

City Secretary

City Engineer

ENGINEER
THE DIMENSION GROUP
10755 SANDHILL ROAD
DALLAS, TEXAS 75238
attn: KEATON MAI

OWNER
CREEKSIDE COMMONS CROSSING, LP
10755 SANDHILL ROAD
DALLAS, TEXAS 75238



SURVEYOR
TEXAS HERITAGE
SURVEYING, LLC
10610 Metric Drive, Suite 124, Dallas, TX 75243
Office 214-340-9700 Fax 214-340-9710
txheritage.com
Firm No. 10169300

FINAL PLAT
LOTS 19-21, BLOCK A
CREEKSIDE COMMONS ADDITION
BEING A REPLAT OF
LOTS 15, 16, & 18, BLOCK A,
CREEKSIDE COMMONS ADDITION
BEING 3 LOTS
13.286 ACRES / 578,731 SF
SITUATED IN THE
W. W. FORD SURVEY, ABSTRACT NO. 80
CITY OF ROCKWALL, ROCKWALL COUNTY, TEXAS



CITY OF ROCKWALL

CITY COUNCIL CASE MEMO

PLANNING AND ZONING DEPARTMENT

385 S. GOLIAD STREET • ROCKWALL, TX 75087

PHONE: (972) 771-7745 • EMAIL: PLANNING@ROCKWALL.COM

TO: Mayor and City Council
DATE: February 2, 2026
APPLICANT: Keaton Mai; *Dimension Group*
CASE NUMBER: P2026-004; *Replat for Lots 19-21, Block A, Creekside Commons Addition*

SUMMARY

Consider a request by Keaton Mai of Dimension Group on behalf of Michael Hampton of Creekside Commons Crossing, LP for the approval of a Replat for Lots 19-21, Block A, Creekside Commons Addition being a 13.286-acre tract of land identified as Lots 15, 16 & 18, Block A, Creekside Commons Addition, City of Rockwall, Rockwall County, Texas, zoned Commercial (C) District, generally located at the southwest corner of the intersection of FM-549 and S. Goliad Street [SH-205], and take any action necessary.

PLAT INFORMATION

- ☑ Purpose. The applicant is requesting approval of a Replat for three (3) existing parcels of land on 13.286-acres (*i.e. Lots 15-18, Block A, Creekside Commons Addition*) in order to establish three (3) new lots (*i.e. Lots 19-21, Block A, Creekside Commons Addition*). The purpose of the Replat is to dedicate new easements and adjust the lot lines of the three (3) existing lots in order to facilitate the future development of the subject property.
- ☑ Background. The subject property was annexed on May 19, 1986 by *Ordinance No. 86-37 [Case No. A1986-005]*. On March 4, 2013, the City Council approved a zoning case [*Case No. Z2013-002*] that rezoned the subject property from an Agricultural (AG) District to a Commercial (C) District. A preliminary plat [*Case No. P2021-027*] was approved by the City Council on June 7, 2021. This preliminary plat was amended by the City Council through *Case No. P2022-030* on July 5, 2022. On November 7, 2022, the City Council approved a final plat [*Case No. P2022-052*] that established the subject property as Lots 2-6, Block A, Creekside Commons Addition. On February 4, 2024, the City Council approved a replat that establish the subject property as Lots 15-18, Block A, Creekside Commons Addition. On October 14, 2025, the Planning and Zoning Commission approved a site plan [*Case No. SP2025-039*] to allow the construction of a *Restaurant Greater than 2,000 SF, with a Drive Through or Drive-In* on a portion of the subject property.
- ☑ Conformance to the Subdivision Ordinance. The surveyor has completed the majority of the technical revisions requested by staff, and this plat -- *conforming to the requirements for plats as stipulated by the Subdivision Ordinance in the Municipal Code of Ordinances* -- is recommended for conditional approval pending the completion of final technical modifications, submittal requirements, and conformance to the items listed in the Conditions of Approval section of this case memo.
- ☑ Conditions of Approval. Conditional approval of this Replat by the City Council shall constitute approval subject to the conditions stipulated in the Conditions of Approval section below.

CONDITIONS OF APPROVAL

If the City Council chooses to approve the Replat for *Lots 19-21, Block A, Creekside Commons Addition*, staff would propose the following conditions of approval:

- (1) All technical comments from City Staff (*i.e. Engineering, Planning and Fire Department*) shall be addressed prior to submittal of civil engineering plans; and,

- (2) Any construction resulting from the approval of this Replat shall conform to the requirements set forth by the Unified Development Code (UDC), the International Building Code (IBC), the Rockwall Municipal Code of Ordinances, city adopted engineering and fire codes and with all other applicable regulatory requirements administered and/or enforced by the state and federal government.

PLANNING AND ZONING COMMISSION

On January 27, 2026, the Planning and Zoning Commission approved a motion to recommend approval of the Replat by a vote of 5-0, with Commissioners Conway and Brock absent.



DEVELOPMENT APPLICATION

City of Rockwall
Planning and Zoning Department
385 S. Goliad Street
Rockwall, Texas 75087

STAFF USE ONLY
PLANNING & ZONING CASE NO.

NOTE: THE APPLICATION IS NOT CONSIDERED ACCEPTED BY THE CITY UNTIL THE PLANNING DIRECTOR AND CITY ENGINEER HAVE SIGNED BELOW.

DIRECTOR OF PLANNING:

CITY ENGINEER:

PLEASE CHECK THE APPROPRIATE BOX BELOW TO INDICATE THE TYPE OF DEVELOPMENT REQUEST (SELECT ONLY ONE BOX):

PLATTING APPLICATION FEES:

- MASTER PLAT (\$100.00 + \$15.00 ACRE) ¹
- PRELIMINARY PLAT (\$200.00 + \$15.00 ACRE) ¹
- FINAL PLAT (\$300.00 + \$20.00 ACRE) ¹
- REPLAT (\$300.00 + \$20.00 ACRE) ¹ (\$565.72)
- AMENDING OR MINOR PLAT (\$150.00)
- PLAT REINSTATEMENT REQUEST (\$100.00)

SITE PLAN APPLICATION FEES:

- SITE PLAN (\$250.00 + \$20.00 ACRE) ¹
- AMENDED SITE PLAN/ELEVATIONS/LANDSCAPING PLAN (\$100.00)

ZONING APPLICATION FEES:

- ZONING CHANGE (\$200.00 + \$15.00 ACRE) ¹
- SPECIFIC USE PERMIT (\$200.00 + \$15.00 ACRE) ^{1&2}
- PD DEVELOPMENT PLANS (\$200.00 + \$15.00 ACRE) ¹

OTHER APPLICATION FEES:

- TREE REMOVAL (\$75.00)
- VARIANCE REQUEST/SPECIAL EXCEPTIONS (\$100.00) ²

NOTES:

¹: IN DETERMINING THE FEE, PLEASE USE THE EXACT ACREAGE WHEN MULTIPLYING BY THE PER ACRE AMOUNT. FOR REQUESTS ON LESS THAN ONE ACRE, ROUND UP TO ONE (1) ACRE.

²: A \$1,000.00 FEE WILL BE ADDED TO THE APPLICATION FEE FOR ANY REQUEST THAT INVOLVES CONSTRUCTION WITHOUT OR NOT IN COMPLIANCE TO AN APPROVED BUILDING PERMIT.

PROPERTY INFORMATION [PLEASE PRINT]

ADDRESS NWC of Hwy 205 and Future FM 549

SUBDIVISION Creekside Commons LOT 15,16 & 18 BLOCK A

GENERAL LOCATION NWC of Hwy 205 and Future FM 549

ZONING, SITE PLAN AND PLATTING INFORMATION [PLEASE PRINT]

CURRENT ZONING Commercial (C) CURRENT USE Undeveloped

PROPOSED ZONING Commercial (C) PROPOSED USE Restaurant w/ drive-through

ACREAGE 13.286 LOTS [CURRENT] 15,16 & 18 LOTS [PROPOSED] 19,20 & 21

SITE PLANS AND PLATS: BY CHECKING THIS BOX YOU ACKNOWLEDGE THAT DUE TO THE PASSAGE OF HB3167 THE CITY NO LONGER HAS FLEXIBILITY WITH REGARD TO ITS APPROVAL PROCESS, AND FAILURE TO ADDRESS ANY OF STAFF'S COMMENTS BY THE DATE PROVIDED ON THE DEVELOPMENT CALENDAR WILL RESULT IN THE DENIAL OF YOUR CASE.

OWNER/APPLICANT/AGENT INFORMATION [PLEASE PRINT/CHECK THE PRIMARY CONTACT/ORIGINAL SIGNATURES ARE REQUIRED]

<input type="checkbox"/> OWNER	Creekside Commons Crossing LP	<input checked="" type="checkbox"/> APPLICANT	The Dimension Group
CONTACT PERSON	Michael Hampton	CONTACT PERSON	Keaton Mai
ADDRESS	[REDACTED]	ADDRESS	[REDACTED]
CITY, STATE & ZIP	[REDACTED]	CITY, STATE & ZIP	[REDACTED]
PHONE	[REDACTED]	PHONE	[REDACTED]
E-MAIL	[REDACTED]	E-MAIL	[REDACTED]

NOTARY VERIFICATION [REQUIRED]

BEFORE ME, THE UNDERSIGNED AUTHORITY, ON THIS DAY PERSONALLY APPEARED Michael Hampton [OWNER] THE UNDERSIGNED, WHO STATED THE INFORMATION ON THIS APPLICATION TO BE TRUE AND CERTIFIED THE FOLLOWING:


I HEREBY CERTIFY THAT I AM THE OWNER FOR THE PURPOSE OF THIS APPLICATION; ALL INFORMATION SUBMITTED HEREIN IS TRUE AND CORRECT; AND THE APPLICATION FEE OF \$ 565.72 TO COVER THE COST OF THIS APPLICATION, HAS BEEN PAID TO THE CITY OF ROCKWALL ON THIS THE 16th DAY OF JANUARY, 2026 BY SIGNING THIS APPLICATION, I AGREE THAT THE CITY OF ROCKWALL (I.E. "CITY") IS AUTHORIZED AND PERMITTED TO PROVIDE INFORMATION CONTAINED WITHIN THIS APPLICATION TO THE PUBLIC. THE CITY IS ALSO AUTHORIZED AND PERMITTED TO REPRODUCE ANY COPYRIGHTED INFORMATION SUBMITTED IN CONJUNCTION WITH THIS APPLICATION, IF SUCH REPRODUCTION IS ASSOCIATED OR IN RESPONSE TO A REQUEST FOR PUBLIC INFORMATION."


GIVEN UNDER MY HAND AND SEAL OF OFFICE ON THIS THE 16th DAY OF January, 2026

OWNER'S SIGNATURE

[Signature of Michael Hampton]
[Signature of Kathy Granberg]

NOTARY PUBLIC IN AND FOR THE STATE OF TEXAS








City of Rockwall

Planning & Zoning Department
 385 S. Goliad Street
 Rockwall, Texas 75087
 (P): (972) 771-7745
 (W): www.rockwall.com


The City of Rockwall GIS maps are continually under development and therefore subject to change without notice. While we endeavor to provide timely and accurate information, we make no guarantees. The City of Rockwall makes no warranty, express or implied, including warranties of merchantability and fitness for a particular purpose. Use of the information is the sole responsibility of the user.





CURVE #	LENGTH	RADIUS	DELTA	CHORD
C1	81.75'	1155.00'	4°03'19"	S58° 43' 21"W 81.73'
C2	160.34'	1110.00'	8°16'36"	S56° 38' 44"W 160.20'
C3	28.00'	36.00'	44°33'46"	S66° 35' 16"W 27.30'

LINE #	LENGTH	DIRECTION
L1	114.68'	S33°19'17"E
L2	25.09'	S29°29'58"E
L3	269.61'	S44°06'48"W
L4	228.23'	N45°52'18"W
L5	269.64'	N44°08'20"E
L6	22.85'	N45°51'55"W
L7	121.80'	N1°07'51"W
L8	217.17'	S1°14'47"E
L9	45.15'	S88°52'09"W
L10	21.83'	S44°43'37"W
L11	169.64'	N45°51'55"W
L12	81.31'	S45°51'55"E



LEGEND:

IRF IRON ROD FOUND
PC "TXDOT" IRON ROD FOUND WITH PINK CAP STAMPED "TXDOT"
YC "TXHS" IRON ROD FOUND WITH YELLOW CAP STAMPED "TXHS"
IRS IRON ROD SET WITH YELLOW CAP STAMPED "TXHS"
-CM- CONTROLLING MONUMENT
D.R.R.C.T. DEED RECORDS, ROCKWALL COUNTY, TEXAS
M.R.R.C.T. MAP RECORDS, ROCKWALL COUNTY, TEXAS
O.P.R.R.C.T. OFFICIAL PUBLIC RECORDS, ROCKWALL COUNTY, TEXAS
INST. NO. INSTRUMENT NUMBER
VOL., PG. VOLUME, PAGE

ENGINEER
THE DIMENSION GROUP
10755 SANDHILL ROAD
DALLAS, TEXAS 75238
attn: KEATON MAI

OWNER
CREEKSIDE COMMONS CROSSING, LP
10755 SANDHILL ROAD
DALLAS, TEXAS 75238



SURVEYOR
TEXAS HERITAGE
SURVEYING, LLC
10610 Metric Drive, Suite 124, Dallas, TX 75243
Office 214-340-9700 Fax 214-340-9710
txheritage.com
Firm No. 10169300

FINAL PLAT
LOTS 19-21, BLOCK A
CREEKSIDE COMMONS ADDITION
BEING A REPLAT OF
LOTS 15, 16, & 18, BLOCK A,
CREEKSIDE COMMONS ADDITION
BEING 3 LOTS
13.286 ACRES / 578,731 SF
SITUATED IN THE
W. W. FORD SURVEY, ABSTRACT NO. 80
CITY OF ROCKWALL, ROCKWALL COUNTY, TEXAS

PARCEL CURVE TABLE				
CURVE #	LENGTH	RADIUS	DELTA	CHORD
C4	28.00'	36.00'	44°33'46"	S66° 35' 16"W 27.30'
C5	5.02'	25.00'	11°30'57"	N5° 51' 30"W 5.02'
C6	39.77'	25.00'	91°09'19"	S45° 40' 41"E 35.71'
C7	39.22'	25.00'	89°53'04"	S43° 48' 41"W 35.32'
C8	47.03'	20.00'	134°44'04"	S21° 30' 07"W 36.92'
C9	28.32'	20.00'	81°08'24"	S86° 26' 06"E 26.02'
C10	21.46'	49.00'	25°05'14"	N65° 32' 19"E 21.28'
C11	9.22'	49.00'	10°47'12"	N83° 28' 33"E 9.21'

PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L16	15.00'	N44°07'42"E
L17	52.07'	N45°52'18"W
L18	20.00'	N45°54'27"W
L19	51.04'	N43°59'07"E
L20	22.38'	N1°00'53"W
L21	153.66'	N43°59'07"E
L22	11.87'	N45°30'22"W
L23	19.90'	N44°29'38"E
L24	11.70'	S46°00'53"E
L25	31.45'	N43°59'07"E

PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L26	35.20'	N46°00'53"W
L27	20.00'	N44°08'05"E
L28	35.15'	S45°51'55"E
L29	12.34'	N43°59'07"E
L30	35.29'	N88°52'09"E
L31	5.01'	N1°06'12"W
L32	20.00'	N88°52'09"E
L33	5.00'	S1°06'12"E
L34	453.33'	N88°52'09"E
L35	301.80'	S54°13'54"E


PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L36	18.16'	S29°14'52"E
L37	20.00'	S60°45'12"W
L38	13.73'	S29°14'52"E
L39	290.70'	N54°13'54"W
L40	493.69'	S88°52'09"W
L41	220.81'	S43°59'07"W
L42	22.38'	S1°00'53"E
L43	59.36'	S43°59'07"W
L44	134.56'	N88°52'09"E
L45	20.01'	N2°38'25"W

PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L46	586.72'	S88°52'09"W
L47	20.00'	S1°13'55"E
L48	25.89'	S44°06'48"W
L49	10.00'	S44°06'48"W
L50	16.89'	N45°53'12"W
L51	15.09'	S89°06'48"W
L52	200.57'	N45°53'12"W
L53	10.32'	N44°08'20"E
L54	196.43'	S45°47'38"E
L55	15.09'	N89°06'48"E

PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L56	21.03'	S45°53'12"E
L57	12.00'	N88°45'13"E
L58	193.03'	N88°45'13"E
L59	5.00'	S1°14'47"E
L60	192.63'	S88°45'13"W
L61	168.03'	N88°45'13"E
L62	24.00'	S1°14'47"E
L63	168.18'	S88°45'13"W
L64	74.45'	N1°07'51"W
L65	10.00'	N88°45'13"E


PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L66	182.71'	S1°14'47"E
L67	9.99'	S88°52'09"W
L68	12.02'	S1°14'47"E
L69	34.64'	S88°52'09"W
L70	71.67'	N45°51'55"W
L71	44.60'	N88°52'09"E
L72	11.98'	S1°14'47"E

PARCEL LINE TABLE		
LINE #	LENGTH	DIRECTION
L13	22.85'	N45°51'55"W
L14	45.15'	S88°52'09"W
L15	21.83'	S44°43'37"W




LEGEND:

- IRF IRON ROD FOUND
- PC "TXDOT" IRON ROD FOUND WITH PINK CAP STAMPED "TXDOT"
- IRS IRON ROD SET WITH YELLOW CAP STAMPED "TXHS"
- <CM> CONTROLLING MONUMENT
- D.R.R.C.T. DEED RECORDS, ROCKWALL COUNTY, TEXAS
- M.R.R.C.T. MAP RECORDS, ROCKWALL COUNTY, TEXAS
- O.P.R.R.C.T. OFFICIAL PUBLIC RECORDS, ROCKWALL COUNTY, TEXAS
- INST. NO. INSTRUMENT NUMBER
- VOL., PG. VOLUME, PAGE
- ESMT. EASEMENT
- WSEL WATER SURFACE ELEVATION
- MIN. F.F.E. MINIMUM FINISHED FLOOR ELEVATION



BLOCK 1
SOMERSET PARK
INST. NO. 2018000001707
O.P.R.R.C.T.

BLOCK A
EDWARDS ACRES SUBDIVISION
INST. NO. 2014000006510
O.P.R.R.C.T.



SYLVANPARK DRIVE
(83' RIGHT-OF-WAY)

SANITARY SEWER ESMT.
INST. NO. 20170000002409
O.P.R.R.C.T.



10' ELECTRIC &
TELEPHONE ESMT.
INST. NO. 20140000006510
O.P.R.R.C.T.

15' WATER LINE ESMT.
INST. NO. 20140000006510
O.P.R.R.C.T.

BLOCK A
EDWARDS ACRES SUBDIVISION
INST. NO. 2014000006510
O.P.R.R.C.T.


10' ELECTRIC &
TELEPHONE ESMT.
INST. NO. 20140000006510
O.P.R.R.C.T.

15' WATER LINE ESMT.
INST. NO. 20140000006510
O.P.R.R.C.T.



MATCH LINE PG 2

WILLIAM W. FORD SURVEY,
ABSTRACT NO. 80



CREEKSIDE COMMONS ADDITION
BLOCK A

578,731 SQ. FT.
13.286 ACRES

CREEKSIDE COMMONS CROSSING, LP
INST. NO. 20220000021201
O.P.R.R.C.T.

SANITARY SEWER ESMT.
INST. NO. 20150000003475
D.R.R.C.T.

DETENTION ESMT.
INST. NO. 20240000004925
O.P.R.R.C.T.

SANITARY SEWER ESMT.
INST. NO. 20150000003475
D.R.R.C.T.

20' WATER ESMT.
INST. NO. 20230000008813
O.P.R.R.C.T.

20' DRAINAGE ESMT.
INST. NO. 20240000004925
O.P.R.R.C.T.

100-YR WSEL = 519.58

BFE = 519

30' WASTEWATER ESMT.
INST. NO. 20230000008813
O.P.R.R.C.T.

100-YR WSEL = 518.87

10' UTILITY ESMT.
INST. NO. 20230000008813
O.P.R.R.C.T.

15' WATER PIPELINE ESMT.
R.C.H. WATER SUPPLY CORP.
VOL. 64, PG. 319
D.R.R.C.T.


MIN. F.F.E. = 521.54

20' LANDSCAPE BUFFER
INST. NO. 20230000008813
O.P.R.R.C.T.

STATE HIGHWAY 549
(VARIABLE WIDTH RIGHT-OF-WAY)

MATCH LINE PG 5

MATCH LINE PG 2



VISIBILITY ESMT.
INST. NO. 2024000004925
O.P.R.R.C.T.

VISIBILITY ESMT.
INST. NO. 2024000004925
O.P.R.R.C.T.

1/2" IRF
YC 'SUMMIT'

STATE OF TEXAS
INST. NO. 20180000021509
O.P.R.R.C.T.

STATE HIGHWAY 205
(VARIABLE WIDTH RIGHT-OF-WAY)

STATE OF TEXAS
INST. NO. 20210000017067
O.P.R.R.C.T.

VISIBILITY ESMT.
INST. NO. 2024000004925
O.P.R.R.C.T.

VISIBILITY ESMT.
INST. NO. 2024000004925
O.P.R.R.C.T.

1/2" IRF
YC 'SUMMIT'

STATE OF TEXAS
INST. NO. 20180000021509
O.P.R.R.C.T.

STATE HIGHWAY 205
(VARIABLE WIDTH RIGHT-OF-WAY)

STATE OF TEXAS
INST. NO. 20210000017067
O.P.R.R.C.T.

20' DRAINAGE ESMT.
INST. NO. 2024000004925
O.P.R.R.C.T.

LOT 14
BLOCK A
CREEKSIDE COMMONS
INST. NO. 2024000004925
O.P.R.R.C.T.

24' FIRELANE, ACCESS,
& UTILITY ESMT.
INST. NO. 20230000008813
O.P.R.R.C.T.

549 CROSSING, LP
INST. NO. 20210000028395
O.P.R.R.C.T.

LOT 1
BLOCK A
CREEKSIDE COMMONS
INST. NO. 20230000008813
O.P.R.R.C.T.

15' UTILITY ESMT.
INST. NO. 20230000008813
O.P.R.R.C.T.

25' BUILDING LINE
INST. NO. 20230000008813
O.P.R.R.C.T.

20' LANDSCAPE BUFFER
INST. NO. 20230000008813
O.P.R.R.C.T.

DETENTION ESMT.
INST. NO. 20230000008813
O.P.R.R.C.T.

GENERAL NOTES:

1) Subdivider's Statement: Selling a portion of this addition by metes and bounds is unlawful and a violation of the Subdivision Ordinance of the City of Rockwall and Chapter 212, Municipal Regulation of Subdivisions and Property Development, of the Texas Local Government Code, and shall be subject to the City of Rockwall withholding utilities and building permits.

2) Public Improvement Statement: It shall be the policy of the City of Rockwall to withhold issuing building permits until all streets, water, sewer and storm drainage systems have been accepted by the City. The approval of a subdivision plat by the City does not constitute any representation, assurance or guarantee that any building within such plat shall be approved, authorized or permit issued, nor shall such approval constitute any representation, assurance or guarantee by the City of Rockwall of the adequacy and availability for water and sanitary sewer for personal use and fire protection within such subdivision plat, as required under the Subdivision Ordinance of the City of Rockwall.

3) Drainage and Detention Easements: Property owner shall be responsible for maintaining, repairing, and replacing and shall bear sole liability of all systems within the drainage and detention easements.

4) Fire Lanes: All Fire Lanes will be constructed, maintained, repaired and replaced by the property owner. Fire Lanes shall be constructed in accordance with the approved Civil Engineering Plans for both on-site and off-site Fire Lane improvements.

5) Street Appurtenances: All decorative signage, posts, or lights installed in public right-of-way shall be installed, maintained, repaired, and replaced by the homeowner's association (HOA).

6) Bearings are based upon the Texas State Plane Coordinate System, Texas North Central Zone (4202), North American Datum of 1983 (2011).

7) The purpose of this replat is to create easements and change lot boundary lines.

8) Benchmarks:

COR-8: Aluminum disk stamped "City of Rockwall Survey Monument" at the northerly intersection of Silver View Lane and Diamond Way Drive ± 1 foot north of curb line in center of curve.
N= 7,018,063.113; E= 2,609,533.682; Elevation= 600.48'

COR-9: Brass disk stamped "City of Rockwall Survey Monument" on the south side of Discovery Boulevard at the southeaster corner of curb inlet ± 180 feet east intersection of Discovery/Corporate.
N= 7,020,550.132; E= 2,607,463.893; Elevation= 595.63'


9) Zoning: Commercial (C) District

10) Base Flood Elevation information per FEMA GIS, FIRM Panel #48397C0045L.

11) All Visibility Easements are 30'x30' unless otherwise noted.

12) WSEL information based upon Floodplain / Detention Study NDMCE No. 23-014 by Nathan D. Maier Consulting Engineers, Inc. completed December of 2023.

MATCH LINE PG 5



MATCH LINE PG 3

MATCH LINE PG 4

OWNER'S CERTIFICATE:

STATE OF TEXAS
COUNTY OF ROCKWALL

WHEREAS, Creekside Commons Crossing, LP is the owner of that tract of land situated in the William W. Ford Survey, Abstract No. 80, City of Rockwall, Rockwall County, Texas, being Lots 15, 16, & 18, Block A of Creekside Commons, an addition to the City of Rockwall, Rockwall County, Texas according to the plat thereof recorded in Instrument Number 2024000004925 of the Official Public Records of Rockwall County, Texas, and being a part of that tract of land described in Special Warranty Deed to Creekside Commons Crossing, LP recorded in Instrument Number 2022000021201 of the Official Public Records of Rockwall County, Texas, and being more particularly described by metes and bounds as follows:

Commencing at a 1/2 inch iron rod with yellow plastic cap stamped "TXHS" found for corner, said corner being in the northeast corner of that tract of land described as Parcel 1 Part 1 in deed to the State of Texas recorded in Instrument Number 2018000021509 of the Official Public Records of Rockwall County, Texas, said corner also being the northwest corner of Lot 17, Block A of said Creekside Commons Addition, said corner also being in the south right-of-way line of existing State Highway 549 (variable width right-of-way);

Thence North 88 degrees 45 minutes 13 seconds East, along the south right-of-way line of said existing State Highway 549, a distance of 491.43 feet to an "X" found for corner, said corner being the northeast corner of said Lot 17, Block A, said corner being the POINT OF BEGINNING;

Thence North 88 degrees 45 minutes 13 seconds East, along the south right-of-way line of said existing State Highway 549, a distance of 1,358.95 feet to a 5/8 inch iron rod with pink plastic cap stamped "TXDOT" found for corner, said corner being the northwest corner of that tract of land described as Parcel 1 Part 2 in deed to the State of Texas recorded in Instrument Number 2018000021509 of the Official Public Records of Rockwall County, Texas, said corner also being the most northerly northeast corner of said Lot 18, Block A, said corner also being in a northwest right-of-way line of new State Highway 549 (variable width right-of-way);

Thence, along the northwest line of said State of Texas Parcel 1 Part 2 tract and along the northwest line of said new State Highway 549, the following courses and distances:

Thence South 33 degrees 19 minutes 17 seconds East, a distance of 114.68 feet to a 1/2 inch iron rod with yellow plastic cap stamped "TXHS" found for corner, said corner being the beginning of a non-tangent curve to the right, having a delta of 04 degrees 03 minutes 19 seconds, a radius of 1,155.00 feet and a chord bearing and distance of South 58 degrees 43 minutes 21 seconds West, 81.73 feet;

Thence, in a southwesterly direction, along said curve to the right, an arc length of 81.75 feet to a 5/8 inch iron rod with pink plastic cap stamped "TXDOT" found for corner;

Thence South 60 degrees 46 minutes 14 seconds West, a distance of 382.65 feet to a 1/2 inch iron rod with yellow plastic cap stamped "TXHS" found for corner;

Thence South 29 degrees 29 minutes 58 seconds East, a distance of 25.09 feet to a 1/2 inch iron rod with yellow plastic cap stamped "TXHS" found for corner;

Thence South 60 degrees 45 minutes 08 seconds West, a distance of 437.07 feet to a "X" found for corner, said corner being the beginning of a non-tangent curve to the left, having a delta of 08 degrees 16 minutes 36 seconds, a radius of 1,110.00 feet and a chord bearing and distance of South 56 degrees 38 minutes 44 seconds West, 160.20 feet;

Thence, in a southwesterly direction, along said curve to the left, an arc length of 160.34 feet to a 1/2 inch iron rod with yellow plastic cap stamped "TXHS" found for corner, said corner being the east corner of Lot 1, Block A of said Creekside Commons, an addition to the City of Rockwall, Rockwall County, Texas according to the plat thereof recorded in Instrument Number 2023000008813 of the Official Public Records of Rockwall County, Texas;

Thence North 45 degrees 53 minutes 13 seconds West, along the northeast line of said Lot 1, Block A, a distance of 261.06 feet to an "X" found for corner, said corner being the north corner of said Lot 1, Block A, said corner also being the east corner of Lot 14, Block A of said Creekside Commons Addition (Inst. No. 2024000004925);

Thence North 45 degrees 51 minutes 55 seconds West, along the northeast line of said Lot 14, Block A, a distance of 202.16 feet to an "X" found for corner, said corner being the north corner of said Lot 14, Block A;


Thence South 44 degrees 06 minutes 48 seconds West, along the northwest line of said Lot 14, Block A, a distance of 269.61 feet to a 1/2 inch iron rod with cap stamped "SUMMIT" found for corner, said corner being the west corner of said Lot 14, Block A, said corner also being in the northeast line of said State of Texas Parcel 1 Part 1 tract;

Thence North 45 degrees 52 minutes 18 seconds West, along a northeast line of said State of Texas Parcel 1 Part 1 tract, a distance of 228.23 feet to a 1/2 inch iron rod with yellow plastic cap stamped "TXHS" found for corner, said corner being the south corner of said Lot 17, Block A;

Thence North 44 degrees 08 minutes 20 seconds East, along the southeast line of said Lot 17, Block A, a distance of 269.64 feet to an "X" found for corner, said corner being the east corner of said Lot 17, Block A;

Thence North 45 degrees 51 minutes 55 seconds West, along the easterly line of said Lot 17, Block A, a distance of 22.85 feet to an "X" found for corner;

Thence North 01 degrees 07 minutes 51 seconds West, along the easterly line of said Lot 17, Block A, a distance of 121.80 feet to the POINT OF BEGINNING and containing 578,731 square feet or 13.286 acres of land.



OWNER'S DEDICATION:

NOW THEREFORE, KNOW ALL MEN BY THESE PRESENTS:

STATE OF TEXAS
COUNTY OF ROCKWALL

I the undersigned owner of the land shown on this plat, and designated herein as the CREEKSIDE COMMONS ADDITION subdivision to the City of Rockwall, Texas, and whose name is subscribed hereto, hereby dedicate to the use of the public forever all streets, alleys, parks, water courses, drains, easements and public places thereon shown on the purpose and consideration therein expressed. I further certify that all other parties who have a mortgage or lien interest in the CREEKSIDE COMMONS ADDITION subdivision have been notified and signed this plat. I understand and do hereby reserve the easement strips shown on this plat for the purposes stated and for the mutual use and accommodation of all utilities desiring to use or using same. I also understand the following;

1. No buildings shall be constructed or placed upon, over, or across the utility easements as described herein.
2. Any public utility shall have the right to remove and keep removed all or part of any buildings, fences, trees, shrubs, or other growths or improvements which in any way endanger or interfere with construction, maintenance or efficiency of their respective system on any of these easement strips; and any public utility shall at all times have the right of ingress or egress to, from and upon the said easement strips for purposes of construction, reconstruction, inspecting, patrolling, maintaining, and either adding to or removing all or part of their respective system without the necessity of, at any time, procuring the permission of anyone.
3. The City of Rockwall will not be responsible for any claims of any nature resulting from or occasioned by the establishment of grade of streets in the subdivision.
4. The developer/property owner and subdivision engineer shall bear total responsibility for storm drain improvements.
5. The developer/property owner shall be responsible for the necessary facilities to provide drainage patterns and drainage controls such that properties within the drainage area are not adversely affected by storm drainage from the development.
6. No house dwelling unit, or other structure shall be constructed on any lot in this addition by the owner or any other person until the developer and/or owner has complied with all requirements of the Subdivision Regulations of the City of Rockwall regarding improvements with respect to the entire block on the street or streets on which property abuts, including the actual installation of streets with the required base and paving, curb and gutter, water and sewer, drainage structures, storm structures, storm sewers, and alleys, all according to the specifications of the City of Rockwall; or

Until an escrow deposit, sufficient to pay for the cost of such improvements, as determined by the city's engineer and/or city administrator, computed on a private commercial rate basis, has been made with the city secretary, accompanied by an agreement signed by the developer and/or owner, authorizing the city to make such improvements at prevailing private commercial rates, or have the same made by a contractor and pay for the same out of the escrow deposit, should the developer and/or owner fail or refuse to install the required improvements within the time stated in such written agreement, but in no case shall the City be obligated to make such improvements itself. Such deposit may be used by the owner and/or developer as progress payments as the work progresses in making such improvements by making certified requisitions to the city secretary, supported by evidence of work done; or

Until the developer and/or owner files a corporate surety bond with the city secretary in a sum equal to the cost of such improvements for the designated area, guaranteeing the installation thereof within the time stated in the bond, which time shall be fixed by the city council of the City of Rockwall.

I further acknowledge that the dedications and/or exaction's made herein are proportional to the impact of the Subdivision upon the public services required in order that the development will comport with the present and future growth needs of the City; I, my successors and assigns hereby waive any claim, damage or cause of action that I may have as a result of the dedication of exactions made herein.

Creekside Commons Crossing, LP

Jassem Setayesh
President/CEO

STATE OF TEXAS
COUNTY OF DALLAS

BEFORE ME, the undersigned authority, on this day personally appeared Jassem Setayesh, a Texas limited liability company, known to me to be the person whose name is subscribed to the foregoing instrument, and acknowledged to me that he executed the same for the purposes and considerations therein stated.

GIVEN UNDER MY HAND AND SEAL OF OFFICE, this _____ day of _____, 2026.

Notary Signature

SURVEYORS CERTIFICATE:

I, J. R. January, do hereby certify that I prepared this plat from an actual and accurate survey of the land, and that the corner monuments shown thereon were properly placed under my personal supervision.

J. R. January, R.P.L.S. No. 5382

APPROVED: I hereby certify that the above and foregoing Subdivision Plat was reviewed by the Planning and Zoning Commission and approved by the City Council of the City of Rockwall, Texas for the preparation of a Final Plat on the _____ day of _____, 2026.

Mayor of the City of Rockwall

Planning and Zoning Chairman

City Secretary

City Engineer

ENGINEER
THE DIMENSION GROUP
10755 SANDHILL ROAD
DALLAS, TEXAS 75238
attn: KEATON MAI

OWNER
CREEKSIDE COMMONS CROSSING, LP
10755 SANDHILL ROAD
DALLAS, TEXAS 75238



SURVEYOR
TEXAS HERITAGE
SURVEYING, LLC
10610 Metric Drive, Suite 124, Dallas, TX 75243
Office 214-340-9700 Fax 214-340-9710
txheritage.com
Firm No. 10169300

FINAL PLAT
LOTS 19-21, BLOCK A
CREEKSIDE COMMONS ADDITION
BEING A REPLAT OF
LOTS 15, 16, & 18, BLOCK A,
CREEKSIDE COMMONS ADDITION
BEING 3 LOTS
13.286 ACRES / 578,731 SF
SITUATED IN THE
W. W. FORD SURVEY, ABSTRACT NO. 80
CITY OF ROCKWALL, ROCKWALL COUNTY, TEXAS



DATE: March 24, 2026

TO: Keaton Mai
The Dimension Group
10755 Sandhill Road
Dallas, Texas 75238

CC: Michael Hampton
Creekside Commons Crossing LP
10755 Sandhill Road
Dallas, TX 75238

FROM: Henry Lee, AICP
City of Rockwall Planning and Zoning Department
385 S. Goliad Street
Rockwall, TX 75087

SUBJECT: P2026-004; Replat for Lots 19-21, Block A, Creekside Commons Addition

Keaton Mai:

This letter serves to notify you that the above referenced platting case, that you submitted for consideration by the City of Rockwall, was approved by the City Council on February 2, 2026. The following is a record of all recommendations, voting records and conditions of approval:

Conditions of Approval

- 1) All technical comments from the Engineering, Planning and Fire Departments shall be addressed prior to the filing of this plat; and,
- 2) Any construction resulting from the approval of this Replat shall conform to the requirements set forth by the Unified Development Code (UDC), the International Building Code (IBC), the Rockwall Municipal Code of Ordinances, city adopted engineering and fire codes and with all other applicable regulatory requirements administered and/or enforced by the state and federal government.

Planning and Zoning Commission

On January 27, 2026, the Planning and Zoning Commission approved a motion to recommend approval of the replat by a vote of 5-0, with Commissioners Conway and Brock absent.

City Council

On February 2, 2026, the City Council approved a motion to approve the Replat by a vote of 6-0, with Council Member Moeller absent.

Prior to submitting the required materials for filing, please send or submit a physical or digital copy of the plat to allow staff to ensure that all outstanding comments have been addressed. Once staff has verified all comments have been addressed you will be required to submit -- *at a minimum* -- the following:

- (1) One (1) set(s) of mylar copies of the plat.
- (2) One (1) tax certificate for each property being platted that demonstrates that the current years taxes have been paid.
- (3) A check for the filing fees (see below) made out to the *Rockwall County Clerk's Office*.

FILING FEES:

Mylars: \$49.00 per page for the 1st set only (*No charge for additional sets*).

Tax Certificates: \$29.00 for the 1st certificate and \$4.00 for each additional certificate.

Please note that the filling fee amount above is only an estimate and that filing fees are subject to change based on the requirements of the *Rockwall County Clerk's Office*.

All plats must be submitted to the City with the required filing fees and tax certificates within a 180-days of the approval date. Failure to adhere to this deadline, will result in the plat being expired in accordance with the requirements of Chapter 38, *Subdivisions*, of the Municipal Code of Ordinances. Should you have any questions or concerns regarding your plat or the platting process, please feel free to contact me a (972) 771-6434.

Please note that after plats have been filed, the applicant/owner has 30 days to pick up any requested certified copies at City Hall. After 30 days, the requested copies will be discarded by staff.

Sincerely,



Henry Lee, AICP, *Senior Planner*
City of Rockwall Planning and Zoning Department