



# DEVELOPMENT APPLICATION

City of Rockwall  
Planning and Zoning Department  
385 S. Goliad Street  
Rockwall, Texas 75087

STAFF USE ONLY  
PLANNING & ZONING CASE NO.

**NOTE:** THE APPLICATION IS NOT CONSIDERED ACCEPTED BY THE CITY UNTIL THE PLANNING DIRECTOR AND CITY ENGINEER HAVE SIGNED BELOW.

DIRECTOR OF PLANNING:

CITY ENGINEER:

PLEASE CHECK THE APPROPRIATE BOX BELOW TO INDICATE THE TYPE OF DEVELOPMENT REQUEST [SELECT ONLY ONE BOX]:

## PLATTING APPLICATION FEES:

- ☐ MASTER PLAT (\$100.00 + \$15.00 ACRE)<sup>1</sup>  
☐ PRELIMINARY PLAT (\$200.00 + \$15.00 ACRE)<sup>1</sup>  
☒ FINAL PLAT (\$300.00 + \$20.00 ACRE)<sup>1</sup>  
☐ REPLAT (\$300.00 + \$20.00 ACRE)<sup>1</sup>  
☐ AMENDING OR MINOR PLAT (\$150.00)  
☐ PLAT REINSTATEMENT REQUEST (\$100.00)

## SITE PLAN APPLICATION FEES:

- ☐ SITE PLAN (\$250.00 + \$20.00 ACRE)<sup>1</sup>  
☐ AMENDED SITE PLAN/ELEVATIONS/LANDSCAPING PLAN (\$100.00)

## ZONING APPLICATION FEES:

- ☐ ZONING CHANGE (\$200.00 + \$15.00 ACRE)<sup>1</sup>  
☐ SPECIFIC USE PERMIT (\$200.00 + \$15.00 ACRE)<sup>1 & 2</sup>  
☐ PD DEVELOPMENT PLANS (\$200.00 + \$15.00 ACRE)<sup>1</sup>

## OTHER APPLICATION FEES:

- ☐ TREE REMOVAL (\$75.00)  
☐ VARIANCE REQUEST/SPECIAL EXCEPTIONS (\$100.00)<sup>2</sup>

## NOTES:

<sup>1</sup>: IN DETERMINING THE FEE, PLEASE USE THE EXACT ACREAGE WHEN MULTIPLYING BY THE PER ACRE AMOUNT. FOR REQUESTS ON LESS THAN ONE ACRE, ROUND UP TO ONE (1) ACRE.  
<sup>2</sup>: A \$1,000.00 FEE WILL BE ADDED TO THE APPLICATION FEE FOR ANY REQUEST THAT INVOLVES CONSTRUCTION WITHOUT OR NOT IN COMPLIANCE TO AN APPROVED BUILDING PERMIT.

## PROPERTY INFORMATION [PLEASE PRINT]

ADDRESS 4156 North Goliad St, Rockwall, Texas 75087

SUBDIVISION Goliad Street Addition

LOT 1 BLOCK 1

GENERAL LOCATION East side of N. Goliad St and South of John King Blvd. The site is directly adjacent to the Rockwall Hills Equestrian Center.

## ZONING, SITE PLAN AND PLATTING INFORMATION [PLEASE PRINT]

CURRENT ZONING ETJ

CURRENT USE Vacant Land

PROPOSED ZONING N/A - to remain in ETJ

PROPOSED USE Flex Business Park / Office / Warehouse

ACREAGE 4.998

LOTS [CURRENT] 2

LOTS [PROPOSED] 1

☒ **SITE PLANS AND PLATS:** BY CHECKING THIS BOX YOU ACKNOWLEDGE THAT DUE TO THE PASSAGE OF HB3167 THE CITY NO LONGER HAS FLEXIBILITY WITH REGARD TO ITS APPROVAL PROCESS, AND FAILURE TO ADDRESS ANY OF STAFF'S COMMENTS BY THE DATE PROVIDED ON THE DEVELOPMENT CALENDAR WILL RESULT IN THE DENIAL OF YOUR CASE.

## OWNER/APPLICANT/AGENT INFORMATION [PLEASE PRINT/CHECK THE PRIMARY CONTACT/ORIGINAL SIGNATURES ARE REQUIRED]

☐ OWNER Tachtical Investment Group LLC

☒ APPLICANT Gardner Construction

CONTACT PERSON Khalid Motorwala

CONTACT PERSON James Martin

ADDRESS 2224 Courtland Dr

ADDRESS 15950 State Hwy 205

CITY, STATE & ZIP Frisco, Texas 75034

CITY, STATE & ZIP Terrell, Texas 75160

PHONE

PHONE

E-MAIL

E-MAIL

## NOTARY VERIFICATION [REQUIRED]


BEFORE ME, THE UNDERSIGNED AUTHORITY, ON THIS DAY PERSONALLY APPEARED James Martin [OWNER] THE UNDERSIGNED, WHO STATED THE INFORMATION ON THIS APPLICATION TO BE TRUE AND CERTIFIED THE FOLLOWING:

"I HEREBY CERTIFY THAT I AM THE OWNER FOR THE PURPOSE OF THIS APPLICATION; ALL INFORMATION SUBMITTED HEREIN IS TRUE AND CORRECT; AND THE APPLICATION FEE OF \$ 400.00 TO COVER THE COST OF THIS APPLICATION, HAS BEEN PAID TO THE CITY OF ROCKWALL ON THIS THE June DAY OF 13, 2025 BY SIGNING THIS APPLICATION, I AGREE THAT THE CITY OF ROCKWALL (I.E. "CITY") IS AUTHORIZED AND PERMITTED TO PROVIDE INFORMATION CONTAINED WITHIN THIS APPLICATION TO THE PUBLIC. THE CITY IS ALSO AUTHORIZED AND PERMITTED TO REPRODUCE ANY COPYRIGHTED INFORMATION SUBMITTED IN CONJUNCTION WITH THIS APPLICATION, IF SUCH REPRODUCTION IS ASSOCIATED OR IN RESPONSE TO A REQUEST FOR PUBLIC INFORMATION."

GIVEN UNDER MY HAND AND SEAL OF OFFICE ON THIS THE 13 DAY OF June, 2025


OWNER'S SIGNATURE

NOTARY PUBLIC IN AND FOR THE STATE OF TEXAS



MY COMMISSION EXPIRES







## City of Rockwall

Planning & Zoning Department  
385 S. Goliad Street  
Rockwall, Texas 75087  
(P): (972) 771-7745  
(W): [www.rockwall.com](http://www.rockwall.com)

The City of Rockwall GIS maps are continually under development and therefore subject to change without notice. While we endeavor to provide timely and accurate information, we make no guarantees. The City of Rockwall makes no warranty, express or implied, including warranties of merchantability and fitness for a particular purpose. Use of the information is the sole responsibility of the user.








NOT TO SCALE

GENERAL NOTES

1. The Basis of Bearings is from the Texas State Plane Coordinate System, NAD83, North Central Zone is derived from GPS Observations using the Allterra RTK Network and adjusted to surface using a scale factor of 1.000146135.
2. Notice: Selling a portion of this addition by metes and bounds is a violation of City subdivision ordinance and state platting statutes and is subject to fines and withholding of utilities and building certificates.
3. The purpose of this plat is to create one recorded lot out of a tract of land.

FLOOD NOTES

No portion of the subject property shown hereon lies within the 100 year flood hazard area according to the Flood Insurance Rate Map, Community Panel No. 48397C0030L, dated September 26, 2008. The subject property is located in the area designated as Zone "X", (areas determined to be outside the 0.2% annual chance floodplain).



SHENNENDOAH REAL ESTATE PARTNERS, LP  
VOL. 3351, PG. 114  
D.R.R.C.T.

Curve Data Table					
Curve #	Arc	Radius	Delta	Chord Bearing	Chord
C1	35.26'	15.07'	134°05'34"	N07°43'03"E	27.75'
C2	39.85'	523.62'	004°21'39"	N76°56'40"E	39.84'
C3	44.59'	93.53'	027°19'01"	S87°13'00"E	44.17'
C4	16.30'	480.79'	001°56'34"	S74°31'47"E	16.30'
C5	8.81'	14.41'	035°01'24"	S57°59'22"E	8.67'
C6	26.29'	116.17'	012°58'07"	S33°59'36"E	26.24'
C7	22.75'	16.02'	081°24'15"	S43°50'03"E	20.89'

FINAL PLAT  
LOT 1, BLOCK 1  
GOLIAD STREET  
ADDITION

BEING 4.998 ACRES  
OUT OF THE JOSEPH STRICKLAND SURVEY  
ABSTRACT NUMBER 187  
CITY OF ROCKWALL ETJ,  
ROCKWALL COUNTY, TEXAS  
JUNE 2025



359 Lake Park Road, Suite 102, Lewisville, Texas 75057 T: 469.784.9321  
W: TraverseLandSurveying.com | Texas Firm No. 10194631

Surveying | Construction Staking | Platting

Date: 2025.06.11

Project No.: TR-337-25

ENGINEER  
Civil Point Engineering  
5900 South Lake Forest Drive, Suite 300  
McKinney, Texas 75070

OWNER/DEVELOPER  
Jeff Swafford  
4078 N. Goliad Street  
Rockwall, Texas 75087

STATE OF TEXAS  
COUNTY OF ROCKWALL

WHEREAS Jeff Swafford is the owner of a 4.998 acre tract of land within the Joseph Strickland Survey, Abstract Number 187, Rockwall County, Texas and being all of a tract of land described to Jeff Swafford by deed recorded in Instrument Number 2020000012120, Instrument Number 20200000012121, Official Public Records, Rockwall County, Texas and being corrected in Instrument Number 2023000006362, Official Public Records, Rockwall County, Texas and being more particularly described by metes and bounds as follows:

BEGINNING at a 1/2 inch rebar found for the northwest corner of a tract of land described to Lavenda Bogue Swafford and Thomas Swafford by deed recorded in Volume 4363, Page 5, Deed Records, Rockwall County, Texas and lying on the east right-of-way line of North Goliad Street (Variable Width right-of-way);

THENCE North 07 degrees 25 minutes 58 seconds West, with the east right-of-way line of said North Goliad Street, a distance of 54.18 feet to a 1/2 inch rebar found for corner;

THENCE North 03 degrees 03 minutes 15 seconds East, with the east right-of-way line of said North Goliad Street, a distance of 67.25 feet to an "X" Cut found for the southwestern most corner of a tract of land described to Daniel Marion Ash and Wife, Alice A Ash by deed recorded in Volume 842, Page 161, Deed Records, Rockwall County, Texas;

THENCE North 32 degrees 41 minutes 09 seconds East, departing the east right-of-way line of said North Goliad Street, with the south line of said Ash tract, a distance of 140.23 feet to a 1/2 inch rebar capped "BURNS" found for corner;

THENCE North 82 degrees 56 minutes 01 seconds East, with a south line of said Ash tract, a distance of 213.77 feet to a 1/2 inch rebar found for corner;

THENCE South 86 degrees 50 minutes 47 seconds East, with the south line of said Ash tract, continuing with the south line of a tract of land described to Joe J. Katin by deed recorded in Instrument Number 20150000020492, Official Public Records, Rockwall County, Texas, a total distance of 222.53 feet to a 1/2 inch rebar found for corner;

THENCE North 87 degrees 17 minutes 05 seconds East, with the south line of said Katin tract, a distance of 377.02 feet to a 1/2 inch rebar found for the southeast corner of said Katin tract, same being a point on the west line of a tract of land described to Shennendoah Real Estate Partners, LP by deed recorded in Volume 3351, Page 114, Deed Records, Rockwall County, Texas;

THENCE South 00 degrees 41 minutes 17 seconds East, with a west line of said Shennendoah tract, a distance of 256.95 feet to a 1/2 inch rebar found for the northeast corner of said Lavenda and Thomas tract;

THENCE South 89 degrees 06 minutes 09 seconds West, departing the west line of said Shennendoah tract, with the north line of said Lavenda and Thomas tract, a distance of 886.44 feet to THE POINT OF BEGINNING and containing 217,697 square feet or 4.998 acres of land, more or less.

NOW, THEREFORE, KNOW ALL MEN BY THESE PRESENTS

THAT we Jeff Swafford do hereby adopt this plat designating the hereinabove described property as Goliad Street Addition, an addition to the City of Rockwall, and do hereby dedicate to the public use forever the streets and alleys shown thereon and do hereby reserve the easement strips shown on this plat for the mutual use and accommodation of garbage collection agencies and all public utilities desiring to use or using same. Any public utility shall have the right to remove and keep removed all or part of any buildings, fences, trees, shrubs or other improvements or growths which in any way endanger or interfere with the construction, maintenance or efficiency of its respective systems on any of these easement strips and any public utility shall at all times have the right to remove and keep removed all or part of any buildings, fences, trees, shrubs, or other improvements or growths which in any way endanger or interfere with the constructions, maintenance or efficiency of its respective systems on any of these easement strips and any public utility shall at all times have the right of ingress and egress to and from and upon the said easement strip for the purpose of constructing, reconstructing, inspecting, and patrolling without the necessity at any time of procuring the permission of anyone. This plat approved subject to the platting ordinances, rules, regulations and resolutions of the City of Rockwall, Texas.

We further understand the following:

1. No building shall be constructed or placed upon, over, or across the utility easements as described herein.
2. Any public utility shall have the right to remove and keep removed all or part of any buildings, fences, trees, shrubs or other growths or improvements which in any way endanger or interfere with construction, reconstruction, inspecting, patrolling, maintaining, and either adding to or removing all or part of their respective system without the necessity of, at any time, procuring the permission of anyone.
3. The City of Rockwall will not be responsible for any claims of any nature resulting from or occasioned by the establishment of grade of streets or improvements.
4. The developer/property owner and subdivision engineer shall bear total responsibility for storm drain improvements.
5. The developer/property owner shall be responsible for the necessary facilities and maintenance to provided drainage patterns and drainage controls such that properties within the drainage area are not adversely affected by storm drainage from the development.
6. No house, dwelling, unit or other structure shall be constructed on any lot in the addition by the owner or any other person until the developer and/or owner has complied with all requirements of the Subdivision Regulations of the City of Rockwall regarding improvements with respect to the entire block on the street or streets on which property abuts, including the actual installation of streets with required base and paving, curb and gutter, water and sewer, drainage structures, storm structures and storm sewers all according to the specifications of the City of Rockwall.

Witness, my hand at \_\_\_\_\_, \_\_\_\_\_, This \_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_.

Signature – Jeff Swafford Representative

Printed Name

Title / Date

STATE OF TEXAS §

COUNTY OF \_\_\_\_\_ §

BEFORE ME, the undersigned authority, a Notary Public in and for the State of Texas, on this day personally appeared\_\_\_\_\_, known to me to be the person whose name is subscribed to the foregoing instrument and acknowledged to me that she executed the same for the purposes and consideration therein expressed.

GIVEN UNDER MY HAND AND SEAL OF OFFICE this \_\_\_\_\_day of \_\_\_\_\_ 20\_\_\_\_\_.

Notary Public in and for the State of Texas

SURVEYOR’S CERTIFICATION

KNOW ALL MEN BY THESE PRESENTS:

That I, David F. McCullah, do hereby certify that I prepared this plat from an actual and accurate survey of the land and that the corner monuments shown thereon as set were properly placed under my personal supervision.

David F. McCullah  
REGISTERED PROFESSIONAL LAND SURVEYOR  
TEXAS REGISTRATION NO. 4023

DATE: \_\_\_\_\_

STATE OF TEXAS §  
COUNTY OF DENTON §

BEFORE ME, the undersigned authority, a notary public in and for the State of Texas, on this day personally appeared David F. McCullah, known to me to be the person whose name is subscribed to the foregoing instrument and acknowledged to me that he executed the same in the capacity therein stated.

Given under my hand and seal of office this \_\_\_\_ day of \_\_\_\_\_, 202\_\_

Notary Public in and for the State of Texas

CERTIFICATE OF APPROVAL:
Approved:
I hereby certify that the above and foregoing subdivision plat, being an addition to the City of Rockwall, Texas, was approved by City Council on the City of Rockwall, Texas, on the _____ day of _____, 20_____.
_____ Mayor, City of Rockwall
_____ Director of Planning and Zoning
_____ Planning and Zoning Commission Charirman
_____ City Engineer
_____ City Secretary

ENGINEER  
Civil Point Engineering  
5900 South Lake Forest Drive, Suite 300  
McKinney, Texas 75070

OWNER/DEVELOPER  
Jeff Swafford  
4078 N. Goliad Street  
Rockwall, Texas 75087



359 Lake Park Road, Suite 102, Lewisville, Texas 75057 T: 469.784.9321  
W: TraverseLandSurveying.com | Texas Firm No. 10194631

Surveying | Construction Staking | Platting

Date: 2025.06.11 Project No.: TR-337-25

FINAL PLAT  
LOT 1, BLOCK 1  
GOLIAD STREET  
ADDITION  
BEING 4.998 ACRES  
OUT OF THE JOSEPH STRICKLAND SURVEY  
ABSTRACT NUMBER 187  
CITY OF ROCKWALL ETJ,  
ROCKWALL COUNTY, TEXAS  
JUNE 2025

2 of 2