



DEVELOPMENT APPLICATION

City of Rockwall
Planning and Zoning Department
385 S. Goliad Street
Rockwall, Texas 75087

STAFF USE ONLY
PLANNING & ZONING CASE NO.

NOTE: THE APPLICATION IS NOT CONSIDERED ACCEPTED BY THE CITY UNTIL THE PLANNING DIRECTOR AND CITY ENGINEER HAVE SIGNED BELOW

DIRECTOR OF PLANNING:

CITY ENGINEER:

PLEASE CHECK THE APPROPRIATE BOX BELOW TO INDICATE THE TYPE OF DEVELOPMENT REQUEST [SELECT ONLY ONE BOX]

PLATTING APPLICATION FEES:

- ☐ MASTER PLAT (\$100.00 + \$15.00 ACRE)¹
- ☐ PRELIMINARY PLAT (\$200.00 + \$15.00 ACRE)¹
- ☐ FINAL PLAT (\$300.00 + \$20.00 ACRE)¹
- ☐ REPLAT (\$300.00 + \$20.00 ACRE)¹
- ☐ AMENDING OR MINOR PLAT (\$150.00)
- ☐ PLAT REINSTATEMENT REQUEST (\$100.00)

SITE PLAN APPLICATION FEES:

- ☐ SITE PLAN (\$250.00 + \$20.00 ACRE)¹
- ☒ AMENDED SITE PLAN/ELEVATIONS/LANDSCAPING PLAN (\$100.00)

ZONING APPLICATION FEES:

- ☐ ZONING CHANGE (\$200.00 + \$15.00 ACRE)¹
- ☐ SPECIFIC USE PERMIT (\$200.00 + \$15.00 ACRE)^{1, 2}
- ☐ PD DEVELOPMENT PLANS (\$200.00 + \$15.00 ACRE)¹

OTHER APPLICATION FEES:

- ☐ TREE REMOVAL (\$75.00)
- ☐ VARIANCE REQUEST/SPECIAL EXCEPTIONS (\$100.00)²

NOTES:

¹ IN DETERMINING THE FEE, PLEASE USE THE EXACT ACREAGE WHEN MULTIPLYING BY THE PER ACRE AMOUNT. FOR REQUESTS ON LESS THAN ONE ACRE, ROUND UP TO ONE (1) ACRE.

² A \$1,000.00 FEE WILL BE ADDED TO THE APPLICATION FEE FOR ANY REQUEST THAT INVOLVES CONSTRUCTION WITHOUT OR NOT IN COMPLIANCE TO AN APPROVED BUILDING PERMIT.

PROPERTY INFORMATION [PLEASE PRINT]

ADDRESS 2651 Sunset Ridge Drive, Rockwall, TX 75032

SUBDIVISION Harbor District

LOT 7 BLOCK A

GENERAL LOCATION Interstate 30 and Sunset Ridge Drive

ZONING, SITE PLAN AND PLATTING INFORMATION [PLEASE PRINT]

CURRENT ZONING PD-32

CURRENT USE N/A

PROPOSED ZONING PD-32

PROPOSED USE Restaurant

ACREAGE 0.9

LOTS [CURRENT]

1

LOTS [PROPOSED]

1

- ☐ **SITE PLANS AND PLATS:** BY CHECKING THIS BOX YOU ACKNOWLEDGE THAT DUE TO THE PASSAGE OF HB3167 THE CITY NO LONGER HAS FLEXIBILITY WITH REGARD TO ITS APPROVAL PROCESS, AND FAILURE TO ADDRESS ANY OF STAFF'S COMMENTS BY THE DATE PROVIDED ON THE DEVELOPMENT CALENDAR WILL RESULT IN THE DENIAL OF YOUR CASE.

OWNER/APPLICANT/AGENT INFORMATION [PLEASE PRINT/CHECK THE PRIMARY CONTACT/ORIGINAL SIGNATURES ARE REQUIRED]

☐ OWNER

CONTACT PERSON Elias Pope

ADDRESS 2010 Greenville Ave
Suite D

CITY, STATE & ZIP Dallas, TX 75206

PHONE 732-887-9699

E-MAIL elias@unco.com

☒ APPLICANT

CONTACT PERSON

ADDRESS

CITY, STATE & ZIP

PHONE

E-MAIL

Teague, Nall and Perkins, Inc.

Cameron Slown

825 Watters Creek Blvd.

Suite M300

Allen, TX 75013

817-889-5050

cslow@tnpinc.com

NOTARY VERIFICATION [REQUIRED]

BEFORE ME, THE UNDERSIGNED AUTHORITY, ON THIS DAY PERSONALLY APPEARED Elias Pope [OWNER] THE UNDERSIGNED, WHO STATED THE INFORMATION ON THIS APPLICATION TO BE TRUE AND CERTIFIED THE FOLLOWING:


I HEREBY CERTIFY THAT I AM THE OWNER FOR THE PURPOSE OF THIS APPLICATION. ALL INFORMATION SUBMITTED HEREIN IS TRUE AND CORRECT, AND THE APPLICATION FEE OF \$20 TO COVER THE COST OF THIS APPLICATION, HAS BEEN PAID TO THE CITY OF ROCKWALL ON THIS THE 15 DAY OF 05 2023. BY SIGNING THIS APPLICATION, I AGREE THAT THE CITY OF ROCKWALL (I.E. "CITY") IS AUTHORIZED AND PERMITTED TO PROVIDE INFORMATION CONTAINED WITHIN THIS APPLICATION TO THE PUBLIC. THE CITY IS ALSO AUTHORIZED AND PERMITTED TO REPRODUCE ANY COPYRIGHTED INFORMATION SUBMITTED IN CONJUNCTION WITH THIS APPLICATION, IF SUCH REPRODUCTION IS ASSOCIATED OR IN RESPONSE TO A REQUEST FOR PUBLIC INFORMATION.


GIVEN UNDER MY HAND AND SEAL OF OFFICE ON THIS THE 15 DAY OF 05 2023

OWNER'S SIGNATURE

NOTARY PUBLIC IN AND FOR THE STATE OF TEXAS

[Signature]
Notary Public





SP2025-020: Amended Site Plan for HG Supply & Co.

Case Location Map = 





City of Rockwall

Planning & Zoning Department
385 S. Goliad Street
Rockwall, Texas 75087
(P): (972) 771-7745
(W): www.rockwall.com


The City of Rockwall GIS maps are continually under development and therefore subject to change without notice. While we endeavor to provide timely and accurate information, we make no guarantees. The City of Rockwall makes no warranty, express or implied, including warranties of merchantability and fitness for a particular purpose. Use of the information is the sole responsibility of the user.




Drawing: P:\00_FCCony\Projects\6-Commercial\Harbor District - HG Supply\1-DRAWINGS\1F-DESIGN-CURRENT\04 - HG SUPPLY - SITE PLAN.dwg at May 16, 2025--7:39am by cslwn
LAYOUT: C1.04 SITE PLAN Xrefs: HG SUPPLY-BASE.dwg - XREF-BORDER.dwg




- 8"-4,000 PSI CONCRETE PAVEMENT WITH NO. 4 BARS 18" ON CENTER BOTH WAYS. (6.5 SACK MIX MIN.)
- 8" COMPACTED LIME STABILIZED SUBGRADE. SCARIFY 8" DEEP AND COMPACT TO A STANDARD PROCTOR MAXIMUM DRY DENSITY NOT LESS THAN 95% AND WITHIN 2% BELOW AND 5% ABOVE OPTIMUM MOISTURE CONTENT. NO SAND ALLOWED. ALL GENERAL FILL TO BE COMPACTED WITH A SHEEP'S FOOT ROLLER.





- 6"-4,000 PSI CONCRETE PAVEMENT WITH NO. 3 BARS 24" ON CENTER BOTH WAYS. (6.5 SACK MIX MIN.)
- 8" COMPACTED LIME STABILIZED SUBGRADE. SCARIFY 8" DEEP AND COMPACT TO A STANDARD PROCTOR MAXIMUM DRY DENSITY NOT LESS THAN 95% AND WITHIN 2% BELOW AND 5% ABOVE OPTIMUM MOISTURE CONTENT. NO SAND ALLOWED. ALL GENERAL FILL TO BE COMPACTED WITH A SHEEP'S FOOT ROLLER.



- 5"-3,600 PSI CONCRETE PAVEMENT WITH NO. 3 BARS 24" ON CENTER BOTH WAYS. (6.5 SACK MIX MIN.)
- 8" COMPACTED LIME STABILIZED SUBGRADE. SCARIFY 8" DEEP AND COMPACT TO A STANDARD PROCTOR MAXIMUM DRY DENSITY NOT LESS THAN 95% AND WITHIN 2% BELOW AND 5% ABOVE OPTIMUM MOISTURE CONTENT. NO SAND ALLOWED. ALL GENERAL FILL TO BE COMPACTED WITH A SHEEP'S FOOT ROLLER.



- 4"-3,000 PSI CONCRETE PAVEMENT WITH NO. 3 BARS 24" ON CENTER BOTH WAYS. EXPANSION JOINTS TO BE PROVIDED EVERY 40'. 1" DEEP SAW JOINTS TO BE CUT INTO SIDEWALK EVERY 5'. (5.5 SACK MIX MIN.)
- 8" COMPACTED LIME STABILIZED SUBGRADE. SCARIFY 8" DEEP AND COMPACT TO A STANDARD PROCTOR MAXIMUM DRY DENSITY NOT LESS THAN 95% AND WITHIN 2% BELOW AND 5% ABOVE OPTIMUM MOISTURE CONTENT. NO SAND ALLOWED. ALL GENERAL FILL TO BE COMPACTED WITH A SHEEP'S FOOT ROLLER.



LOCATION MAP

NOTE:
- DUMPSTER ENCLOSURE MATERIAL AND FINISH TO MATCH THAT OF THE RESTAURANT EXTERIOR.

SITE INFORMATION

LAND AREA:	0.90 ACRES (39,184 S.F.)
CURRENT ZONING:	PD-32
EXISTING USE:	UNUSED
PROPOSED USE:	RESTAURANT
BUILDING AREA:	6,800 S.F.
BUILDING TO LOT COVERAGE:	6,800/39,184=17.4% -> 17.4%
RESTAURANT SPACE:	11,625 S.F.
BUILDING HEIGHT:	38 FEET
BUILDING REQUIRED PARKING:	116 SPACES (SEE BREAKDOWN BELOW)
BUILDING PARKING PROVIDED:	116 TOTAL (*67 TREND TOWER GARAGE, 49 PARKING LOT) (INCLUDES 3 HANDICAP SPACES)
IMPERVIOUS AREA:	30,505 S.F.
LANDSCAPE AREA REQUIRED:	0 S.F.
LANDSCAPE AREA PROVIDED:	8,679 S.F.

PARKING REQUIREMENT BREAKDOWN:
RESTAURANT SPACE AT 1 SPACE/100 S.F. --> 11,625/100 = 116 SPACES
* TREND TOWER PARKING REQUIREMENT:
OFFICE SPACE AT 1 SPACE/300 S.F. --> 107,129/300 = 357 SPACES
TREND TOWER PARKING GARAGE CURRENTLY PROVIDES 441 PARKING SPACES SO PER THE SHARED PARKING AGREEMENT, A PORTION OF THIS PARKING MAY BE USED BY LOT 3 BLOCK A, THEREFORE 67 PARKING STALLS FROM THE TREND TOWER PARKING GARAGE WILL BE AVAILABLE FOR USE ON LOT 3 BLOCK A.

APPROVED:
I hereby certify that the above and foregoing site plan for a development in the City of Rockwall, Texas was approved by the Planning and Zoning Commission of the City of Rockwall on the ____ day of ____, 2025.
Witness our hands this ____ day of ____, 2025.

Planning & Zoning Commission, Chairman


Director of Planning & Zoning

CASE NUMBER: SP2025-005

no.	revision	by	date



teague nall and perkins, inc
825 Walters Creek Blvd., Suite M300
Allen, Texas 75013
214.461.9867 ph 214.461.9864 fx
www.tnpinc.com
TBPE: F-230; TBPLS: 10011600, 10011601, 10194381



scale
when bar is
1 inch long
horiz
1"=20'
vert
N/A
May 2025

8020 HOSPITALITY, LLC.
2008 GREENVILLE AVE.
DALLAS, TX 75206

City of RockWall, Texas
Improvements for
HG SPLY, CO. RESTAURANT
SITE PLAN

tnp project
HSP21134
sheet
C1.04






SW7008
Alabaster

Paint Colors

SW 6871
Positive Red

SW 6258
Tricorn Black



NORTH ELEVATION

1

1/8" = 1'-0"

TOTAL BUILDING WALL HARD SURFACE= 2,371 SF
TOTAL BURNISHED BLOCK = 1395 SF=58.8%
TOTAL GLAZED TILE = 539 SF= 22.8%
TOTAL WOOD SCREEN = 335 SF= 14.1%
TOTAL METAL PANELS = NA
TOTAL PTD WALLS = 102 SF= 4.3%

EAST ELEVATION

2

1/8" = 1'-0"

TOTAL ELEVATION WALL HARD SURFACE: 2,292 SF
TOTAL BURNISHED BLOCK: 1,172 SF 51.1%
TOTAL GLAZED TILE: 531.5 SF 23.2%
TOTAL WOOD SCREEN: 465.5 SF 20.3%
TOTAL PTD WALLS: 123 SF 5.4%



WEST ELEVATION

3

1/8" = 1'-0"

TOTAL BUILDING WALL HARD SURFACE: 1557 SF
TOTAL BURNISHED BLOCK: 890 SF 57.2%
TOTAL GLAZED TILE: 231 SF 14.8%
TOTAL WOOD SCREEN: 388 SF 25%
TOTAL METAL PANELS: 48 SF 3%
TOTAL PTD WALLS: - SF

SOUTH ELEVATION

4

1/8" = 1'-0"

TOTAL BUILDING WALL HARD SURFACE: 1,971 SF
TOTAL BURNISHED BLOCK: 955 SF 48.5%
TOTAL GLAZED TILE: 376 SF 19.1%
TOTAL WOOD SCREEN: 459 SF 23.3%
TOTAL METAL PANELS: 129 SF 6.5%
TOTAL PTD WALLS: 52 SF 2.6%

APPROVED:
I hereby certify that the above and foregoing site plan for a development in the City of Rockwall, Texas
was approved by the Planning and Zoning Commission of the City of Rockwall on the ____ day of ____, 2025.
Witness our hands this ____ day of ____, 2025.

Planning & Zoning Commission, Chairman Director of Planning & Zoning

CASE NUMBER: SP2025-005

REVISIONS :

ELEVATIONS

HG SPLY
2651 SUNSET RIDGE DR.
ROCKWALL, TX 75032

P101